

PROFESSIONAL SEALS

PROJECT PARTNERS:

[illegible]

☐ APPROVED FOR CONSTRUCTION
☒ NOT APPROVED FOR CONSTRUCTION

PATIENT INFORMATION:

Wayne State University



WAYNE STATE
UNIVERSITY

5454 CASS AVE
DETROIT, MICHIGAN
48202

CLIENT PROJECT #:	PROJECT NUMBER
HA PROJECT #:	PROJECT NUMBER

PROJECT INFORMATION:

WSU APPLEBAUM
MRI INSTALLATION

259 MACK AVE
DETROIT, MICHIGAN
48201

PROJECT #:	023-03727-00
PROJECT MANAGER:	JEFF FALZON

SSOE®

01 Madison Avenue
ledo, OH 43604
(419) 255-3830

THIS DRAWING IS THE PROPERTY OF SSOE GROUP. UNAUTHORIZED USE OF ANY
INCLUDING USE ON OTHER PROJECTS, IS PROHIBITED.

© SSOE, INC. 2022

OVERALL LEVEL 0 LIFE SAFETY PLAN

GI-300

APPROVED FOR CONSTRUCTION
NOT APPROVED FOR CONSTRUCTION

IENT INFORMATION:

Wayne State University



454 CASS AVE
TROY, MICHIGAN
48064

CLIENT PROJECT #:	PROJECT NUMBER
HA PROJECT #:	PROJECT NUMBER

PROJECT INFORMATION:

WSU APPLEBAUM
MRI INSTALLATION

259 MACK AVE
DETROIT, MICHIGAN
48201

DOE PROJECT #:	023-03727-00
DOE MANAGER:	JEFF FALZON

SSOE®


01 Madison Avenue
ledo, OH 43604
(419) 255-3830

THIS DRAWING IS THE PROPERTY OF SSOE GROUP. UNAUTHORIZED USE OF ANY KIND,
INCLUDING USE ON OTHER PROJECTS, IS PROHIBITED.


OVERALL LEVEL 0 FLOOR PLAN

AE-100







ENLARGED NMR 0250 REFLECTED CEILING PLAN




ENLARGED NMR 0250 NEW WORK PLAN
 SCALE: 1/4" = 1'-0"





ENLARGED NMR 0250 DEMOLITION PLAN
 SCALE: 1/4" = 1'-0"




ENLARGED MRI OFFICE A110 REFLECTED CEILING PLAN

SCALE: 1/4" = 1'-0"




C5 ENLARGED MRI OFFICE A110 NEW WORK PLAN
AE-100 SCALE: 1/4" = 1'-0"



ENLARGED MRI OFFICE A110 DEMOLITION PLAN

- | |
|--------------------------|
| GENERAL FLOOR PLAN NOTES |
|--------------------------|

1. THESE DRAWINGS SHOULD BE USED TO DETERMINE THE DESIGN INTENT. THE CONTRACTOR SHALL FIELD VERIFY ALL WORK AND SHALL NOTIFY THE ARCHITECT IMMEDIATELY IN WRITING OF ANY DISCREPANCIES IN THE DOCUMENTS BEFORE PROCEEDING. FAILURE TO DO SO WILL NOTIFY THE CONTRACTOR OF THE ASSUMPTION OF LIABILITY AND LIABILITY FOR SUE DISCREPANCIES.
2. ALL WALLS EXTEND TO UNDERSIDE OF FLOOR/CEILING. CONTRACTOR TO PROVIDE FINISH WALLS EXTEND TO BOTTOM OF TRUSS AT LIGHT GAUGE METAL TRUSSES).
3. ALL WALLS 12" TO 12' FLECTION WHERE WALL MEETS STRUCTURE ABOVE. PROVIDE COMPRESSIBLE FILLER BETWEEN TOP OF WALL AND STRUCTURE ABOVE. PROVIDE WALL CONSTRUCTION AS SHOWN AT RATED WALL CONSTRUCTION.
4. FILL PARTS OF DECK WALL CONSTRUCTION AND FIRE SAVING AT RATED WALL CONSTRUCTION.
5. PROVIDE FIRE RATED PARTITION WALLS PER MATERIALS.
6. COORDINATE OPENINGS IN WALLS w/ OTHER TRADES AND SEAL.
7. SEAL ALL PENETRATIONS THROUGH WALL TYPE.
8. FEC - FIRE EXTINGUISHER CABINET & EXTINGUISHER.
9. ALL DOORS AND EXTERIOR DOOR/STOPS ARE TO BE 48" HIGH AND 36" WIDE. BELOW UNLESS NOTED OR DIMENSIONED OTHERWISE.
10. ALL EXTERIOR DIMENSIONS ARE TO FACE OF BRICK OR CONCRETE.
11. ANY EXISTING FLOORS TO RECEIVE RESILIENT OR VINYL FLOORING SHALL BE GROUNDED OR LEVELLED TO ACCEPT FINISH FLOORING.
12. ALL WORK SHALL BE DONE IN ACCORDANCE WITH MANUFACTURER TO MAINTAIN WARRANTY.
13. ALL EXPOSED STRUCTURAL STEEL TO HAVE 2 HOUR FIRE RATED FIRE PROOFING UNLESS NOTED OTHERWISE.
14. PROVIDE BULLNOSE CORNER BLOCKS AT ALL EXPOSED OUTSIDES OF WALLS AND PARTITIONS UNLESS NOTED OTHERWISE - TYPICAL.
15. PROVIDE DRYWALL CONTROL JOINTS AT LOCATIONS AS SHOWN ON DRAWINGS.
16. PROVIDE JOINTS IN ALL DIRECTIONS AND AT JAMB SPACING OF 30-0" IN ALL DIRECTIONS AND AT ALL JAMB SPACING AT ALL OPENINGS - TYPICAL. INSTALL IN WALLS TO PROVIDE WITH JOINTS AT ALL LOCATIONS. PROVIDE JOINTS ALIGNED WITH DOOR JAMBS AND/OR EDGE OF SOFFITS WHEREVER POSSIBLE. ALL GWSB CONTROL JOINTS LOCATIONS FOR ALL WALLS TO BE MARKED UP ON SHOP DRAWINGS AND SUBMITTED TO THE ARCHITECT PRIOR TO INSTALLATION.
17. WALLS TO BE GWSB. PROVIDE MINIMUM NUMBER OF LAYERS OF GWSB. INSTALL FINAL LAYERS OF GWSB FLUSH.
18. PROVIDE JOINTS TO PROVIDE ALL FINISHING IN WALLS FOR ALL BUILT-IN CABINETS, COUNTERTOP SUPPORTS, GRAB BARS, ETC.
19. LOCATIONS WHERE THERE ARE JOINTS IN WALL ASSEMBLIES HAVE FURRED OUT DRYWALL WRAP BAR TO DOOR/FLOOR.
20. PROVIDE FIRE BLOCKING AS REQUIRED PER CBC.
21. ACCESS DOORS SHALL BE INSTALLED IN WALLS AT EQUIPMENT VENT LOCATIONS.
22. PROVIDE ACCESS FOR MAINTENANCE WHICH ARE LOCATED BEHIND FINISHED SURFACES. SEE SECTION 05050 FOR SPECIFIC REQUIREMENTS AND DIRECTIONS.



EQUIPMENT ABBREVIATIONS

- FEC - FIRE EXTINGUISHER CABINET & EXTINGUISHER
FF - SURFACE MTD FIRE EXTINGUISHER
PTD - PAPER TOWEL DISPENSER
UC - UTILITY CABINET
PORT - PORTFOLIO STORAGE CABINET
PB - PAPER STORAGE CABINET

DEMOLITION PLAN KEYNOTES

- | | |
|----|---|
| 01 | REMOVE CEILING SYSTEM. COORDINATE MECHANICAL AND ELECTRICAL. REFER TO CEILING PLAN AND ROOM FINISH SCHEDULE. |
| 02 | REMOVE FLOORING SYSTEM. COORDINATE WITH MECHANICAL AND ELECTRICAL. REFER TO ROOM FINISH SCHEDULE. |
| 03 | EXISTING DOOR, FRAME, AND HARDWARE TO BE REMOVED. SALVAGE CARD READER FOR REINSTALLATION IN NEW WORK. |
| 04 | REMOVE EXISTING PLUMBING FIXTURES. CUT & CAP PLUMBING LINES. REFER TO PLUMBING DRAWINGS FOR EXTENT OF DEMOLITION. |
| 05 | REMOVE PORTION OF WALL INCLUDING ALL WALL-MOUNTED ACCESSORIES AND UTILITIES CONCEALED WITHIN THE WALL. GARY. |
| 06 | REMOVE EXISTING TOILET ROOM ACCESSORIES AND TOILET PARTITIONS. |
| 07 | REMOVE EXISTING MILLWORK, INCLUDING ASSOCIATED PLUMBING FIXTURES WHERE APPLICABLE. CUT & CAP PLUMBING LINES. REFER TO PLUMBING DRAWINGS FOR EXTENT OF DEMOLITION. |
| 08 | |

- 08
09
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24



PROFESSIONAL SEALS

PROJECT PARTNERS:

[illegible]

☐ APPROVED FOR CONSTRUCTION
☒ NOT APPROVED FOR CONSTRUCTION

CLIENT INFORMATION:

Wayne State University



WAYNE STATE
UNIVERSITY

5454 CASS AVE
DETROIT, MICHIGAN
48202

CLIENT PROJECT #:	PROJECT NUMBER
JHA PROJECT #:	PROJECT NUMBER

PROJECT INFORMATION:

WSU APPLEBAUM
MRI INSTALLATION

259 MACK AVE
DETROIT, MICHIGAN
48201

SSOE PROJECT #:	023-03727-00
SSOE MANAGER:	JEFF FALZON

SSOE
1001 Madison Avenue
Toledo, OH 43604
T. (419) 255-3830

THIS DRAWING IS THE PROPERTY OF SSOE GROUP. UNAUTHORIZED USE OF ANY KIND,
INCLUDING USE ON OTHER PROJECTS, IS PROHIBITED.

7 ENLARGED NMR AND MRI OFFICE PLANS

AE-102

GENERAL NOTES

NOTE 1: MOUNTING HEIGHTS SHOWN ARE FOR ACCESSORIES AND FIXTURES REQUIRED UNLESS OTHERWISE NOTED OR DIMENSIONED ON DRAWINGS FOR SPECIFIC CONDITIONS.

NOTE 2: THE REFERENCE STANDARDS FOR THESE DETAILS IS THE 2009 INTERNATIONAL CODE COUNCIL A117.1-2009, ACCESSIBLE AND USABLE BUILDING AND FACILITIES, AS REFERENCED BY CHAPTER 11 OF THE INTERNATIONAL CODE COUNCIL MODEL CODES AND THE DEPARTMENT OF JUSTICE 2010 ADA STANDARDS FOR ACCESSIBLE DESIGN.

NOTE 3: THE BASIS OF DESIGN FOR THESE DETAILS IS BOBRICK. REFER TO THE SPECIFICATION MANUAL FOR OTHER MANUFACTURERS. ADJUST MOUNTING TO MATCH CRITICAL DIMENSIONS AND OPERATION REQUIREMENTS AND REACH RANGES.

NOTE 4: DIMENSIONS NOTED AS MINIMUM / MAXIMUM OR CLEAR INDICATE FINISHED DIMENSION AND MUST BE MAINTAINED. ADJUST WALL DIMENSIONS IF NECESSARY TO MAINTAIN REQUIRED CLEARANCES BETWEEN FIXTURES AND FINISHES.

NOTE 5: OPERABLE PARTS SHALL BE OPERABLE WITH ONE HAND AND SHALL NOT REQUIRE TIGHT GRASPING, PINCHING, OR TWISTING OF THE WRIST. THE FORCE REQUIRED TO ACTIVATE OPERABLE PARTS SHALL BE 5 POUND (22.2N) MAXIMUM.

NOTE 6: PROVIDE BARRIER FREE (BF), AMBULATORY (AM) OR STANDARD (ST) DETAILS AS INDICATED ON FLOOR PLANS. MOUNT ALL ACCESSORIES AS INDICATED BELOW IN EACH TOILET STALL TYPE. PROVIDE MINIMUM (1) SET OF BARRIER FREE (BF) ACCESSORIES FOR EACH BARRIER FREE (BF) FIXTURE.

TOILET ACCESSORY SCHEDULE

Toilet Key Name	Toilet Item Name
-----------------	------------------




PROFESSIONAL SEALS:


PROJECT PARTNERS:

BARRIER FREE (BF)
GENERAL NOTE:
PROVIDE 9" TOE CLEARANCE EXTENDING 6" BEYOND THE COMPARTMENT FRONT AND SIDE FACE OF THE PARTITION, EXCLUSIVE OF PARTITION SUPPORT MEMBERS TYPICAL. IF 9" TOE CLEARANCE IS NOT PROVIDED AT PARTITIONS, EXTEND COMPARTMENT DEPTH TO 82" AT WALL HUNG TOILETS AND 65" AT FLOOR MOUNTED TOILETS MINIMUM. MAINTAIN ALL OTHER CLEARANCES.


WATER CLOSET




URINALS




LAVATORY




DRINKING FOUNTAINS AND BOTTLE FILLING STATIONS



JANITORIAL ACCESSORIES




ACCESSORIES DETAILS




SHOWER STALL AND ACCESSORIES


RECESSED FIXTURE REQUIRED DIMENSIONS




SAFETY AND FIRE PROTECTION ACCESSORIES




MISCELLANEOUS ACCESSORIES




DOOR IN SERIES CLEARANCES




DOOR MANEUVERING CLEARANCES (LATCH & CLOSER)




MANEUVERING CLEARANCES AT RECESSED DOORS - ALL FORWARD APPROACH



MISCELLANEOUS BARRIER FREE REQUIREMENTS



LOCKER DETAILS



SUBMITTAL/REVISION SCHEDULE:		
NO.	DATE	DESCRIPTION
1	10-20-23	DO PROGRESS
2	11-08-23	PROGRESS PRINT

APPROVED FOR CONSTRUCTION
NOT APPROVED FOR CONSTRUCTION

CLIENT INFORMATION:

Wayne State University



WAYNE STATE UNIVERSITY

5454 CASS AVE
DETROIT, MICHIGAN 48202

CLIENT PROJECT #: PROJECT NUMBER
JHA PROJECT #: PROJECT NUMBER

PROJECT INFORMATION:
BASELINE OF WORK
WSU APPLEBAUM MRI INSTALLATION

259 MACK AVE
DETROIT, MICHIGAN 48201
SSOE PROJECT #: 023-03727-00
SSOE MANAGER: JEFF FALZON

SSOE
1001 Madison Avenue
Troy, OH 45360
T: (419) 253-3830
F: (419) 253-3830

TYPICAL MOUNTING HEIGHTS

AE-400

A		B		C		D	
MATERIAL FINISH SCHEDULE							
CODE	BASIS OF DESIGN MANUFACTURER	STYLE NAME #	COLOR NAME #	DESCRIPTION		LOCATION	
ACOUSTICAL CEILING TILE							
ACT-1	ARMSTRONG CEILING SOLUTIONS	OPTIMA	WHITE (WH)	2'x2', SQUARE TEGULAR IN 15/16" PRELUDE GRID WITH STABILIZER CLIPS		OFFICE BREAKROOM, CONFERENCE ROOMS, HUDDLE ROOMS, PRIVATE OFFICES, OPEN OFFICE, CORRIDORS, SUPPORT AREAS	
CARPET TILE							
CPT-1	INTERFACE	TBD	TBD	FIELD			
CPT-2	INTERFACE	TBD	TBD	ACCENT			
CERAMIC FLOOR TILE							
FT-1	MILESTONE - FLORIM USA	CONCRETE LOOK FLOOR TILE	TBD	LARGE FORMAT FIELD TILE		OFFICE BREAKROOM, TOILET ROOM FLOORS	
CERAMIC FLOOR TILE BASE							
FTB-1	MILESTONE - FLORIM USA	CONCRETE LOOK BULLNOSE TILE BASE	TBD	BULLNOSE TRIM TO COORDINATE WITH FT-1		OFFICE BREAKROOM	
CERAMIC WALL TILE							
WT-1	AMERICAN OLEAN	COLOR STORY	TBD			TBD	
WT-2	AMERICAN OLEAN	COLOR STORY	TBD			TBD	
LUXURY VINYL TILE							
LVT-1	INTERFACE	TBD	TBD	FIELD			
LVT-2	INTERFACE	TBD	TBD	ACCENT			
PAINT AND COATINGS							
PT-1	SHERWIN WILLIAMS	TBD	TBD	FIELD; EGGSHELL FINISH		TYPICAL WALLS, U.N.O.	
PT-3	SHERWIN WILLIAMS	TBD	TBD	ACCENT; EGGSHELL FINISH		TBD	
PT-4	SHERWIN WILLIAMS	SW 7757	HIGH REFLECTIVE WHITE	FLAT		TYPICAL PAINTED GWB CEILINGS IN NON WET LOCATIONS	
PLASTIC LAMINATE							
PL-1	WILSONART	TBD	TBD	STANDARD HPL		MILLWORK VERTICAL SURFACES	
PL-2	WILSONART	TBD	TBD	STANDARD HPL		MILLWORK COUNTERTOPS	
QUARTZ COUNTERTOPS							
QZ-1	WILSONART	QUARTZ COUNTERTOP	TBD			QUARTZ COUNTERTOPS	
RESILIENT BASE / ACCESSORIES / STAIR ACCESSORIES							
RB-1	JOHNSONITE	TRADITIONAL VINYL 1/8"	TBD	4" H CONTINUOUS ROLL, COLORMATCH		TYPICAL THROUGHOUT, UNO	
WINDOW TREATMENT							
WS-1	MECHOSHADE	ECOVEIL #1550	TBD	MANJAL ROLLER SHADES WITH 3% OPENNESS		ALL WINDOWS THROUGHOUT EXCEPT NORTH FACING AND WINDOWS RECEIVING GLASS FILM (GF-1) UNO	



CLIENT INFORMATION:

Wayne State University

5454 CASS AVE
DETROIT, MICHIGAN
48202

CLIENT PROJECT #:	PROJECT NUMBER
JHA PROJECT #:	PROJECT NUMBER

PROJECT INFORMATION:

WSU APPLEBAUM
MRI INSTALLATION

7.7
259 MACK AVE
DETROIT, MICHIGAN
48201

SSOE PROJECT #:	023-03727-00
SSOE MANAGER:	JEFF FALZON

886600®

1001 Madison Avenue
Toledo, OH 43604
T. (419) 255-3830

THIS DRAWING IS THE PROPERTY OF SSOE GROUP. UNAUTHORIZED USE OF ANY KIND, INCLUDING USE ON OTHER PROJECTS, IS PROHIBITED.

STUDENT LOUNGE -
INTERIOR FINISH FLOOR
PLAN

AE-701





PROVIDE:

- ELECTRICAL FOR TWO (2) VENDING MACHINES.
- 5'-0" COUNTERTOP WITH ELECTRICAL INCLUDED FOR MICROWAVE
- SINK

NEW STUDENT LOUNGE FLOORING NOTES:

- * PROVIDE ALLOWANCE FOR NEW FLOORING INSTALLATION PER FINISH FLOOR PLAN AND LEGEND.
- * FINAL FLOOR FINISHES AND PATTERN - TBD
- * PROVIDE CONVENIENCE OUTDOORS 12' O.C. AROUND LOUNGE PERIMETER WALLS.
- * PROVIDE CONVENIENCE DOOR OUTLETS WITHIN EACH "SEATING" AREA.
- * PROVIDE ALLOWANCE FOR A FEATURE GRAPHIC WALL.
- * PROVIDE ALLOWANCE FOR ALL NEW HIGH STC ACOUSTICAL CEILING TILES (ALTERNATE #3)



☐ APPROVED FOR CONSTRUCTION
☒ NOT APPROVED FOR CONSTRUCTION

CLIENT INFORMATION:

Wayne State University



**WAYNE STATE
UNIVERSITY**
5454 CASS AVE
DETROIT, MICHIGAN
48202

CLIENT PROJECT #:	PROJECT NUMBER
JHA PROJECT #:	PROJECT NUMBER

PROJECT INFORMATION:

WSU APPLEBAUM
MRI INSTALLATION

259 MACK AVE
DETROIT, MICHIGAN
48201

SSOE PROJECT #: 023-03727-00

SSOE MANAGER: JEFF FALZON

SSOE[®]
1001 Madison Avenue
Toledo, OH 43604
T. (419) 255-3830

THIS DRAWING IS THE PROPERTY OF SSOE GROUP. UNAUTHORIZED USE OF ANY KIND,
INCLUDING USE ON OTHER PROJECTS, IS PROHIBITED.



INTERIOR DETAILS

AE-870

<p>MECHANICAL SPECIFICATIONS</p>	
<p>1. DESCRIPTION OF WORK</p>	
<p>A. Contractor shall provide all materials, equipment, and labor to provide a complete and operating installation.</p>	<p>F. Protect all paint, etc. be abraded</p>
<p>B. Work includes labor and materials necessary for demolition and installation of new equipment, piping, ductwork, and other mechanical items as described herein and shown on drawings. Omission of duct reference herein to any essential item shall not excuse contractor from complying with design intent. Drawings are diagrammatic unless dimensioned. The drawings diagrammatically show suggested examples for possible routing of mechanical systems. The drawings do not contain available information and do not show the only possible arrangement, nor do they relieve the contractors of the responsibility of field verification and preparation of coordination drawings.</p>	<p>G. Clear away operations. Where necessary condition</p>
<p>C. Provide miscellaneous steel and hardware as required to support, handle, and secure equipment furnished as part of this work.</p>	<p>H. Clean up surfaces.</p>
<p>D. Perform cutting and core drilling as required for work described.</p>	<p>I. SELECTIVE</p>
<p>E. Provide sleeves for pipes passing through slabs, walls, or floors (3" high at floor penetrations).</p>	<p>A. Remove or operations. grilles and airtight control to remain.</p>
<p>F. The Owner's representative is to be notified of all testing and flushing & cleaning and equipment start-ups. Copies of start-up reports are to be provided to Owner's representative.</p>	<p>B. All equipment not released and directed to work.</p>
<p>G. The installing contractor shall provide a walkthrough and training for the Owner's building engineers at or near completion of the project.</p>	<p>C. Uncleaned contractors</p>
<p>H. Operation and maintenance manuals are to be provided for all components and/or systems requiring a manual.</p>	<p>D. CONNECT</p>
<p>I. Submit for approval shop drawings for all mechanical systems or equipment but not limited to the items listed below:</p>	<p>A. Make all designate contract to be required for the existing</p>
<p>Duct Accessories</p>	
<p>Grilles, Registers & Diffusers</p>	
<p>Controls</p>	
<p>Insulation</p>	
<p>2. CODES, PERMITS, AND INSPECTIONS</p>	

	<p>installation against defects in materials, equipment, or workmanship during the period of 12 months from the date of final acceptance. If, after completion of the project, at any time, due to causes other than defective work, or any defect appears, Contractor shall remedy them, without cost to the Owner.</p> <p>The Contractor shall provide all materials and labor, without cost to the Owner.</p> <p>WORK</p> <p>If damage done to the existing and new work.</p> <p>INTERFERENCE</p> <p>Other trades to avoid interferences and to present a neat appearance which result due to lack of coordination are the responsibility to correct.</p> <p>When piping for connections to same and building structural interference.</p> <p>To coordinate installation to preclude any interference between ductwork, wiring, lighting fixtures, cable trays, ductwork, building exterior contractors, and other construction.</p> <p>Installation of equipment requiring service to preclude any permanent access doors or panels, or with service to others; such as shall be provided by mechanical service can have to remove equipment.</p> <p>Pipe shall be welded #8 gauge aluminum or 25 gauge stainless steel radius elbows and with 3' of 2.0 lbs/cu. ft., expanded (R11 minimum) with vapor barrier.</p> <p>#6 and smaller shall be Type L hard drawn copper tubing per type fittings, Type L wrought copper (ASTM B16-22), pipe type brass (ASTM B62). Solder shall be lead-free 95-5.</p> <p>Type ACR drawn or annealed temper copper tubing with non-copper fittings and unions (ASME B16.22) with brazed joints.</p> <p>Cooled steam piping shall be pitched uniformly down in the direction of flow at ¼" per foot, and return piping shall be pitched toward the condensate flow at ½" per 10 feet.</p> <p>Fabricated in the United States of America and bear</p>	<p>the Owner's existing system.</p> <p>E. Content of Legend</p> <p>F. Control of legend</p> <p>I. Identify contents of piping systems 20'-0" O.C. above ceilings if both fluid contained and unique temperature and/or pressure (if necessary to distinguish between other systems with same fluid at different conditions); i.e., Potable Hot Water - 110°F vs. Potable hot Water - 140°f, low pressure steam - 5 psig vs. low pressure steam - 2 psig.</p> <p>J. Clearly identify direction of flow in pipe with flow arrows "1" wide x 6" long with arrow head, 2" wide at base installed at intervals, above ceiling, pipe spaces, adjacent to Location of Markers</p> <p>G. Location of Markers</p> <p>L. Pipe labels shall be based in all access panels or doors, adjacent to valves and branch connections, both sides of floors, ceilings and walls, all major changes in direction, on straight lengths of pipes every 20 feet, and at points of entry termination.</p> <p>M. Similarly for duct labels flow arrows on ducts, 20'-0" O.C.</p> <p>N. Arrows and markers shall be mounted to provide unobstructed visibility from floor level.</p> <p>O. Piping identification materials shall be larger, legible letters, 1"-high as manufactured by Brady or Seton on piping 10" and larger, 1/2"-high on piping smaller than 10", and ¾" lettering on piping ¾" and smaller.</p> <p>P. Locations for pipe markers above handrails in finished areas shall be adjacent to each valve, and on all horizontal pipe run-marched every 20'-0", and on each side of a wall penetration.</p> <p>15. MECHANICAL INSULATION</p> <p>A. General</p> <p>1. Contractor shall provide thermal insulation on all supply ductwork, outside air intake ductwork and return air ductwork. Insulation shall not be installed until systems have been tested and inspected.</p> <p>2. All insulation on piping and equipment that has been damaged or has been damaged during construction shall be repaired to like-new condition.</p> <p>3. Approved manufacturers for fiberglass insulation: Certaintecd, Owens-Corning Fiberglass Corp., Manville Products Company, and Knaflex Fiber Glass.</p> <p>4. All insulation, including facings, cements, and adhesives when tested per ASTM E84 by UL shall have a flame spread rating of less than 25, and a smoke developed rating no more than 50.</p> <p>For adhesives, mastics, coatings and sealants, approved manufacturers are Foster Products Div., HB Fuller Co. ICS Adhesives Co., Chicago Mastec Co.,</p>
F	F	

Children Products Co., and St. Clair Rubber Co.	d
uctwork Insulation	C
Concealed ductwork shall be covered with 1-1/2 inch glass fiber, flexible blanket insulation with a density of 5 lb/cu ft. Blanket shall have a vapor retardant consisting of aluminum foil reinforced with fiberglass yarn and laminated to a fire resistant kraft paper, secured with UL listed pressure sensitive tape.	C
FAL DUCTWORK	C
uctwork Construction	C
All ductwork shall be constructed and supported in accordance with the requirements of the latest SMACNA HVAC Metal Ductwork Standards. All joints and seams of all ductwork shall be sealed. All ductwork shall be constructed in a tight and after the installation, ductwork shall be tested. Ductwork shall be kept free of dirt and foreign materials and therefore, after and during assembly of ducts, clean all dirt, grease, rubbish, etc. from both the interior and exterior of ductwork.	C
Pressure Class	C
Ductwork pressure classification shall be no less than +2" for all supply ductwork, and no greater than -2" for all exhaust and return ductwork.	C
Sealing Ductwork	C
All existing and new ductwork shall be effectively sealed per seal class A. All sealant shall be UL rated and shall comply with NFPA 904. Sealing shall be defined as caulking all joints with duct sealer. Not only circumferential joints shall be sealed, but all along each and every Pittsburgh seam shall be sealed, and preformed prefabricated duct connectors (Ductco or Nexus). Duct joint sealers shall be tested in accordance with ASTM E-84-80 and not exceed 25 percent flame spread and 50 smoke developed ratings.	C
Insulated Flexible Duct	C
Low pressure and high pressure insulated flexible duct shall be Flexmaster USA Inc., type 8M7, mechanically locked without adhesives into a formed aluminum hick on the duct's outside surface, and shall be factory wrapped in a black blanket of fiberglass insulation with a C-factor of 0.23 or less. The insulation shall be encased in a fire retardant polyethylene protective vapor barrier with a perm rating of not over 0.1 gram/micron/hour. The flexible duct shall be UL listed 181 Class I air duct and comply with NFPA 90A and 90B and have a flame spread of not over 25 and a smoke developed of not over 50. The flexible duct shall have a minimum pressure rating of 12" W.C. through a temperature range of -20 deg. F to +250 deg. F. Maximum length of flexible duct shall be (5) five feet to each connection.	C
Access Panels	C
Access panels shall be double wall construction with 1" rigid insulation on insulated ducts and single wall panels on uninsulated ducts. Access panels shall be installed wherever ducts contain devices requiring maintenance or calibration, such as coils, air flow stations, humidifiers, fire dampers, smoke dampers, etc. Access doors for ductwork shall be rated for pressure of 12" W.G. on both frame and door made from 16 gauge galvanized steel. Approved Manufacturers: Cesco Models GHS and CAD, Aislen, Ruskin, and Advanced	C
Clear Access	C
Clear access from the occupied space shall be maintained to devices within ducts (dampers, sensors, TAB boxes, etc.), without requiring personnel to step into ductwork, remove equipment, remove piping, or remove equipment or piping supports.	C
DUCTWORK ACCESSORIES	C
turning Vanes	C
All mitered duct elbows greater than 45°, shall have SMACNA 24 gauge turning vanes. Provide turning vanes constructed of 1-1/2" wide curved blades and painted at 1/2 O.C., supported with bars perpendicular to blades set at 2" O.C. and set into side strips suitable for mounting in ductwork. Approved manufacturers: Duro Dymec Co.	C
Volume Dampers	C
All supply, return and exhaust branch ducts shall have manual opposed blade volume dampers. A sealing access panel or door is required to each accessible damper. Approved manufacturers: Nalor, Ruskin, and Young Regulator.	C
PUTTING AND PATCHING	C
Puttals and floor slabs for new work. Patch and paint to match new work.	C
TESTING AND BALANCING	C
Testing and Balancing (T&B) Contractor shall meet with Mechanical Contractor	C

<p>early phase of construction to review project for preliminary and collision testing and flow measurement requirements prior to any work on call systems, and to point out location of taps and dampers that T&B may require to conduct his tests.</p> <p>Contractor shall be a current member in good standing of AABC, NEBB, ACMA. The services of an Independent T&B agency that specializes in business is limited to the testing and balancing of air conditioning equipment.</p> <p>Testing and balancing shall be performed under the direct supervision of a mechanical technician.</p> <p>After ceiling tiles for testing and balancing have to be re-installed at the end of each day, unless Owner's Representative agrees otherwise.</p> <p>Starting any new work, the balancing contractor shall take readings and provide the following data for each existing air handling system to be modified: for each diffuser, grille and register (supply, return, and/or exhaust). Flow rate and static pressure, and manufacturer of all diffusers, grilles, registers, filters, fans, shutoff valves, and motors.</p> <p>Assemble the complete records in hard-backed loose-leaf binders properly labeled. Furnish three (3) copies of each system and deliver to the Owner's Representative.</p> <p>The contractor shall be responsible for providing all testing and balancing equipment required to conduct these tests.</p> <p>Measure and record all existing and new air and hydronic terminal device pressures to the flow rates indicated on the drawings.</p> <p>When system tested, the contractor shall provide a certificate testifying that the work was satisfactorily tested as specified and passed. The certification shall include the following information:</p> <ul style="list-style-type: none"> Location of system tested including specific equipment (model and number) connected to the system. Time and date of test. Room temperature and humidity at time of test. Pressure and duration of test (for duct leak testing). Design and actual flow rates and temperatures for all flows (supply air, return air, exhaust air, relief air, outside air, HW/HSR, CHW/SCR). Final dual equipment system pressure drops. Measurements and checks used to ensure accuracy of data obtained and uncertainties were met. Use of testing, calibration and certification dates. Performance data sheets shall be furnished for equipment, including curves and operating information. When necessary repairs made before system passed the test. Method of formulas and references used for correcting measure readings. Flow plot data traces, (main and branch ductwork). <p>Information that may be useful in an analysis of test results.</p> <p>Submitted final report shall include a one-line diagram of each measured unit with locations of all measurements shown and given a unique identification that is also shown in the report data.</p> <p>Time of volume dampers.</p> <p>Flow and cooling coil inlet and outlet temperatures.</p> <p>No Tolerance Schedule with permissible tolerances is as follows:</p> <table border="0" style="width: 100%;"> <tr> <td>Return and exhaust fan</td> <td>+5% to 10%</td> </tr> <tr> <td>and supply grilles</td> <td>0% to +10%</td> </tr> <tr> <td>and exhaust grilles</td> <td>0% to -10%</td> </tr> </table> <p>The contractor shall assemble the complete record in hard-backed, loose-leaf binder, properly identified. Supply three (3) copies of each system and deliver to the Owner's Representative.</p> <p>For T&B Contractors: Envo Airflow Inc., Absolute Balancing Co., Inc., Testing Inc., International Test Air, Balance.</p>	Return and exhaust fan	+5% to 10%	and supply grilles	0% to +10%	and exhaust grilles	0% to -10%	<div style="border: 1px solid black; padding: 5px; margin-bottom: 10px;"> <p><input checked="" type="checkbox"/> APPROVED FOR CONSTRUCTION</p> <p><input checked="" type="checkbox"/> NOT APPROVED FOR CONSTRUCTION</p> </div> <p style="text-align: center; font-weight: bold;">CLIENT INFORMATION:</p> <div style="text-align: center;">  <p style="font-weight: bold; font-size: 1.2em;">WAYNE STATE UNIVERSITY</p> <p>5454 CASS AVE DETROIT, MICHIGAN 48202</p> </div> <table border="1" style="width: 100%; border-collapse: collapse; margin-top: 10px;"> <tr> <td style="width: 50%;">CLIENT PROJECT #:</td> <td style="width: 50%;">PROJECT NUMBER</td> </tr> <tr> <td>JHA PROJECT #:</td> <td>PROJECT NUMBER</td> </tr> </table> <p style="text-align: center; font-weight: bold;">PROJECT INFORMATION:</p> <p style="font-size: 1.2em; font-weight: bold;">WSU APPLEBAUM MRI</p> <div style="text-align: center; margin-top: 10px;">  <p>AREA OF WORK</p> <p>NO SCALE</p> </div> <p style="text-align: center;">259 MACK AVE DETROIT, MICHIGAN 48201</p> <table border="1" style="width: 100%; border-collapse: collapse; margin-top: 10px;"> <tr> <td style="width: 50%;">SSOE PROJECT #:</td> <td style="width: 50%;">023-03727-00</td> </tr> <tr> <td>SSOE MANAGER:</td> <td>JEFF FALZON</td> </tr> </table> <div style="text-align: center; margin-top: 10px;"> <p>SSOE</p> <p>1050 Wilshire Drive, Suite 260 Troy, MI 48064-1526 T: (248) 643-9222</p> </div> <p style="font-size: 0.8em;">THIS DRAWING IS THE PROPERTY OF SSOE GROUP, INC. UNAUTHORIZED USE OF ANY PART, INCLUDING FOR ANY PURPOSES IS PROHIBITED.</p> <p style="font-size: 0.7em;">© SSOE, INC. 2023</p>	CLIENT PROJECT #:	PROJECT NUMBER	JHA PROJECT #:	PROJECT NUMBER	SSOE PROJECT #:	023-03727-00	SSOE MANAGER:	JEFF FALZON
Return and exhaust fan	+5% to 10%														
and supply grilles	0% to +10%														
and exhaust grilles	0% to -10%														
CLIENT PROJECT #:	PROJECT NUMBER														
JHA PROJECT #:	PROJECT NUMBER														
SSOE PROJECT #:	023-03727-00														
SSOE MANAGER:	JEFF FALZON														

Contractor shall keep site clean and free of debris at all times. Remove unused materials from premises. Owner shall be given the option of retaining used items.

DRAWINGS

Use of the project and prior to receipt of final payment, submit to the owner one set of documents clearly indicating all deviations from the original drawings.

MH-001

[illegible]

☐ APPROVED FOR CONSTRUCTION
☐ NOT APPROVED FOR CONSTRUCTION


CLIENT INFORMATION



5454 CASS AVE
DETROIT, MICHIGAN
48202

CLIENT PROJECT #:	PROJECT NUMBER
JHA PROJECT #:	PROJECT NUMBER

PROJECT INFORMATION:
WSU APPLEBAUM MRI



KEY PLAN
NO SCALE
259 MACK AVE
DETROIT, MICHIGAN
48201

SSOE PROJECT #:	023-03727-00
SSOE MANAGER:	JEFF FALZON


SSOE
1050 Wilshire Drive, Suite 260
Troy, MI 48064-1526
T. (248) 643-6222

THIS DRAWING IS THE PROPERTY OF SSOE GROUP. UNAUTHORIZED USE OF ANY KIND
INCLUDING USE ON OTHER PROJECTS, IS PROHIBITED.

© SSOE, INC. 2003


PARTIAL LEVEL 0 HVAC
DEMOLITION AND NEW
WORK FLOOR PLANS

MH-101



PARTIAL LEVEL 0 NMR 0250
HVAC NEW WORK PLAN

A5
MH-101 SCALE: 1/8" = 1'-0"




PARTIAL LEVEL 0 OFFICE A110
HVAC NEW WORK PLAN

- HVAC NEW WORK KEYNOTES


- ① REBALANCE EXISTING BOX AND DIFFUSER TO 170 CFM AND RELOCATE THERMOSTAT.
- ② REBALANCE EXISTING BOX TO 180 CFM AND RELOCATE THERMOSTAT.
- ③ REBALANCE EXISTING BOX TO 400 CFM AND RELOCATE THERMOSTAT.

- ② EXISTING 4"x4" EXHAUST GRILLE TO REMAIN.




PARTIAL LEVEL 0 MRI SUITE
HVAC NEW WORK PLAN


SCALE: 1/8" = 1'-0"



PARTIAL LEVEL 0 MRI SUITE
HVAC DEMOLITION PLAN



PARTIAL LEVEL 0 NMR 0250
HVAC DEMOLITION PLAN



PARTIAL LEVEL 0 OFFICE A110
HVAC DEMOLITION PLAN

- HVAC DEMOLITION KEYNOTES

- ⚠ REMOVE ALL DIFFUSERS, GRILLES, CEILING EXHAUST FANS AND ASSOCIATED DUCTWORK IN THE PROJECT WORK AREA AS SHOWN. REMOVE DUCTS AS SHOWN AND CAP AIRTIGHT.
- ⚠ REMOVE EXISTING THERMOSTATS FOR FUTURE INSTALLATION LOCATION.
- ⚠ REMOVE EXISTING OXYGEN SENSORS FOR FUTURE INSTALLATION LOCATION.
- ⚠ RELOCATE EXISTING THERMOSTAT.



PROJECT PARTNERS

KEYPLAN


■ APPROVED FOR CONSTRUCTION
■ NOT APPROVED FOR CONSTRUCTION

CLIENT INFORMATION



CLIENT PROJECT #:	PROJECT NUMBER
JHA PROJECT #:	PROJECT NUMBER

PROJECT INFORMATION:
WSU APPLEBAUM MRI




SSOE PROJECT #:	023-03727-00
SSOE MANAGER:	JEFF FALZON



ES&OE
1050 Wilshire Drive, Suite 260
Troy, MI 48064-1526
T. (248) 643-6222

THIS DRAWING IS THE PROPERTY OF ES&OE GROUP. UNAUTHORIZED USE OF ANY KIND, INCLUDING USE ON OTHER PROJECTS, IS PROHIBITED.


MH-102



FLEX DUCT DROP DETAIL



VOLUME DAMPER DETAIL




BRANCH DUCT DETAIL (SUPPLY)
 SCALE: NONE

[illegible]

GRILLES, REGISTERS AND DIFFUSERS					
MARK	FACE SIZE	NECK SIZE	FACE FLOW PATTERN	MANUFACTURER & MODEL	REMARKS
S-1	24"x24"	SEE PLANS	SQUARE	TITUS OMNI-AA	WHITE POWDER COAT FINISH, ALL ALUMINUM
S-2	24"x12"	----	RECT	TITUS 300FL	DUCT MOUNTED, WITH OPPOSED BLADE DAMPER
R-1	24"x24"	SEE PLANS	RECT	TITUS PXP-AA	ALL ALUMINUM PERFORATED
R-2	20"x20"	SEE PLANS	RECT	TITUS 50F	EGG CRATE, ALUMINUM, WALL MOUNTED
E-1	24"x12"	SEE PLANS	RECT	TITUS PAR	PERFORATED WITH 22"x10" SOUND BOOT

[illegible]

PROFESSIONAL SEALS

PROJECT PARTNERS:

KEYPLAN

[illegible]

☐ APPROVED FOR CONSTRUCTION
☐ NOT APPROVED FOR CONSTRUCTION

CLIENT INFORMATION:




5454 CASS AVE
DETROIT, MICHIGAN
48202

CLIENT PROJECT #:	PROJECT NUMBER
JHA PROJECT #:	PROJECT NUMBER

PROJECT INFORMATION:

WSU APPLEBAUM MRI



SSOE PROJECT #:	023-03727-00
SSOE MANAGER:	JEFF FALZON

SSOE®
1050 Wilshire Drive, Suite 260
Troy, MI 48064-1526
T. (248) 643-6222

THIS DRAWING IS THE PROPERTY OF ESSE GROUP. UNAUTHORIZED USE OF ANY KIND,
INCLUDING USE ON OTHER PROJECTS, IS PROHIBITED.

© 2020, INC. 2021

HVAC EQUIPMENT SCHEDULES AND DETAILS

MH-600

[illegible]

☐ APPROVED FOR CONSTRUCTION
☐ NOT APPROVED FOR CONSTRUCTION



CLIENT PROJECT #:	PROJECT NUMBER
JHA PROJECT #:	PROJECT NUMBER

PROJECT INFORMATION:
WSU APPLEBAUM MRI



SSOE PROJECT #:	023-03727-00
SSOE MANAGER:	JEFF FALZON


SSOE
1050 Wilshire Drive, Suite 260
Troy, MI 48064-1526
T. (248) 643-6222

THIS DRAWING IS THE PROPERTY OF SSOE GROUP. UNAUTHORIZED USE OF ANY KIND
INCLUDING USE ON OTHER PROJECTS, IS PROHIBITED.

© SSOE, INC. 2012


PARTIAL UNDERGROUND PLUMBING DEMO. & NEW WORK FLOOR PLANS

PL-100



PARTIAL UNDERGROUND PLUMBING
MRI SUITE NEW WORK PLAN

SCALE: 1/8" = 1'-0"



PARTIAL UNDERGROUND PLUMBING
MRI SUITE DEMOLITION PLAN

PL-100 SCALE: 1/8" = 1'-0"



PROJECT PARTNERS:

■ APPROVED FOR CONSTRUCTION
■ NOT APPROVED FOR CONSTRUCTION

CLIENT INFORMATION



CLIENT PROJECT #:	PROJECT NUMBER
JHA PROJECT #:	PROJECT NUMBER

PROJECT INFORMATION:
WSU APPLEBAUM MRI



SSOE PROJECT #:	023-03727-00
SSOE MANAGER:	JEFF FALZON

SSOE
1050 Wilshire Drive, Suite 260
Troy, MI 48064-1526
T. (248) 643-6222

THIS DRAWING IS THE PROPERTY OF SSOE GROUP. UNAUTHORIZED USE OF ANY KIND
INCLUDING USE ON OTHER PROJECTS, IS PROHIBITED.

© SSOE, INC. 2012

PARTIAL LEVEL 0
PLUMBING DEMO. & NEW
WORK FLOOR PLANS

PL-101

LIGHTING SYMBOL LEGEND		(NOT ALL SYMBOLS USED)
	LIGHT FIXTURE TYPE, REFER TO LIGHT FIXTURE SCHEDULE	
	SURFACE OR PENDANT LIGHT FIXTURE, CHEVRON INDICATED WALL WASH AIMING, SHADING INDICATES EMERGENCY EGRESS LIGHT FIXTURE	
	RECESSED LIGHT FIXTURE, CHEVRON INDICATED WALL WASH AIMING, HALF-SHADING INDICATES EMERGENCY EGRESS LIGHT FIXTURE	
	SURFACE OR PENDANT LIGHT FIXTURE, HALF-SHADING INDICATES EMERGENCY EGRESS LIGHT FIXTURE	
	RECESSED LIGHT FIXTURE, HALF-SHADING INDICATES EMERGENCY EGRESS LIGHT FIXTURE	
	RECESSED ARCHITECTURAL LIGHT FIXTURE, HALF-SHADING INDICATES EMERGENCY EGRESS LIGHT FIXTURE	
	SURFACE OR CHAIN HUNG STRIP LIGHT FIXTURE, HALF-SHADING INDICATES EMERGENCY EGRESS LIGHT FIXTURE	
	WALL MOUNTED LIGHT FIXTURE, HALF-SHADING INDICATES EMERGENCY EGRESS LIGHT FIXTURE	
	TRACK MOUNTED LIGHT FIXTURE	
	EXIT SIGN, PROVIDE ARROWS/CHEVRONS AS INDICATED ON PLANS, SHADED AREA INDICATES FACE, FOOT ON SYMBOL INDICATES WALL MOUNTED, LIGHT HEADS INDICATE COMBINATION EXIT/BATTERY POWERED EMERGENCY LIGHTING UNIT	
	BATTERY POWERED EMERGENCY LIGHTING UNIT, LIGHT HEADS ON SIDES OF UNIT INDICATES CEILING MOUNTED	
	SINGLE POLE SWITCH - 20A, 120/277V UON, -X- INDICATES WHICH FIXTURES/DEVICES ARE CONTROLLED VIA SWITCH -X- DENOTES TYPE: BLANK - SINGLE POLE 2 - DOUBLE POLE 3 - THREE WAY 4 - FOUR WAY D - DIMMER K - KEY OPERATED I - ILLUMINATED (ILLUMINATED IN 'OFF' POSITION) P - WITH PILOT LIGHT (LIGHT ON IN 'ON' POSITION) T - TIME SWITCH L - LOW VOLTAGE C - MOMENTARY CONTACT O - WALL BOX OCCUPANCY SENSOR - PASSIVE INFRARED V - WALL BOX VACANCY SENSOR - PASSIVE INFRARED	
	OCCUPANCY/VACANCY SENSOR, FOOT ON SYMBOL INDICATES WALL MOUNTED, -a- INDICATES WHICH FIXTURES ARE CONTROLLED VIA SENSOR -X- DENOTES TYPE: A - 180° DUAL TECHNOLOGY OCCUPANCY SENSOR B - 360° DUAL TECHNOLOGY OCCUPANCY SENSOR C - 180° PASSIVE INFRARED OCCUPANCY SENSOR D - 360° ULTRASONIC OCCUPANCY SENSOR	
	DAYLIGHT SENSOR, FOOT ON SYMBOL INDICATES WALL MOUNTED, -a- INDICATES WHICH FIXTURES ARE CONTROLLED VIA SENSOR	
	LIGHTING CONTACTOR, SIZE AS INDICATED ON DRAWINGS/DETAIL	
	EMERGENCY LOAD/GENERATOR TRANSFER DEVICE	
	TIME CLOCK	

ONE-LINE DIAGRAM SYMBOL LEGEND				(NOT ALL SYMBOLS USED)
	TERMINAL		DELTA	
	TERMINATOR		WYE - SOLIDLY GROUNDED	
	STRESS CONE CABLE TERMINATION		GROUND	
	STAB		ENGINE GENERATOR	
	STATIONARY CIRCUIT BREAKER		SHUNT TRIP	
	DRAWOUT CIRCUIT BREAKER		AMMETER	
	STATIONARY SWITCH		UTILITY METER	
	FUSE		VOLT METER	
	MOTOR STARTER WITH OVERLOAD		ELECTRONIC MONITORING UNIT	
	THERMAL OVERLOAD RELAY		POWER MONITORING UNIT	
	NORMALLY OPEN CONTACTS		KEYED INTERLOCK	
	NORMALLY CLOSED CONTACTS		SURGE PROTECTION DEVICE	
	GROUND		MANHOLE	
	LIGHTNING ARRESTER		HANDHOLE	
	CURRENT TRANSFORMER		TRANSFORMER	
	POTENTIAL TRANSFORMER		PANELBOARD, 'XX-XX' INDICATES PANELBOARD DESIGNATION	
	TRANSFER SWITCH			

GROUNDING AND LIGHTNING PROTECTION LEGEND		(NOT ALL SYMBOLS USED)
	CADWELD CONNECTION BETWEEN GROUND CABLE AND BUILDING COLUMN	
	CADWELD CABLE TO CABLE 'X' CONNECTION	
	CADWELD CABLE TO CABLE 'T' CONNECTION	
	COPPERWELD TYPE GROUND ELECTRODE WITH CADWELD CONNECTION, 'TW' INDICATES TEST WELL	
	BARE COPPER GROUND CABLE, INSTALL MINIMUM 30" BELOW FINISHED FLOOR OR GRADE	
	LUG CONNECTION BETWEEN BUS BAR AND CABLE OR BONDING CONNECTION TO EQUIPMENT	
	CADWELD CONNECTION BETWEEN REBAR OR ROD AND CABLE	
	WALL MOUNTED GROUND BAR	
	COPPER LIGHTNING PROTECTION CONDUCTOR	
	AIR TERMINAL	
	THRU ROOF PENETRATION	
	THRU ROOF PENETRATION WITH CONNECTION TO BUILDING STEEL	
	BOND OR DOWN LEAD TO GROUND ROD	
	BOND TO GROUND RING BELOW GRADE AT EACH DOWN LEAD	
	DOWN LEAD TO COPPER CLAD GROUND ROD	

POWER SYMBOL LEGEND		(NOT ALL SYMBOLS USED)
	SIMPLEX RECEPTACLE - NEMA 5-20R, HORIZONTAL LINE INDICATES MOUNTED AFC UON, SHADING INDICATES CIRCUITED TO GENERATOR/UPS POWER	
	DUPLEX RECEPTACLE - NEMA 5-20R, HORIZONTAL LINE INDICATES MOUNTED AFC UON, SHADING INDICATES CIRCUITED TO GENERATOR/UPS POWER	
	DUPLEX RECEPTACLE - NEMA 5-20R, GROUND FAULT INTERRUPTING, HORIZONTAL LINE INDICATES MOUNTED AFC UON, SHADING INDICATES CIRCUITED TO GENERATOR/UPS POWER	
	SPLIT-WIRED DUPLEX RECEPTACLE - NEMA 5-20R, HORIZONTAL LINE INDICATES MOUNTED AFC UON, SHADING INDICATES CIRCUITED TO GENERATOR/UPS POWER	
	COMBINATION DUPLEX RECEPTACLE - NEMA 5-20RVUSB (TYPE A, 2 & 3), TWO CHARGING USB PORTS, HORIZONTAL LINE INDICATES MOUNTED AFC UON, SHADING INDICATES CIRCUITED TO GENERATOR/UPS POWER	
	QUADPLEX RECEPTACLE - NEMA 5-20R, HORIZONTAL LINE INDICATES MOUNTED AFC UON, SHADING INDICATES CIRCUITED TO GENERATOR/UPS POWER (ALL OTHER NEMA 5-20R QUAD RECEPTACLE SYMBOLS FOLLOW SAME STACKED DUPLEX PATTERN)	
	SPECIAL RECEPTACLE -X- DENOTES TYPE: A - (NEMA L5-30R) 125V, 30A, SINGLE PHASE, TWIST-LOCK RECEPTACLE 2 POLE, 3 WIRE B - (NEMA L6-20R) 250V, 20A, SINGLE PHASE, TWIST-LOCK RECEPTACLE 2 POLE, 3 WIRE C - (NEMA L6-30R) 250V, 30A, SINGLE PHASE, TWIST-LOCK RECEPTACLE 2 POLE, 3 WIRE D - (NEMA L15-20R) 250V, 20A, THREE PHASE, TWIST-LOCK RECEPTACLE 3 POLE, 4 WIRE E - (NEMA L15-30R) 250V, 30A, THREE PHASE, TWIST-LOCK RECEPTACLE 3 POLE, 4 WIRE F - (NEMA L21-30R) 208Y/120V, 30A, THREE PHASE, TWIST-LOCK RECEPTACLE 4 POLE, 5 WIRE G - (NEMA 14-30R) 125/250V SINGLE PHASE RECEPTACLE 3 POLE, 4 WIRE H - (NEMA 14-50R) 125/250V SINGLE PHASE RECEPTACLE 3 POLE, 4 WIRE	
	CEILING MOUNTED SIMPLEX RECEPTACLE - NEMA 5-20R, SHADING INDICATES CIRCUITED TO GENERATOR/UPS POWER	
	CEILING MOUNTED DUPLEX RECEPTACLE - NEMA 5-20R, SHADING INDICATES CIRCUITED TO GENERATOR/UPS POWER	
	CEILING MOUNTED SPECIAL RECEPTACLE -X- DENOTES TYPE: REFER TO WALL MOUNTED SPECIAL RECEPTACLE TYPES ABOVE	
	MULTI-OUTLET SURFACE RACEWAY	
	SINGLE POINT ELECTRICAL CONNECTION OR AS INDICATED IN CIRCUITING/EQUIPMENT SCHEDULE	
	JUNCTION BOX, LEG INDICATES WALL/EQUIPMENT MOUNTING IS REQUIRED, SQUARE INDICATES FLOOR MOUNTED	
	MANUAL MOTOR STARTER/DISCONNECT SWITCH WITH THERMAL OVERLOAD PROTECTION	
	ENCLOSED DISCONNECT SWITCH, SHADING INDICATES SWITCH IS FUSIBLE	
	ENCLOSED CIRCUIT BREAKER	
	COMBINATION MAGNETIC MOTOR CONTROLLER/STARTER, SHADING INDICATES STARTER IS FUSIBLE	
	MAGNETIC MOTOR CONTROLLER	
	VARIABLE FREQUENCY DRIVE (FURNISHED BY OTHERS)	
	PUSHBUTTON STATION	
	MOTOR	
	AUTOMATIC OR MANUAL TRANSFER SWITCH	
	UTILITY METER	
	TRANSFORMER, DASHED LINE INDICATES NEC WORKING SPACE.	
	DISTRIBUTION PANELBOARD, SOLID FILL INDICATES 480V LINE TO LINE, NO FILL INDICATES 208V OR 240V LINE TO LINE, DASHED LINE INDICATES NEC WORKING SPACE.	
	SURFACE MOUNTED PANELBOARD, SOLID FILL INDICATES 480V LINE TO LINE, NO FILL INDICATES 208V OR 240V LINE TO LINE, INSTALL DOOR HINGE ON THE SIDE SHOWN ON SYMBOL, DASHED LINE INDICATES NEC WORKING SPACE, HALF-TONE LINE INDICATES WALL.	
	FLUSH/RECESSED MOUNTED PANELBOARD, SOLID FILL INDICATES 480V LINE TO LINE, NO FILL INDICATES 208V OR 240V LINE TO LINE, INSTALL DOOR HINGE ON THE SIDE SHOWN ON SYMBOL, DASHED LINE INDICATES NEC WORKING SPACE, HALF-TONE LINE INDICATES WALL.	
	MULTI-SECTION SWITCHBOARD OR MOTOR CONTROL CENTER, DASHED LINE INDICATES NEC WORKING SPACE.	
	CONTROL PANEL/CONTROL POWER PANEL (FURNISHED BY OTHERS)	
	POWER SUPPLY	
	GENERATOR ANNUNCIATOR	
	BUILDING MANAGEMENT SYSTEM PANEL (FURNISHED BY OTHERS)	
	FIRE ALARM CONTROL PANEL (FURNISHED BY OTHERS)	
	FIRE ALARM ANNUNCIATOR (FURNISHED BY OTHERS)	
	FIRE ALARM NOTIFICATION APPLIANCE CIRCUIT PANEL (FURNISHED BY OTHERS) EDIT ITEMS IN (I) TO SUIT PROJECT	
	CONDUIT TURNING UP	
	CONDUIT TURNING DOWN	
	INDICATES CIRCUITS TO PANEL, 'RP1' INDICATES PANEL DESIGNATION AND '1,3,5' INDICATED POLE POSITION(S)	
	'X' INDICATES QUANTITY AND 'Y' INDICATES SIZE OF CONDUCTORS, 'Z' INDICATES CONDUIT SIZE	
	PANEL TAG, I.e. CIRCUITS WITHIN AREA WHERE TAG IS LOCATED ON PLAN ARE CIRCUITED TO PANEL 'RP1' UON	
	MECHANICAL EQUIPMENT CONNECTION TAG, DESIGNATION ON TOP INDICATES EQUIPMENT IDENTIFIER AND DESIGNATION ON BOTTOM INDICATES ASSOCIATED EQUIPMENT CONNECTION SCHEDULE AS FOLLOWS: MECH = MECHANICAL, KITCH = KITCHEN, PUMP = PUMP, HEAT = HEATER, FAN = FAN, REFER TO ELECTRICAL SCHEDULES SHEETS FOR ADDITIONAL INFORMATION.	

ELECTRICAL GENERAL NOTES	
1.	PRIOR TO BID, THE CONTRACTOR SHALL VISIT SITE TO SURVEY EXISTING CONDITIONS AFFECTING WORK. INCLUDE NECESSARY MATERIALS AND LABOR TO ACCOMPLISH THE ELECTRICAL WORK, INCLUDING RELOCATION OF EXISTING EQUIPMENT TO ALLOW FOR NEW CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT/ENGINEER AND RESOLVED PRIOR TO BID. WORK SHALL BE COORDINATED WITH ALL OTHER TRADES.
2.	THESE DRAWINGS ARE A PART OF A COMPLETE SET OF ARCHITECTURAL/ENGINEERING DRAWINGS. DRAWINGS SHOWING ELECTRICAL WORK ARE DIAGRAMMATIC. REFER TO ARCHITECTURAL AND STRUCTURAL DRAWINGS FOR GUIDANCE AND COORDINATION WITH DIMENSIONS, CEILINGS, DOOR SWINGS, ELEVATIONS, CASEWORK, FINISHES, STRUCTURAL CONCRETE, FRAMING, DUCTWORK, AND PIPING.
3.	ALL ELECTRICAL WORK SHALL BE DONE IN ACCORDANCE WITH THE NEC AND LOCAL ORDINANCES INCLUDING ALL REQUIREMENTS OF APPLICABLE CODES. CONTRACTOR SHALL OBTAIN AND PAY FOR ALL NECESSARY PERMITS.
4.	ALL SYMBOLS SHOWN ON THESE LEGENDS MAY NOT BE USED.
5.	PROVIDE EXPANSION JOINT FITTINGS ON ALL CONDUITS THAT CROSS EXPANSION JOINTS OR CONDUITS THAT PENETRATE WALLS WITH SEISMIC BRACING. SEE ARCHITECTURAL DRAWINGS.
6.	ALL FLUSH MOUNTED PANELS SHALL HAVE (4) 1" EMPTY CONDUITS STUBBED OUT ABOVE ACCESSIBLE CEILING FOR FUTURE CIRCUITS.
7.	VERIFY LOCATION OF ALL FLOOR OUTLETS WITH ARCHITECT PRIOR TO ROUGH-IN.
8.	ALL WALL OUTLETS NOT PROVIDED WITH A DEVICE BY THIS CONTRACTOR SHALL BE PROVIDED WITH BLANK WALL PLATES.
9.	MULTI-WIRE BRANCH CIRCUITS ARE PROHIBITED UNLESS SPECIFICALLY NOTED OTHERWISE. FINAL EQUIPMENT CONNECTIONS - THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING ALL LABOR AND MATERIALS REQUIRED TO MAKE FINAL CONNECTIONS TO ALL EQUIPMENT FURNISHED BY THIS CONTRACTOR AND/OR EQUIPMENT FURNISHED BY OTHERS. VERIFY ALL REQUIREMENTS, CONDUCTOR SIZE, OVERCURRENT PROTECTION, PHASE, VOLTAGE, ETC., INDICATED ON DRAWINGS WILL SATISFY EQUIPMENT SUPPLIER REQUIREMENTS PRIOR TO ROUGH-IN. PROVIDE FUSED DISCONNECT IF REQUIRED BY MANUFACTURER.
11.	REFER TO "TYPICAL MOUNTING AND ALIGNMENT CRITERIA" DETAIL FOR OUTLET DEVICE MOUNTING HEIGHT AND LOCATIONS.
12.	TYPE "ENT" ELECTRICAL NON-METALLIC TUBING SHALL NOT BE USED.
13.	PROVIDE ACCESS PANELS IN GYPBOARD CEILINGS WHERE ACCESS TO JUNCTION BOXES IS REQUIRED.
14.	PROVIDE A MINIMUM OF (1) 3/4" WITH PULLSTRUNG AND NYLON END BUSHING STUBBED TO ABOVE ACCESSIBLE CEILING FOR ALL WALL MOUNTED AUXILIARY DEVICE, JUNCTION BOXES INCLUDING, BUT NOT LIMITED TO CARD READERS, PUSH PLATES, ETC. UON.
15.	ALL 120V RECEPTACLE OUTLETS WITHIN 6FT OF A WATER SOURCE SHALL BE GFCI PROTECTED. VERIFY ALL DOOR SWINGS W/ ARCHITECT PRIOR TO ROUGH-IN OF WALL MOUNTED LIGHTING CONTROLS, ACCESS CONTROLS, DOOR OPERATORS, ETC. UON.
16.	PROVIDE ADDITIONAL STEEL SUPPORTS FOR MOTOR CONTROLLERS, FIXTURES, RACEWAYS, CABINETS, BOXES, AND THE LIKE WHERE THE BUILDING, EQUIPMENT, OR STRUCTURE IS NOT SUITABLE FOR MOUNTING DIRECTLY THEREON.
18.	"PROVIDE" USED IN SPECIFICATIONS AND DRAWINGS SHALL MEAN "TO FURNISH, INSTALL, CONNECT," AND PLACE IN SERVICE COMPLETELY IN SPECIFIED OR APPROVED MANNER THE ITEM DESCRIBED.
19.	ELECTRICAL WORK EMBEDDED IN CONCRETE OR OTHERWISE PERMANENTLY CONCEALED SHALL NOT BE COVERED UNTIL INSPECTED BY THE OWNER'S REPRESENTATIVE.
20.	ALL PENETRATIONS THROUGH FIRE RESISTANT WALLS AND OTHER SUCH RATED ASSEMBLIES SHALL BE FIRESSTOPPED TO MAINTAIN ITS RATING.
21.	DIVISION 22 AND 23 EQUIPMENT CIRCUITING, DISCONNECT, AND OVERCURRENT PROTECTION CHARACTERISTICS ARE BASED ON THE BASIS OF DESIGN EQUIPMENT SPECIFICATION. CONTRACTOR SHALL BEAR ALL COSTS OF ELECTRICAL CHANGES RESULTING FROM PROVIDING EQUIPMENT FROM AN ALTERNATE MANUFACTURER.

ELECTRICAL DEMOLITION LEGEND		
TAG	SYMBOLGY	DESCRIPTION
(EX)		EXISTING DEVICE TO REMAIN.
(ED)		EXISTING DEVICE TO BE DEMOLISHED.
(ER)		EXISTING DEVICE TO BE RELOCATED.
(EL)		EXISTING DEVICE SHOWN IN NEW LOCATION TO BE REINSTALLED.
(EN)		EXISTING DEVICE TO BE REPLACED WITH NEW DEVICE IN SAME LOCATION.

ELECTRICAL DEMOLITION NOTES	
1.	THE CONTRACTOR SHALL REMOVE THE EXISTING ELECTRICAL WORK NECESSARY TO PROVIDE THE INTENDED ARRANGEMENT OF WALLS AND CEILINGS, AND SHALL RECONNECT ALL CIRCUITS INTERRUPTED BY THIS DEMOLITION WHERE THOSE CIRCUITS ARE UTILIZED BEYOND THE DEMOLITION, WHETHER SUCH CIRCUITS ARE INDICATED OR NOT.
2.	WHERE AN ELECTRICAL DEVICE THAT IS TO BE REMOVED IS AN "END OF LINE" OR A SINGLE DEVICE, THE CONDUCTORS SHALL BE DISCONNECTED AT THE NEXT UPSTREAM DEVICE TO REMAIN OR AT ITS RELATED PANELBOARD. ALL NON-FUNCTIONAL CONDUCTORS INCLUDING POWER AND TELECOMMUNICATION CABLES SHALL BE REMOVED.
3.	DEMOLITION: ACCURACY OF ORIGINAL PLANS HAS NOT BEEN VERIFIED. THE CONTRACTORS SHALL MAINTAIN CIRCUIT CONTINUITY OF ALL EXISTING FIXTURES AND DEVICES THAT ARE TO REMAIN.
4.	EXISTING CIRCUITS, IF INDICATED, ARE DIAGRAMMATIC ONLY. VERIFY EXACT CONDUIT LOCATION AND ROUTINGS OF EXISTING CONDUIT RUNS AND NUMBER OF CONDUCTORS, AND PROVIDE ADDITIONAL CONDUITS / CONDUCTORS AS NECESSARY TO ACCOMPLISH THE DESIGN INTENT.
5.	CIRCUIT BREAKERS ADDED TO THE EXISTING PANELBOARDS SHALL MATCH THE EXISTING BREAKER TYPE, MANUFACTURER, AND AIC RATING. PROVIDE NEW TYPE WRITTEN, UPDATED DIRECTORIES IN THE EXISTING PANELBOARDS TO REFLECT CHANGES MADE BY THIS RENOVATION.
6.	ALL ADDITIONS TO SYSTEMS SHALL MATCH THE MANUFACTURER'S EXISTING SYSTEMS PRESENTLY INSTALLED IN THE FACILITY UNLESS OTHERWISE NOTED.
7.	EXISTING SYSTEMS SHALL REMAIN UNLESS NOTED FOR REMOVAL OR RELOCATION. ALL SYSTEMS SHALL BE CHECKED TO ENSURE THEY ARE IN PROPER WORKING ORDER BEFORE ANY DEMOLITION IS STARTED. SYSTEMS NOT FOUND TO BE IN SATISFACTORY WORKING CONDITION SHALL BE REPORTED TO THE OWNER IN WRITING PRIOR TO THE START OF ANY DEMOLITION WORK. ALL SYSTEMS SHALL BE CHECKED TO ENSURE THAT THEY ARE WORKING PROPERLY AFTER THE DEMOLITION WORK IS FINISHED AND AFTER THE NEW ELECTRICAL INSTALLATION IS COMPLETE.
8.	DEMOLITION, WHERE INDICATED ON PLAN, IS BASED ON EXISTING DRAWINGS AND LIMITED FIELD INVESTIGATION OF EXISTING CONDITIONS. SELECT DEMOLITION MAY BE REQUIRED FOR NEW CONSTRUCTION AND MAY NOT BE DELINEATED ON THIS DRAWING. CAREFULLY COORDINATE DEMOLITION WITH NEW CONSTRUCTION PLANS OF ALL DISCIPLINES TO VERIFY ACTUAL EXTENT OF DEMOLITION. VISIT THE SITE PRIOR TO SUBMISSION OF BID TO EXAMINE THE EXISTING CONDITIONS AND FULLY UNDERSTAND THE EXTENT OF DEMOLITION WORK.
9.	EXAMINE THE DRAWINGS OF OTHER TRADES AND BE FAMILIAR WITH THE DEMOLITION REQUIRED BY OTHER TRADES. PERFORM ALL INCIDENTAL ELECTRICAL DEMOLITION AND/OR RELOCATION REQUIRED TO FACILITATE THE DEMOLITION WORK OF OTHER TRADES, WHETHER OR NOT SPECIFICALLY INDICATED.
10.	QUANTITY AND LOCATION OF EXISTING DEVICES SHOWN ON PLANS ARE APPROXIMATE. FIELD VERIFY DEVICES AND LOCATIONS.
11.	ITEMS SHOWN HEAVY LINE WEIGHT DASHED LINES, HATCHED AND/OR NOTED SHALL BE DEMOLISHED AND ALL ASSOCIATED DEVICES, CONDUIT, AND WIRING SHALL BE REMOVED BACK TO THE NEAREST ACTIVE JUNCTION BOX OR SOURCE UNLESS NOTED OTHERWISE. SEE DEMOLITION LEGEND FOR ADDITIONAL INFORMATION.
12.	ALL EXISTING EQUIPMENT MAY NOT BE INDICATED. CONTRACTOR SHALL FIELD VERIFY EXISTING CONDITIONS PRIOR TO BIDDING. EXISTING ITEMS NOT SHOWN HATCHED SHALL REMAIN IN OPERATION. REVISE THE EXISTING CIRCUITRY TO MAINTAIN OPERATION OF ITEMS TO REMAIN.
13.	MAINTAIN ELECTRICAL SERVICE TO ALL LIGHTING FIXTURES, DEVICES, AND EQUIPMENT THAT ARE OUTSIDE AREA OF RENOVATION. EXTEND CONDUIT AND WIRE AS REQUIRED WHERE DEMOLITION WORK AFFECTS ELECTRICAL SERVICE TO DOWNSTREAM LOADS THAT ARE TO REMAIN.
14.	RECYCLE OR DISPOSE OF ALL MATERIALS OFF SITE AND INCLUDE ALL ASSOCIATED COSTS IN BID. ALL MATERIALS SHALL BE DISPOSED OF IN ACCORDANCE WITH ALL FEDERAL, STATE, AND LOCAL REGULATIONS, INCLUDING LEED REQUIREMENTS, TCLP TESTING, PROPER DISPOSAL AND/OR RECYCLING OF FLUORESCENT LAMPS.
15.	RING OUT AND TAG ALL CIRCUITS AFFECTED BY THIS ALTERATION AT BOTH ENDS. MARK ALL UNUSED CIRCUIT BREAKERS "SPARE" AND PLACE IN THE "OFF" POSITION.
16.	VERIFY ALL UNDERGROUND AND IN SLAB UTILITY LOCATIONS PRIOR TO SAW-CUTTING OR PENETRATING ANY FLOOR SLAB.
17.	OFFER OWNERS REPRESENTATIVE FIRST RIGHT OF REFUSAL OF ALL EQUIPMENT REMOVED FROM SPACE.
18.	PROVIDE CODE-COMPLIANT SUPPORT TO EXISTING-TO-REMAIN UNSUPPORTED CONDUITS AND BOXES WHERE CEILINGS ARE TO BE REMOVED. RE-ROUTE BRANCH CIRCUITS AND RELOCATE JUNCTION BOXES AS REQUIRED TO FACILITATE INSTALLATION OF NEW EQUIPMENT AND SYSTEMS IN CEILING SPACES.

ELECTRICAL ABBREVIATIONS	
ABBREVIATION	DESCRIPTION
(ED)	EXISTING TO BE DEMOLISHED
(EL)	EXISTING DEVICE SHOWN IN NEW LOCATION TO BE REINSTALLED
(EN)	EXISTING TO BE REPLACED WITH NEW.
(ER)	EXISTING TO BE RELOCATED
(EX)	EXISTING TO REMAIN
A, AMP	AMPERES
AF	AMP FRAME - CIRCUIT BREAKER, AMP FUSE - FUSED SWITCH
AFC, AC	ABOVE FINISHED CABINET/COUNTER
AFF	ABOVE FINISHED FLOOR
AG	ABOVE FINISHED GRADE
AFI	ARC FAULT INTERRUPTER
AIC	AMPERE INTERRUPTING CAPACITY
AL	ALUMINUM
ALSI	ARC FLASH ENERGY REDUCTION, LONG TIME, SHORT TIME, INSTANTANEOUS
ALSIG	ARC FLASH ENERGY REDUCTION, LONG TIME, SHORT TIME, INSTANTANEOUS, GROUND FAULT
AT	AMP TRIP
ATS	AUTOMATIC TRANSFER SWITCH
BKR, CB	CIRCUIT BREAKER
CM	CONDUIT
CM	COFFEE MAKER
CPT	CONTROL POWER TRANSFORMER
CR	CRITICAL / CRITICAL BRANCH EMERGENCY
CT	CURRENT TRANSFORMER
CU	COPPER
DISC	DISCONNECT
DIV	DIVISION
DW	DISHWASHER
EC	ELECTRICAL CONTRACTOR
ECB	ENCLOSED CIRCUIT BREAKER
EG	EQUIPMENT GROUND
EM	EMERGENCY
EPO	ELECTRICALLY OPERATED
EPO	EMERGENCY POWER OFF
EQ	EQUIPMENT BRANCH EMERGENCY
EWC	ELECTRIC WATER COOLER
FLA	FULL LOAD AMPS
FWE	FURNISHED WITH EQUIPMENT
S, GND	GROUND
GD	GARBAGE DISPOSAL
GDS	GENERATOR DOCKING STATION
GFI, GFCI	GROUND FAULT INTERRUPTER
GFPE	GROUND FAULT PROTECTION OF EQUIPMENT
H	HORIZONTAL, HORIZONTALLY MOUNTED
HOA	HAND-OFF-AUTO
HP	HORSEPOWER
IAW	IN ACCORDANCE WITH
IS	ISOLATED GROUND
IM	ICE MACHINE
KV	KILOVOLT
KVA	KILOVOLT-AMPERES
KWH	KILOWATT-HOURS
LS	LIFE SAFETY BRANCH EMERGENCY
LSI	LONG TIME, SHORT TIME, INSTANTANEOUS
LSIG	LONG TIME, SHORT TIME, INSTANTANEOUS, GROUND FAULT
LTS	LIGHTS
MCA	MAXIMUM CIRCUIT AMPACITY
MCB	MAIN CIRCUIT BREAKER
MCC	MOTOR CONTROL CENTER
MCP	MECHANICAL CONTROL PANEL
MLO	MAIN LUGS ONLY
MOCB	MAXIMUM OVERCURRENT PROTECTION
MRS	MOTOR RATED SWITCH
MW	MEGAWATT
NC	NORMALLY CLOSED
NEC	NATIONAL ELECTRICAL CODE
NIC	NOT IN CONTRACT
NL	NIGHT LIGHT - FIXTURE CONTROLLED AT BRANCH CIRCUIT BREAKER ONLY
NO	NORMALLY OPEN
NTS	NOT TO SCALE
OC	ON CENTER
P	POLE
PH	PHASE
PNL	PANEL
PT	POTENTIAL TRANSFORMER
RCPT, RCPT	RECEPTACLE
REF	REFRIGERATOR
SPD	SURGE PROTECTION DEVICE
SWBD	SWITCHBOARD
TR	TAMPER-RESISTANT
TYP	TYPICAL
UNO, UON	UNLESS NOTED OTHERWISE
UPS	UNINTERRUPTIBLE POWER SUPPLY
V	VOLTS
VA	VOLT-AMPERES
VB	VIEWBOX
W	WATTS, WIRE
WP	WEATHERPROOF WHILE IN USE COVER
XFMR	TRANSFORMER
XP, EP	EXPLOSION PROOF

STANDARD MOUNTING HEIGHTS	
	<p>1. MOUNTING HEIGHTS SHOWN ARE FROM FINISHED FLOOR TO CENTERLINE OF DEVICE/OUTLET/FIXTURE, UNLESS OTHERWISE NOTED.</p> <p>2. MOUNTING HEIGHTS, WHERE INDICATED, ON FLOOR PLANS, SHALL TAKE PRECEDENCE OVER THESE MOUNTING HEIGHTS. LOCATIONS OF OUTLETS SHOWN ON ARCHITECTURAL ELEVATIONS SHALL TAKE PRECEDENCE OVER THESE MOUNTING HEIGHTS. FIELD LOCATE OUTLETS WITH ARCHITECT DURING ROUGH-IN.</p> <p>3. INSTALL OUTLETS THAT ARE IN CLOSE PROXIMITY ON THE SAME CENTERLINE. OUTLETS THAT ARE WITHIN 2'-0" HORIZONTALLY AND WITHIN 1'-0" VERTICALLY SHALL BE INSTALLED ON THE SAME HORIZONTAL CENTERLINE LOCATED HALF WAY BETWEEN THE HEIGHTS SHOWN. OUTLETS THAT ARE MORE THAN 1'-0" APART VERTICALLY SHALL BE INSTALLED ON THE SAME VERTICAL CENTERLINE.</p> <p>4. MAXIMUM MOUNTING HEIGHT FOR SWITCHES ABOVE A COUNTER TOP 20" DEEP OR LESS IS 48" AFT TO TOP OF BOX. SWITCHES MOUNTED ABOVE COUNTER TOPS DEEPER THAN 20" SHALL BE INSTALLED AT NO MORE THAN 44" ABOVE FINISHED FLOOR TO TOP OF BOX. NOTIFY ARCHITECT WHERE COUNTERTOP PROHIBITS SWITCH INSTALLATION.</p>
NOTES:	

ELECTRICAL INDEX OF DRAWINGS	
SHEET NUMBER	SHEET NAME
E-000	ELECTRICAL LEGEND, SYMBOLS, & NOTES
E-001	ELECTRICAL SPECIFICATIONS
E-002	ELECTRICAL SPECIFICATIONS
E-100	OVERALL LEVEL 0 FLOOR PLAN
E-201	ENLARGED CLINICAL PLANS - LIGHTING & POWER
E-202	ENLARGED NMR 0250 & MRI OFFICE AT110 PLANS - LIGHTING & POWER
E-801	ELECTRICAL STANDARD CIRCUITING AND CONDUIT SIZING SCHEDULES
E-810	PANEL SCHEDULES
E-901	ELECTRICAL DETAILS
TOTAL COUNT: 9	

	A	B	C	D	E	F	G	H	I	J
	ELECTRICAL GENERAL REQUIREMENT.		IDENTIFICATION		ENCLOSED SWITCHES AND CIRCUIT BREAKERS		DRY-TYPE TRANSFORMERS (600 V AND LESS)			
	A.	SCOPE OF WORK: ALL MATERIAL SHALL BE NEW UNLESS OTHERWISE INDICATED. FURNISH ALL LABOR, EQUIPMENT, TECHNICAL SUPERVISION, AND INCIDENTAL SERVICES REQUIRED TO COMPLETE, TEST AND LEAVE READY FOR OPERATION THE ELECTRICAL SYSTEMS AS SPECIFIED AND AS INDICATED ON DRAWINGS.	1.	COMPLY WITH ANSI A13.1, ANSI C2, NFPA 70, AND 29 CFR 1910.145.	A.	SUBJECT TO COMPLIANCE WITH REQUIREMENTS, PROVIDE PRODUCTS BY SQUARE D, EATON, GENERAL ELECTRIC, OR SIEMENS.	A.	SUBJECT TO COMPLIANCE WITH REQUIREMENTS, PROVIDE PRODUCTS BY SQUARE D, EATON, ABB, OR SIEMENS.	1.	PROFESSIONAL SEALS:
	B.	ORDINANCES AND CODES: PERFORM ALL WORK IN ACCORDANCE WITH APPLICABLE FEDERAL, STATE AND LOCAL ORDINANCES AND REGULATIONS, THE RULES AND REGULATIONS OF NFPA, NECA, AND UL UNLESS OTHERWISE INDICATED.	2.	COORDINATE IDENTIFICATION NAMES, ABBREVIATIONS, COLORS, AND OTHER FEATURES WITH REQUIREMENTS IN THE CONTRACT DOCUMENTS, SHOP DRAWINGS, MANUFACTURER'S WIRING DIAGRAMS, AND THE OPERATION AND MAINTENANCE MANUAL, AND WITH THOSE REQUIRED BY CODES, STANDARDS, AND 29 CFR 1910.145. USE CONSISTENT DESIGNATIONS THROUGHOUT PROJECT.	B.	FUSIBLE AND NON-FUSIBLE SWITCHES: NEMA KS 1, QUICK MAKE QUICK-BREAK LOAD INTERRUPTER ENCLOSED KNIFE SWITCH TYPE HD, WITH CLIPS OR BOLT PADS TO ACCOMMODATE SPECIFIED FUSES (IF REQUIRED), EXTERNALLY OPERABLE LOCKABLE HANDLE WITH CAPABILITY TO ACCEPT TWO PADLOCKS, AND INTERLOCKED WITH COVER IN CLOSED POSITION. SQUARE D OR EQUAL.	B.	DESCRIPTION: FACTORY-ASSEMBLED AND TESTED, AIR COOLED, DRY-TYPE TRANSFORMER RATED FOR 60 HZ OPERATION. COMPLY WITH NEMA ST 20, AND LIST AND LABEL AS COMPLYING WITH UL 1561.	2.	
1	C.	UNLESS OTHERWISE INDICATED, ALL REQUIRED PERMITS, LICENSES, INSPECTIONS, APPROVALS AND FEES FOR ELECTRICAL WORK SHALL BE SECURED AND PAID FOR BY THE CONTRACTOR. ALL WORK SHALL CONFORM TO ALL APPLICABLE CODES, RULES AND REGULATIONS.	3.	COORDINATE INSTALLATION OF IDENTIFYING DEVICES WITH COMPLETION OF COVERING AND PAINTING OF SURFACES WHERE DEVICES ARE TO BE APPLIED, WITH LOCATION OF ACCESS PANELS AND DOORS.	C.	TOGGLE DISCONNECT SWITCH: HEAVY DUTY, 30A, 600 VOLT, DOUBLE OR THREE POLE AS REQUIRED, SINGLE THROW, MOTOR RATED SWITCH WITHOUT OVERLOAD PROTECTION. PROVIDE NEMA 1 ENCLOSURE AND PADLOCK ATTACHMENT.	C.	INDOOR ENCLOSURE: VENTILATED, NEMA 250, TYPE 2. PROVIDE LIFTING EYES OR BRACKETS.	3.	
	D.	THE DRAWINGS SHOW THE LOCATION AND GENERAL ARRANGEMENT OF EQUIPMENT, ELECTRICAL SYSTEMS AND RELATED ITEMS. THEY SHALL BE FOLLOWED AS CLOSELY AS ELEMENTS OF NEW CONSTRUCTION WILL PERMIT.	4.	INSTALL IDENTIFYING DEVICES BEFORE INSTALLING ACOUSTICAL CEILINGS AND SIMILAR CONCEALMENT.	D.	COMPLY WITH APPLICABLE PORTIONS OF NECA 1, NEMA PB 1.1, AND NEMA PB 2.1 FOR INSTALLATION OF ENCLOSED SWITCHES AND CIRCUIT BREAKERS.	D.	OUTDOOR ENCLOSURE: VENTILATED, RAIN-TIGHT, NEMA 250, TYPE 3R. PROVIDE LIFTING EYES OR BRACKETS.	4.	
	E.	EXAMINE THE DRAWINGS OF OTHER TRADES AND VERIFY THE CONDITIONS GOVERNING THE WORK ON THE JOB SITE. ARRANGE WORK ACCORDINGLY, PROVIDING LABOR AND MATERIALS AS MAY BE REQUIRED TO MEET SUCH CONDITIONS.	5.	USE THE COLORS USED BELOW FOR UNGROUNDED SERVICE, FEEDER, AND BRANCH-CIRCUIT CONDUCTORS: 1. COLOR SHALL BE FACTORY APPLIED OR, FOR SIZES LARGER THAN NO. 10 AWG IF AUTHORITIES HAVING JURISDICTION PERMIT, FIELD APPLIED. 2. COLORS FOR 208/120-V CIRCUITS a. PHASE A: BLACK b. PHASE B: RED c. PHASE C: BLUE d. NEUTRAL: WHITE 3. COLORS FOR 480/277-V CIRCUITS: a. PHASE A: BROWN b. PHASE B: ORANGE c. PHASE C: YELLOW d. NEUTRAL: GRAY 4. FIELD-APPLIED, COLOR-CODING CONDUCTOR TAPE APPLY IN HALF-LAPPED TURNS FOR A MINIMUM DISTANCE OF 8 INCHES FROM TERMINAL POINTS AND IN BOXES WHERE SPLICES OR TAPS ARE MADE. APPLY LAST TWO TURNS OF TAPE WITH NO TENSION TO PREVENT POSSIBLE UNWINDING. LOCATE BANDS TO AVOID OBSCURING FACTORY CABLE MARKINGS.	E.	PANELBOARDS A. SUBJECT TO COMPLIANCE WITH REQUIREMENTS, PROVIDE PRODUCTS BY SQUARE D, EATON, ABB, OR SIEMENS. B. COORDINATE LAYOUT AND INSTALLATION OF PANELBOARDS AND COMPONENTS WITH OTHER CONSTRUCTION THAT PENETRATES WALLS OR IS SUPPORTED BY THEM, INCLUDING ELECTRICAL AND OTHER TYPES OF EQUIPMENT, RACEWAYS, PIPING, AND ENCUMBRANCES TO NFPA 70 DEDICATED AND WORKSPACE CLEARANCE REQUIREMENTS. C. PHASE AND GROUND BUSES SHALL BE HARD-DRAWN COPPER, 98 PERCENT CONDUCTIVITY. D. SERVICE EQUIPMENT LABEL: UL LABELED FOR USE AS SERVICE EQUIPMENT FOR PANELBOARDS WITH MAIN SERVICE DISCONNECT SWITCHES. E. SHORT-CIRCUIT RATING: FULLY RATED TO INTERRUPT SYMMETRICAL SHORT-CIRCUIT CURRENT AVAILABLE AT TERMINALS. F. INSTALL PANELBOARDS AND ACCESSORIES ACCORDING TO NEMA PB 1.1. G. MOUNT TOP OF TRIM 74 INCHES (18130 MM) ABOVE FINISHED FLOOR, UNLESS OTHERWISE INDICATED.	E.	INSULATION CLASS (15 KVA AND LARGER): 220 DEG C, UL-COMPONENT-RECOGNIZED INSULATION SYSTEM WITH A MAXIMUM OF 115 DEG C RISE ABOVE 40 DEG C AMBIENT TEMPERATURE. F. BASIC IMPULSE LEVEL 10 KV. G. TAPS FOR TRANSFORMERS 7.5 TO 24 KVA: ONE 5 PERCENT TAP ABOVE AND ONE 5 PERCENT TAP BELOW NORMAL FULL CAPACITY. H. TAPS FOR TRANSFORMERS 25 KVA AND LARGER: TWO 2.5 PERCENT TAPS ABOVE AND TWO 2.5 PERCENT TAPS BELOW NORMAL FULL CAPACITY. I. CASE TEMPERATURE DO NOT EXCEED 35 DEGREES C RISE ABOVE AMBIENT AT WARMEST POINT. J. CORES GRAIN-ORIENTED, NON-AGING SILICON STEEL. K. COILS: CONTINUOUS WINDINGS WITHOUT SPLICES, EXCEPT FOR TAPS; INTERNAL COIL CONNECTIONS BRAZED OR PRESSURE TYPE; COIL MATERIAL ALUMINUM. L. VIBRATION ISOLATION: ISOLATE CORE AND COIL FROM ENCLOSURE USING VIBRATION-ABSORBING MOUNTS. M. GROUNDING: GROUND CORE AND COIL ASSEMBLY TO ENCLOSURE BY MEANS OF A VISIBLE FLEXIBLE COPPER GROUNDING STRAP. N. TEST AND INSPECT TRANSFORMERS ACCORDING TO IEEE C57.12.91.	5.	
	F.	COORDINATE ARRANGEMENT, MOUNTING AND SUPPORT OF ELECTRICAL EQUIPMENT WITH OTHER TRADES.	6.	WIRING DEVICES: USE ADHESIVE LABEL, WITH BLACK, RED FOR EMERGENCY, FILM LETTERING ON FACE OF WALL PLATE AND DURABLE WIRE MARKERS OR TAGS INSIDE OUTLET BOXES. LABELS SHALL BE CLEAR POLYESTER WITH BLACK LETTER, RED LETTER FOR EMERGENCY, FONT SIZE OF 7. IDENTIFY PANELBOARD AND CIRCUIT NUMBER FROM WHICH SERVED.	F.	LOAD BALANCING: AFTER SUBSTANTIAL COMPLETION, BUT NOT MORE THAN 60 DAYS AFTER FINAL ACCEPTANCE, MEASURE LOAD BALANCING AND MAKE CIRCUIT CHANGES. K. ON COMPLETION OF INSTALLATION, INSPECT INTERIOR AND EXTERIOR OF PANELBOARDS. REMOVE PAINT SPLATTERS AND OTHER SPOTS. VACUUM DIRT AND DEBRIS. DO NOT USE COMPRESSED AIR TO ASSIST IN CLEANING. REPAIR EXPOSED SURFACES TO MATCH ORIGINAL FINISH. L. DISTRIBUTION PANELBOARDS 1. DOORS: SECURED WITH VAULT-TYPE LATCH WITH TUMBLER LOCK; KEYS ALIKE OMIT FOR FUSED-SWITCH PANELBOARDS. 2. MAIN OVERCURRENT PROTECTIVE DEVICES: AS INDICATED ON DRAWING. 3. BRANCH OVERCURRENT PROTECTIVE DEVICES: a. FOR CIRCUIT-BREAKER FRAME SIZES 125A AND SMALLER: BOLT-ON CIRCUIT BREAKERS. b. FOR CIRCUIT-BREAKER FRAME SIZES LARGER THAN 125A BOLT-ON CIRCUIT BREAKERS; PLUG-IN CIRCUIT BREAKERS WHERE INDIVIDUAL POSITIVE-LOCKING DEVICE REQUIRES MECHANICAL RELEASE FOR REMOVAL. c. FUSED SWITCHES. M. LIGHTING AND APPLIANCE BRANCH-CIRCUIT PANELBOARDS 1. BRANCH OVERCURRENT PROTECTIVE DEVICES: BOLT-ON CIRCUIT BREAKERS, REPLACEABLE WITHOUT DISTURBING ADJACENT UNITS. N. SURGE SUPPRESSION PANELBOARDS 1. BUS COPPER PHASE AND NEUTRAL BUSES: 200 PERCENT CAPACITY NEUTRAL BUS AND LUGS. 2. SURGE SUPPRESSION DEVICE: IEEE C62.41, INTEGRALLY MOUNTED, DIRECT BUS CONNECTED, SOLID-STATE, PARALLEL-CONNECTED, SINE-WAVE TRACKING SUPPRESSION AND FILTERING MODULES. O. MOLDED-CASE CIRCUIT BREAKERS UL 489, WITH INTERRUPTING CAPACITY TO MEET AVAILABLE FAULT CURRENTS. 1. THERMAL-MAGNETIC CIRCUIT BREAKERS INVERSE TIME-CURRENT ELEMENT FOR LOW-LEVEL OVERLOADS, AND INSTANTANEOUS MAGNETIC TRIP ELEMENT FOR SHORT CIRCUITS. ADJUSTABLE MAGNETIC TRIP SETTING FOR CIRCUIT-BREAKER FRAME SIZES 250 A AND LARGER WITH RESTRICTED ACCESS COVER. P. MOLDED-CASE CIRCUIT-BREAKER FEATURES AND ACCESSORIES: 1. LUGS MECHANICAL, STYLE, SUITABLE FOR NUMBER, SIZE, TRIP RATINGS, AND CONDUCTOR MATERIALS. 2. APPLICATION USING: APPROPRIATE FOR APPLICATION; TYPE SWJ FOR SWITCHING FLUORESCENT LIGHTING LOADS; TYPE HACR FOR HEATING, AIR-CONDITIONING, AND REFRIGERATING EQUIPMENT. 3. GROUND-FAULT PROTECTION: INTEGRALLY MOUNTED RELAY AND TRIP UNIT WITH ADJUSTABLE PICKUP AND TIME-DELAY SETTINGS, PUSH-TO-TEST FEATURE, AND GROUND-FAULT INDICATOR. 4. SHUNT TRIP: 120-V TRIP COIL ENERGIZED FROM SEPARATE CIRCUIT, SET TO TRIP AT 75 PERCENT OF RATED VOLTAGE. 5. TANDEM CIRCUIT BREAKERS ARE NOT PERMITTED. 6. PROVIDE CIRCUIT BREAKERS UL LISTED AS TYPE GFPECI FOR ALL SELF REGULATING HEATING (SNOW MELTING AND HEAT TRACE) CABLES BRANCH CIRCUITS. 7. PROVIDE LOCK ON DEVICES FOR CIRCUIT BREAKERS WHEN CALLED OUT ON PANEL SCHEDULES WITH "LOD" DESIGNATION AND WHERE REQUIRED FOR FIRE ALARM BRANCH CIRCUITS. 8. PROVIDE GROUND FAULT INTERRUPT 5MA CIRCUIT BREAKER WHEN CALLED OUT ON PANEL SCHEDULES. 9. PROVIDE SHUNT TRIP BREAKERS WHEN CALLED OUT ON PANEL SCHEDULES. Q. FUSED SWITCH: NEMA KS 1, TYPE HD, CLIPS TO ACCOMMODATE SPECIFIED FUSES, LOCKABLE HANDLE. R. ENCLOSURES: MOUNTING AS NOTED ON PANEL SCHEDULES. 1. NEMA PB 1, RATED FOR ENVIRONMENTAL CONDITIONS AT INSTALLED LOCATION. a. INDOOR DRY LOCATIONS NEMA 250, TYPE 1. b. OUTDOOR LOCATIONS NEMA 250, TYPE 3R. c. OTHER WET OR DAMP INDOOR LOCATIONS: NEMA 250, TYPE 4. 2. CABINET FRONT: FLUSH OR SURFACE CABINET AS NOTED ON THE DRAWINGS, WITH FRONT WITH CONCEALED TRIM CLAMPS, PIANO TYPE HINGED DEAD FRONT COVER, HINGED DOOR, AND FLUSH LOCK AL KEYED ALIKE 3. DIRECTORY CARD WITH TRANSPARENT PROTECTIVE COVER, MOUNTED IN METAL FRAME INSIDE PANELBOARD DOOR.	F.	CASE TEMPERATURE DO NOT EXCEED 35 DEGREES C RISE ABOVE AMBIENT AT WARMEST POINT. J. CORES GRAIN-ORIENTED, NON-AGING SILICON STEEL. K. COILS: CONTINUOUS WINDINGS WITHOUT SPLICES, EXCEPT FOR TAPS; INTERNAL COIL CONNECTIONS BRAZED OR PRESSURE TYPE; COIL MATERIAL ALUMINUM. L. VIBRATION ISOLATION: ISOLATE CORE AND COIL FROM ENCLOSURE USING VIBRATION-ABSORBING MOUNTS. M. GROUNDING: GROUND CORE AND COIL ASSEMBLY TO ENCLOSURE BY MEANS OF A VISIBLE FLEXIBLE COPPER GROUNDING STRAP. N. TEST AND INSPECT TRANSFORMERS ACCORDING TO IEEE C57.12.91. O. VERIFY THAT FIELD MEASUREMENTS ARE AS NEEDED TO MAINTAIN WORKING CLEARANCES REQUIRED BY NFPA 70 AND MANUFACTURER'S WRITTEN INSTRUCTIONS. P. RECORD TRANSFORMER SECONDARY VOLTAGE AT EACH UNIT FOR AT LEAST 48 HOURS OF TYPICAL OCCUPANCY PERIOD. ADJUST TRANSFORMER TAPS TO PROVIDE OPTIMUM VOLTAGE CONDITIONS AT SECONDARY TERMINALS. FUSES A. OBTAIN FUSES FROM A SINGLE MANUFACTURER. B. COORDINATE FUSE RATINGS WITH UTILIZATION EQUIPMENT NAMEPLATE LIMITATIONS OF MAXIMUM FUSE SIZE. C. EXAMINE UTILIZATION EQUIPMENT NAMEPLATES AND INSTALLATION INSTRUCTIONS. INSTALL FUSES OF SIZES AND WITH CHARACTERISTICS APPROPRIATE FOR EACH PIECE OF EQUIPMENT. D. INSTALL LABELS INDICATING FUSE REPLACEMENT INFORMATION ON INSIDE DOOR OF EACH FUSED SWITCH. E. SUBJECT TO COMPLIANCE WITH REQUIREMENTS, PROVIDE PRODUCTS BY COOPER BUSMAN, INC. OR EQUAL. F. CARTRIDGE FUSES: NEMA FU 1, NONRENEWABLE CARTRIDGE FUSE, CLASS AND CURRENT RATING INDICATED; VOLTAGE RATING CONSISTENT WITH CIRCUIT VOLTAGE 1. SERVICE ENTRANCE: CLASS L, TIME DELAY. 2. FEEDERS: CLASS RK5, TIME DELAY. 3. MOTOR BRANCH CIRCUITS: CLASS RK1, TIME DELAY. 4. OTHER BRANCH CIRCUITS: CLASS RK1, TIME DELAY. 5. UL F152 FUSEHOLDERS. LIGHTING A. PROVIDE LIGHTING FIXTURES AS INDICATED ON DRAWINGS. B. INSTALL DRIVERS/BALLASTS, AND SPECIFIED ACCESSORIES AT FACTORY. FOR FIXTURES CONTAINING LAMPS, INSTALL ON PROJECT SITE AFTER FIXTURE INSTALLATION. C. FIXTURES SET LEVEL, PLUMB, AND SQUARE WITH CEILINGS AND WALLS. INSTALL LAMPS IN EACH FIXTURE WHERE REQUIRED. D. SUPPORT LUMINAIRES INDEPENDENT OF CEILING FRAMING. SUPPORT RECESSED GRID LUMINAIRES FROM TWO OPPOSITE CORNERS DIRECTLY TO STRUCTURE. WIRE OR ROD SHALL HAVE BREAKING STRENGTH OF THE WEIGHT OF FIXTURE AT A SAFETY FACTOR OF 3. E. INSTALL RECESSED LUMINAIRES TO PERMIT REMOVAL FROM BELOW. F. INSTALL RECESSED LUMINAIRES USING ACCESSORIES AND FIRE STOPPING MATERIALS TO MEET REGULATORY REQUIREMENTS FOR FIRE RATING. G. INSTALL SURFACE MOUNTED LUMINAIRES AND EXIT SIGNS PLUMB AND ADJUST TO ALIGN WITH BUILDING LINES AND WITH EACH OTHER. SECURE TO PROHIBIT MOVEMENT. H. TIGHTEN ELECTRICAL CONNECTORS AND TERMINALS ACCORDING TO MANUFACTURER'S PUBLISHED TORQUE-TIGHTENING VALUES. IF MANUFACTURER'S TORQUE VALUES ARE NOT INDICATED, USE THOSE SPECIFIED IN UL 486A AND UL 486B. I. MAKE WIRING CONNECTIONS TO BRANCH CIRCUIT USING BUILDING WIRE WITH INSULATION SUITABLE FOR TEMPERATURE CONDITIONS WITHIN LUMINAIRE J. BOND PRODUCTS AND METAL ACCESSORIES TO BRANCH CIRCUIT EQUIPMENT GROUNDING CONDUCTOR. K. CONNECT LUMINAIRES TO BRANCH CIRCUIT OUTLET BOXES PROVIDED UNDER RACEWAYS AND BOXES SECTION USING 1/2" FLEXIBLE CONDUIT OF NO MORE THAN 6'-0" IN LENGTH. L. CLEAN ELECTRICAL PARTS TO REMOVE CONDUCTIVE AND DELETERIOUS MATERIALS. M. REMOVE DIRT AND DEBRIS FROM ENCLOSURES AND LENSES. N. CLEAN PHOTOMETRIC CONTROL SURFACES AS RECOMMENDED BY MANUFACTURER. O. CLEAN FINISHES AND TOUCH UP DAMAGE. P. EACH LED LUMINAIRE TYPE SHALL BE BINNED WITHIN A THREE-STEP MACADAM ELLIPSE TO ENSURE COLOR CONSISTENCY AMONG LUMINAIRES AND CONTAIN INTERNAL DRIVER UNLESS NOTED OTHERWISE. Q. EMERGENCY LOAD TRANSFER DEVICE LOCALIZED LOAD TRANSFER SWITCH TO SENSE NORMAL PRESENCE OF NORMAL POWER FOR SWITCHED CIRCUITS AND SWITCH LUMINAIRE OVER TO EMERGENCY SOURCE UPON LOSS OF NORMAL SOURCE. DEVICE SHALL BE INSTALLED INTEGRAL TO LUMINAIRE OR MOUNTED REMOTELY AS APPLICATION REQUIRED. UL 924 LISTED, INTEGRAL TEST SWITCH AND INDICATING LAMPS TO INDICATE STATUS; BODINE BLDG SERIES OR EQUAL BY LVS OR CHLORIDE. R. EXIT SIGNS: COMPLY WITH UL 924; FOR SIGN COLORS AND LETTERING SIZE, COMPLY WITH AUTHORITIES HAVING JURISDICTION. 1. PROVIDE EXIT SIGNS WIN LIGHT-EMITTING DIODES, 70,000 HOURS MINIMUM OF RATED LAMP LIFE 2. SELF-POWERED EXIT SIGNS (BATTERY TYPE); INTEGRAL AUTOMATIC CHARGER IN A SELF-CONTAINED POWER PACK. 3. BATTERY: SEALED, MAINTENANCE-FREE NICKEL-CADMIUM TYPE WITH SPECIAL WARRANTY. 4. CHARGER: FULLY AUTOMATIC, SOLID-STATE TYPE WITH SEALED TRANSFER RELAY. 5. OPERATION: RELAY AUTOMATICALLY ENERGIZES LAMP FROM BATTERY WHEN CIRCUIT VOLTAGE DROPS TO 80 PERCENT OF NOMINAL VOLTAGE OR BELOW. WHEN NORMAL VOLTAGE IS RESTORED, RELAY DISCONNECTS LAMPS FROM BATTERY, AND BATTERY IS AUTOMATICALLY RECHARGED AND FLOATED ON CHARGER. S. EMERGENCY LIGHTING UNITS SELF-CONTAINED UNITS COMPLYING WITH UL 924. 1. BATTERY: SEALED, MAINTENANCE-FREE LEAD-ACID TYPE WITH MINIMUM 10-YEAR NOMINAL LIFE AND SPECIAL WARRANTY. 2. CHARGER: FULLY AUTOMATIC, SOLID-STATE TYPE WITH SEALED TRANSFER RELAY. 3. OPERATION: RELAY AUTOMATICALLY TURNS LAMP ON WHEN POWER SUPPLY CIRCUIT VOLTAGE DROPS TO 80 PERCENT OF NOMINAL VOLTAGE OR BELOW. WHEN NORMAL VOLTAGE IS RESTORED, RELAY DISCONNECTS LAMPS FROM BATTERY, AND BATTERY IS AUTOMATICALLY RECHARGED AND FLOATED ON CHARGER. T. WIRE GUARD: WHERE INDICATED, HEAVY-CHROME-PLATED WIRE GUARD PROTECTS LAMP HEADS OR FIXTURES. 5. INTEGRAL TIME-DELAY RELAY: HOLDS UNIT ON FOR FIXED INTERVAL WHEN POWER IS RESTORED AFTER AN OUTAGE TIME DELAY PERMITS HIGH-INTENSITY-DISCHARGE LAMPS TO RE-STRIKE AND DEVELOP ADEQUATE OUTPUT.		



PROJECT PARTNERS:

☐ APPROVED FOR CONSTRUCTION
☒ NOT APPROVED FOR CONSTRUCTION

CLIENT INFORMATION:

Wayne State University



CLIENT PROJECT #:	PROJECT NUMBER
JHA PROJECT #:	PROJECT NUMBER

PROJECT INFORMATION:

PROJECT INFORMATION:

WSU APPLEBAUM
MRI

259 MACK AVE
DETROIT, MICHIGAN
48201

48201	
SSOE PROJECT #:	023-03727-00
SSOE MANAGER:	JEFF FALZON

00 000000


SSOE®
1001 Madison Avenue
Toledo, OH 43604
T. (419) 255-3830






THIS DRAWING IS THE PROPERTY OF SSOE GROUP. UNAUTHORIZED USE OF ANY KIND,
INCLUDING USE ON OTHER PRODUCTS, IS PROHIBITED.

THIS DRAWING IS THE PROPERTY OF S&B GROUP. UNAUTHORIZED USE OF ANY KIND, INCLUDING USE ON OTHER PROJECTS, IS PROHIBITED.

7 OVERALL LEVEL 0 FLOOR
PLAN

E-100





LIGHTING FIXTURE SCHEDULE										
TYPE	MFR	MODEL	CCT	LAMP	LUMENS	MOUNTING	VOLTAGE	WATTS	COMMENTS	NOTES
FL	LITHONIA	BLT	3500 K	LED, 4000K	8746 lm			43 W	2'x4' RECESSED LED DECORATIVE LUMINAIRE SUITABLE FOR INSTALLATION IN A LAY-IN CEILING SYSTEM. SMOOTH FROSTED ACRYLIC LENS. FIXTURE COMPLETE WITH 0-10V DIMMING DRIVER DOWN TO 1%.	

MECHANICAL EQUIPMENT CONNECTION SCHEDULE									
MARK	FLA	MCA	MOCP	VOLTAGE	PHASE	CIRCUIT	WIRE & CONDUIT	DISCONNECT SIZE/TYPE	NOTES
CHW-1	48.3 A	53.0 A	70.0 A	480 V	3	(EX) DP-BB-1	3#4, #8 G, IN 1-1/4" C	NEMA 3F FUSIBLE 100A/70AF/3P	1.2

MECHANICAL EQUIPMENT CONNECTION SCHEDULES NOTES

1. PROVIDE MOUNTING HARDWARE FOR DISCONNECT. COORDINATE EXACT MOUNTING LOCATION IN FIELD. REFER TO CHILLER VENDOR DRAWINGS FOR MORE INFORMATION.
2. PROVIDE DEDICATED 120V 20A CIRCUIT (#12, #12 G, IN 3/4" C, 20A BREAKER) FROM NEAREST 208/120V POWER PANEL ON LEVEL 1 FOR SERVICE GFCI WEATHERPROOF RECEPTACLE AND SERVICE LIGHT FIXTURE COMBO. RECEPTACLE AND LIGHT FIXTURE COMBO SHALL BE ADJACENT TO UNIT - NOT FARTHER THAN 25'-0" AS PER NEC 210.63.

GENERAL NOTES - LIGHTING

- A. REFER TO ARCHITECTURAL REFLECTED CEILING PLANS FOR EXACT LOCATION OF ALL LIGHTING FIXTURES UNLESS NOTED OTHERWISE.
- B. REFER TO THE LUMINAIRE SCHEDULE LOCATED ON THE ELECTRICAL GENERAL INFORMATION DRAWING.
- C. ELECTRICAL DEVICES INDICATED ON THIS PLAN SHALL BE NEW UNLESS NOTED OTHERWISE.
- D. LIGHT SWITCHES SHALL BE GROUPED UNDER ONE COMMON FACEPLATE WHERE MORE THAN ONE LIGHT SWITCH IS INDICATED TO BE INSTALLED AT THE SAME LOCATION.
- E. LIGHTING BRANCH CIRCUIT WIRING ASSOCIATED WITH NEW LIGHTING SHALL BE 2#12, 1#12GND IN 3/4" CLESS NOTED OTHERWISE.
- F. EXISTING EQUIPMENT/DEVICES NOT SPECIFICALLY INDICATED TO BE DEMOLISHED SHALL REMAIN OPERATIONAL. REVISE EXISTING CIRCUITRY TO MAINTAIN OPERATION TO SUCH EQUIPMENT/DEVICES AS REQUIRED.
- G. REUSE OF THE LEFT-IN-PLACE EXISTING BRANCH CIRCUIT CONDUIT AND WIRING ASSOCIATED WITH THE LIGHTING FIXTURES REMOVED DURING DEMOLITION TO REFEED NEW LIGHTING FIXTURES IS ACCEPTABLE. REWORK THE EXISTING CIRCUIT TO PROVIDE LIGHTING CONTROL AS INDICATED ON THIS DRAWING. UNLESS NOTED OTHERWISE.
- H. EXISTING LIGHTING INDICATED AS TO REMAIN AND LOCATED IN AREAS WHERE THE CEILING IS BEING MODIFIED SHALL BE TEMPORARILY SUPPORTED AND REINSTALLED UPON COMPLETION OF CEILING REVISIONS. COORDINATE WITH ARCHITECTURAL REFLECTED CEILING PLANS AND ARCHITECTURAL TRADE.
- I. NIGHT LIGHT AND EXIT SIGNS SHALL BE UNCONTROLLED AND CONNECTED AHEAD OF THE LOCAL LIGHTING CONTROL.
- J. CONDUITS INSTALLED IN FINISHED AREAS SHALL BE ROUTED CONCEALED UNLESS NOTED OTHERWISE.
- K. EXIT SIGN FIXTURES ARE TYPE 'XI' UNLESS NOTED OTHERWISE.

GENERAL NOTES - POWER

- A. REFER TO ARCHITECTURAL FLOOR PLAN AND ELEVATIONS FOR EXACT LOCATION OF DEVICES WHERE INDICATED.
- B. RECEPTACLE OUTLETS SHALL BE RATED 20A U.O.N.
- C. DISCONNECT SWITCHES SHALL BE HEAVY DUTY TYPE U.O.N.
- D. PROVIDE GFCI PROTECTION WHERE REQUIRED BY THE NEC WHETHER INDICATED OR NOT.
- E. BRANCH CIRCUIT JUNCTION BOXES SHALL BE LABELED WITH THE CIRCUITS ENCLOSED.
- F. SINGLE PHASE 20A BRANCH CIRCUIT WIRING SHALL BE 2#12, 1#12MID IN 3/4" UNLESS NOTED OTHERWISE.
- G. EXISTING EQUIPMENT/DEVICES NOT SPECIFICALLY INDICATED TO BE DEMOLISHED SHALL REMAIN OPERATIONAL. REVISE EXISTING CIRCUITING TO MAINTAIN OPERATION TO SUCH EQUIPMENT/DEVICES AS REQUIRED.
- H. CONDUITS SHALL BE ROUTED CONCEALED UNLESS NOTED OTHERWISE.
- I. ELECTRICAL EQUIPMENT MOUNTED ON THE FLOOR SHALL BE MOUNTED ON A 4" CONCRETE HOUSEKEEPING PAD.
- J. PROVIDE HOSPITAL GRADE RECEPTACLE OUTLETS.
- K. PROVIDE A METAL RACEWAY SYSTEM, METALLIC CABLE ARMOR, OR SHEATH ASSEMBLY THAT QUALIFIES AS AN EQUIPMENT GROUND CONDUCTOR IN ACCORDANCE WITH SECTION 250.118 OF THE NATIONAL ELECTRICAL CODE AS REQUIRED BY SECTION 517.13 OF THE NEC. AN INSULATED EQUIPMENT GROUND CONDUCTOR SHALL BE PROVIDED IN ADDITION AS INDICATED IN SECTION 517.13 OF THE NEC.
- ## PLAN NOTES
- ED01 RELOCATE PANEL "RP-NRM" TO NEW NRM ROOM. INTERCEPT AND EXTEND EXISTING PANELBOARD FEEDER FROM 45KVA 240D/120V TRANSFORMER ON MAIN STREET LEVEL ELECTRICAL ROOM 0448.
- ED02 RELOCATE EXISTING 30A NON-FUSED DISCONNECT SWITCH AND ASSOCIATED L6-20 RECEPTACLE FOR RELOCATED NRM.
- ED03 DEMOLISH UPS ASSOCIATED FEEDERS, CONDUIT, DEVICES, AND SUPPORTS BACK TO SOURCE. RETURN ALL BREAKERS ASSOCIATED WITH DEMOLISHED UPS TO SPARE AND UPDATE PANEL SCHEDULES ACCORDINGLY.
- ED04 DEMOLISH NITROGEN GENERATOR ASSOCIATED FEEDERS, CONDUIT, DEVICES, AND SUPPORTS BACK TO SOURCE. RETURN ALL BREAKERS ASSOCIATED WITH DEMOLISHED NITROGEN GENERATOR TO SPARE AND UPDATE PANEL SCHEDULES ACCORDINGLY.
- EPO3 REFER TO NRM VENDOR'S DRAWINGS FOR ALL FINAL LOCATIONS, MOUNTING HEIGHTS, DEVICES, WIRING CONNECTIONS, SUPPORTS, PULL BOXES, ELECTRICAL EQUIPMENT, DUCTS, CABLE PULLS AND RACEWAY ROUTING AND SIZES.
- EPOS NEW 225KVA ISOLATION TRANSFORMER FOR NRM PANEL. STACK ON TOP OF EXISTING TRANSFORMER "A" LOCATED IN THIS ROOM. REFER TO DETAIL 3 ON E-001.

PLAN NOTES

- ED01 RELOCATE PANEL RP-NMR* TO NEW NRM ROOM. INTERCEPT AND EXTEND EXISTING PANELBOARD FEEDER FROM 45KVA 2400/120V TRANSFORMER ON MAIN STREET LEVEL ELECTRICAL ROOM 0468.
- ED02 RELOCATE EXISTING 30A NON-FUSED DISCONNECT SWITCH AND ASSOCIATED L6-20 RECEPTACLE FOR RELOCATED NMR.
- ED03 DEMOLISH UPS ASSOCIATED FEEDERS, CONDUIT, DEVICES, AND SUPPORTS BACK TO SOURCE. RETURN ALL BREAKERS ASSOCIATED WITH DEMOLISHED UPS TO SPARE AND UPDATE PANEL SCHEDULES ACCORDINGLY.
- ED04 DEMOLISH NITROGEN GENERATOR ASSOCIATED FEEDERS, CONDUIT, DEVICES, AND SUPPORTS BACK TO SOURCE. RETURN ALL BREAKERS ASSOCIATED WITH DEMOLISHED NITROGEN GENERATOR TO SPARE AND UPDATE PANEL SCHEDULES ACCORDINGLY.
- EP03 REFER TO MRI VENDORS' DRAWINGS FOR ALL FINAL LOCATIONS, MOUNTING HEIGHTS, DEVICES, WIRING, CONNECTIONS, SUPPORTS, PULL BOXES, ELECTRICAL EQUIPMENT, DUCTS, CABLE PULLS AND RACEWAY ROUTING AND SIZE.
- EP05 NEW 225KVA ISOLATION TRANSFORMER FOR MRI PANEL. STACK ON TOP OF EXISTING TRANSFORMER 'TA' LOCATED IN THIS ROOM. REFER TO DETAIL 3 ON E-901.



PROFESSIONAL SEALS:

PROJECT PARTNERS:

[illegible]

☐ APPROVED FOR CONSTRUCTION
☒ NOT APPROVED FOR CONSTRUCTION

CLIENT INFORMATION:

Wayne State University



**WAYNE STATE
UNIVERSITY**

5454 CASS AVE
DETROIT, MICHIGAN
48202

CLIENT PROJECT #:	PROJECT NUMBER
JHA PROJECT #:	PROJECT NUMBER

PROJECT INFORMATION:

PROJECT INFORMATION:

SULL'ADDETERMINAZIONE

WSU APPLEBAUM
MRI

259 MACK AVE
DETROIT, MICHIGAN
48201

SSOE PROJECT #: 023-03727-00

SSOE MANAGER: JEFF FALZON





88 6600®

1001 Madison Avenue
Toledo, OH 43604
T. (419) 255-3830


THIS DRAWING IS THE PROPERTY OF ESSE GROUP. UNAUTHORIZED USE OF ANY KIND,
INCLUDING USE ON OTHER PROJECTS, IS PROHIBITED.

ENLARGED CLINICAL PLANS - LIGHTING & POWER


E-201




DETAIL
DOUBLE DOOR SWITCH & LATCH
RETRACTION (DELAYED EGRESS)
NO SCALE




DETAIL
SECURITY - SINGLE RIGHT HAND DOOR
NO SCALE




DETAIL
SECURITY - SINGLE LEFT HAND DOOR
NO SCALE



4 RECESSED GRID TROFFER LIGHT FIXTURE INSTALLATION
E-901 SCALE: NOT TO SCALE




- NOTES:
1. STACK THE NEW TRANSFORMER ABOVE THE EXISTING. THIS DETAIL SHOW THE DESIGN INTENT. COORDINATE IN THE FIELD.
 2. PROVIDE THOMAS & BETTS SUPERSTRUT OR EQUIVALENT.
 3. ALL PART NUMBERS SHOWN ARE THOMAS & BETTS SUPERSTRUT.



DETAIL
SECURITY
RACEWAY SYSTEM
NO SCALE

- SECURITY DOOR NOTES:**
1. ENTRANCE AND EGRESS CONTROL SYSTEM SHALL COMPLY WITH INTERNATIONAL BUILDING CODE, AND NFPA LIFE SAFETY CODE #101, AND ANY LOCAL CODES.
 2. A SENSOR ON THE EGRESS SIDE DETECTING APPROACHING OCCUPANTS IN THE PATH OF THE EGRESS, OR LOSS OF POWER TO THE SENSOR, MUST UNLOCK THE DOOR.
 3. LOSS OF POWER TO THE MAGNETIC LOCK MUST UNLOCK DOOR.
 4. A MANUAL "PUSH-TO-EXIT" BUTTON MUST BE PROVIDED 42" ON CENTER ABOVE DOOR, WITHIN 5' OF DOOR, AND ON THE SAME PLANE AS THE DOOR. IF POSSIBLE, THE BUTTON SHOULD BE 54" HIGH.
 5. "PUSH-TO-EXIT" BUTTON WHEN OPERATED MUST UNLOCK DOOR FOR NOT LESS THAN 30 SECONDS, INDEPENDENT OF ACCESS CONTROL SYSTEM.
 6. ACTIVATION OF FIRE ALARM OR SPRINKLER SYSTEM, IF PROVIDED, MUST UNLOCK DOOR AND REMAIN UNLOCKED UNTIL SYSTEM HAS BEEN MANUALLY RESET.
 7. IF WIRE IS NOT PROVIDED, EACH CONDUIT MUST CONTAIN PULL STRING FROM DEVICE LOCATION TO 4" JUNCTION BOX ABOVE DOOR.
 8. DRILL 1" TRUE IN DIAMETER HOLE FOR DOOR CONTACT IN FRAME 6" FROM STRIKE SIDE OF DOOR.
 9. PULL WIRE THROUGH HOLLOW METAL FRAME TO STRIKE OR INSTALL CONDUIT FOR Poured FRAME.
 10. PULL WIRE THROUGH HOLLOW FRAME TO LATCH RETRACTION DEVICE OR WALL MOUNTED FRAME. COORDINATE REQUIREMENTS OF ELECTRICAL CONNECT WITH DOOR HATCH AND SECURITY VENDOR.




NOTE:


1. INSTALL IN ACCORDANCE WITH MANUFACTURER'S MOUNTING INSTRUCTIONS AND USING RECOMMENDED MOUNTING HARDWARE

LAY-IN CEILING DOWNLIGHT INSTALLATION

2
E-901 SCALE: NOT TO SCALE




6 TRANSFORMER FLEX CONNECTION
E-901 SCALE: NOT TO SCALE



5
E-901

DETAIL - GROUNDING OF TRANSFORMERS

SCALE: NOT TO SCALE



1 EPO SWITCH
E-901 SCALE: NOT TO SCALE



PROFESSIONAL SEALS

PROJECT PARTNERS:

[illegible]

☐ APPROVED FOR CONSTRUCTION
☒ NOT APPROVED FOR CONSTRUCTION

CLIENT INFORMATION:

Wayne State University

Wayne State University



WAYNE STATE
UNIVERSITY

5454 CASS AVE
DETROIT, MICHIGAN
48202

CLIENT PROJECT #:	PROJECT NUMBER
JHA PROJECT #:	PROJECT NUMBER

PROJECT INFORMATION:

WSU APPLEBAUM
MRI

259 MACK AVE
DETROIT, MICHIGAN
48201

SSOE PROJECT #:	023-03727-00
SSOE MANAGER:	JEFF FALZON



1001 Madison Avenue
Toledo, OH 43604
T. (419) 255-3830

THIS DRAWING IS THE PROPERTY OF SSGE GROUP. UNAUTHORIZED USE OF ANY KIND,
INCLUDING USE ON OTHER PRODUCTS, IS PROHIBITED.

THIS DRAWING IS THE PROPERTY OF SBOE GROUP. UNAUTHORIZED USE OF ANY KIND, INCLUDING USE ON OTHER PROJECTS, IS PROHIBITED.

ELECTRICAL DETAILS

E-901

- A. ALL SECURITY CABLING INCLUDING CARD READERS IS LOW VOLTAGE AND SHALL BE PLENUM RATED. CABLING REQUIREMENTS AND LAYOUT TO BE PROVIDED BY SECURITY CONTRACTOR. ALL CABLING TO BE PROVIDED AND INSTALLED BY ELECTRICAL CONTRACTOR. HOMERUN CABLING TO NEAREST TELE/DATA ROOM. VERIFY WITH ENCOMPASS HEALTH ITG
- B. ALL CAMERA CABLING SHALL BE HOMERUN TO DVR AT NEAREST TELE/DATA ROOM. COORDINATE WITH SECURITY VENDOR.
- C. CONTRACTOR SHALL OBTAIN TV AND NURSE CALL SYSTEM SINGLE LINE DIAGRAMS FROM VENDORS. PROVIDE CABLING PER THEIR REQUIREMENTS.
- D. CONTRACTOR SHALL VERIFY WITH EACH LOW VOLTAGE VENDOR THE HOMERUN LOCATIONS FOR THEIR SYSTEM CABLES BEFORE RUNNING CABLING.
- E. LOW VOLTAGE INSTALLER SHALL HAVE RCDD CERTIFIED STAFF ON SITE FOR INSTALLATION, TESTING AND PROJECT MANAGEMENT PER ENCOMPASS HEALTH ITG.
- F. COORDINATE LOCATION AND REQUIREMENT OF ALL SECURITY DEVICES WITH ENCOMPASS HEALTH ITG, MICHAEL KOK, PRIOR TO ROUGH-IN.
- G. COORDINATE LOCATION OF SMOKE DAMPERS WITH MECHANICAL PRIOR TO ROUGH-IN.
- H. COORDINATE EXACT LOCATION AND MOUNTING HEIGHT FOR TV AND TV DATA OUTLETS WITH OWNER PRIOR TO ROUGH-IN.
- I. ALL LOW VOLTAGE SYSTEMS (VOICE, DATA, TV, PAGING, AND NURSE CALL) SHALL BE PROVIDED IN SEPARATE HOODS/SUPPORTS FOR EACH SYSTEM. NO HOOD/SUPPORT SHALL EXCEED 40 CABLES.
- J. CABLE SYSTEM TYPES (VOICE, DATA, TV, PAGING, AND NURSE CALL) SHALL BE SEPARATED IN SLEEVES/FIRE BARRIERS THROUGH RATED WALLS.
- K. PRIOR TO ROUGH-IN OF PATIENT BED LOCATOR OUTLETS, CONTRACTOR SHALL OBTAIN BED LOCATOR ROUGH-IN TEMPLATE FROM OWNER AND ENSURE OUTLETS ARE ROUGH-IN AT LOCATED REQUIRED PER TEMPLATE. VERIFY WHETHER BED REQUIRES LEFT OR RIGHT SIDE LOCATION PRIOR TO ROUGH-IN.
- L. ALL ELECTRIC LOCKS SHALL BE INTEGRATED WITH FIRE ALARM FOR DOOR RELEASE UPON FIRE ALARM ACTIVATION
- M. COORDINATE SECURITY DEVICES CONNECTION TO POWERED DOORS WITH VENDOR.
- N. SEE ELECTRICAL DETAILS - NURSE CALL WIRING DIAGRAM FOR ADDITIONAL NURSE CALL REQUIREMENTS.

SUBMITTAL/REVISION SCHEDULE:

[illegible]

☐ APPROVED FOR CONSTRUCTION
☒ NOT APPROVED FOR CONSTRUCTION

CLIENT INFORMATION:

Wayne State University

5454 CASS AVE
DETROIT, MICHIGAN
48202

CLIENT PROJECT #:	PROJECT NUMBER
JHA PROJECT #:	PROJECT NUMBER

PROJECT INFORMATION:

WSU APPLEBAUM
MRI

259 MACK AVE
DETROIT, MICHIGAN
48201

SSOE PROJECT #: 023-03727-00

SSOE MANAGER: JEFF FALZON

1001 Madison Avenue
Toledo, OH 43604
T. (419) 255-3830

THIS DRAWING IS THE PROPERTY OF SCDI GROUP. UNAUTHORIZED USE OF ANY KIND, INCLUDING USE ON OTHER PROJECTS, IS PROHIBITED.


T-101

1
T-101

ENLARGED CLINICAL AUXILIARY - NEW WORK PLAN

SCALE: 1/4" = 1'-0"

N



2 ENLARGED CLINICAL AUXILIARY - DEMOLITION PLAN
T-101 SCALE: 1/4" = 1'-0" N

- A. ALL SECURITY CABLING INCLUDING CARD READERS IS LOW VOLTAGE AND SHALL BE PLENUM RATED. CABLING REQUIREMENTS AND LAYOUT TO BE PROVIDED BY SECURITY CONTRACTOR. ALL CABLING TO BE PROVIDED AND INSTALLED BY ELECTRICAL CONTRACTOR. HOMERUN CABLING TO NEAREST TELE/DATA ROOM. VERIFY WITH ENCOMPASS HEALTH ITG
- B. ALL CAMERA CABLING SHALL BE HOMERUN TO DVR AT NEAREST TELE/DATA ROOM. COORDINATE WITH SECURITY VENDOR.
- C. CONTRACTOR SHALL OBTAIN TV AND NURSE CALL SYSTEM SINGLE LINE DIAGRAMS FROM VENDORS. PROVIDE CABLING PER THEIR REQUIREMENTS.
- D. CONTRACTOR SHALL VERIFY WITH EACH LOW VOLTAGE VENDOR THE HOMERUN LOCATIONS FOR THEIR SYSTEM CABLES BEFORE RUNNING CABLING.
- E. LOW VOLTAGE INSTALLER SHALL HAVE RCDD CERTIFIED STAFF ON SITE FOR INSTALLATION, TESTING AND PROJECT MANAGEMENT PER ENCOMPASS HEALTH ITG.
- F. COORDINATE LOCATION AND REQUIREMENT OF ALL SECURITY DEVICES WITH ENCOMPASS HEALTH ITG, MICHAEL KOK, PRIOR TO ROUGH-IN.
- G. COORDINATE LOCATION OF SMOKE DAMPERS WITH MECHANICAL PRIOR TO ROUGH-IN.
- H. COORDINATE EXACT LOCATION AND MOUNTING HEIGHT FOR TV AND TV DATA OUTLETS WITH OWNER PRIOR TO ROUGH-IN.
- I. ALL LOW VOLTAGE SYSTEMS (VOICE, DATA, TV, PAGING, AND NURSE CALL) SHALL BE PROVIDED IN SEPARATE HOOKS/SUPPORTS FOR EACH SYSTEM. NO HOOKS/SUPPORT SHALL EXCEED 40 CABLES.
- J. CABLE SYSTEM TYPES (VOICE, DATA, TV, PAGING, AND NURSE CALL) SHALL BE SEPARATED IN SLEEVES/FIRE BARRIERS THROUGH RATED WALLS.
- K. PRIOR TO ROUGH-IN OF PATIENT BED LOCATOR OUTLETS, CONTRACTOR SHALL OBTAIN BED LOCATOR ROUGH-IN TEMPLATE FROM OWNER AND ENSURE OUTLETS ARE ROUGH-IN AT LOCATED REQUIRED PER TEMPLATE. VERIFY WHETHER BED REQUIRES LEFT OR RIGHT SIDE LOCATION PRIOR TO ROUGH-IN.
- L. ALL ELECTRIC LOCKS SHALL BE INTEGRATED WITH FIRE ALARM FOR DOOR RELEASE UPON FIRE ALARM ACTIVATION
- M. COORDINATE SECURITY DEVICES CONNECTION TO POWERED DOORS WITH VENDOR.
- N. SEE ELECTRICAL DETAILS - NURSE CALL WIRING DIAGRAM FOR ADDITIONAL NURSE CALL REQUIREMENTS.

SUBMITTAL/REVISION SCHEDULE:

☐ APPROVED FOR CONSTRUCTION
☒ NOT APPROVED FOR CONSTRUCTION

CLIENT INFORMATION:



5454 CASS AVE
DETROIT, MICHIGAN
48202

PROJECT INFORMATION:

SSOE®
1001 Madison Avenue
Toledo, OH 43604
T. (419) 255-3830

THIS DRAWING IS THE PROPERTY OF SOBE GROUP. UNAUTHORIZED USE OF ANY KIND, INCLUDING USE ON OTHER PROJECTS, IS PROHIBITED.

T-102