



Division of Finance and Business Operations

Procurement & Strategic Sourcing  
5700 Cass Avenue, suite 4200  
Detroit, Michigan 48202  
(313) 577-3734  
FAX (313) 577-3747

September 5, 2019

**Addendum #2 To  
Request for Proposal  
For I2C MRI Installation: Project 212-313128**

**Dated August 15, 2019**

**As a result of the mandatory pre-bid, the following questions were submitted. The questions and university responses are as follows:**

1. Air and Natural Gas are not shown on the drawings, but the drawings call for new connections at the relocated Fume Hood. Will horizontal footage need to be added long the wall from where the old hood was located?  
Yes. Provide 10" horizontal duct transfer as indicated on plan sheet M-1 from fume hood new location in Chemistry 105-1 to existing vertical fume hood exhaust duct.
2. Does the new Fume Hood require Sanitary waste hookup? If so, where does this connection occur?  
No.
3. Is the sanitary shown on the drawing for the new sink going to a sewage ejector? This is not labeled on the drawings.  
No. Connect new sink to existing sanitary.
4. Is the Chemistry sink new or existing. I see the base cabinet is labeled as existing to be re-used, but no model is provided for the sink. Please provide model if new.  
Chemistry sink will be new with new faucet. Refer to updated Equipment List #21 and added #21a for manufacturer and model number on plan sheet A-161 equipment plan (To be issue as part of Addendum 2 package).
5. Is stainless steel ductwork required for the fume hood or biohazard cabinet?  
No.
6. Who is your Controls vendor? Is a Building Management System required?  
Johnson-Metasy. Building Management system is required.
7. In reviewing the documents associated with the site testing by RBox it indicates that the site did not pass EMI site requirements issued by Time Medical. However, no solution was identified in the report that would bring the site into spec either by shielding or compensation or both? Does a site specific solution exist?  
An updated EMI site report will be issued as part of Addendum 2 package. No additional compensation method or additional shielding is required.
8. On the Finish schedule, Lab 5 105-3 states that all walls have WP-1, but it also states the room is being painted. Is the RF shielded wall under the wall protection to be painted?  
Confirm WP-1 on all walls, full height to suspended ceiling. Omit PT-1. Refer to Updated plan sheet A-161 for Lab 5 105-3 finish.

**The Addendum must be acknowledged on your lump sum bid.**

NOTE: You must have attended a pre-bid conference in order to be eligible to bid on a particular project. Receipt of minutes or addenda without being at a pre-bid conference does not qualify your company to bid.

A copy of this Addendum will be posted to the Purchasing web site at  
<http://go.wayne.edu/bids>.

All questions concerning this project must be emailed to: **Kimberly Tomaszewski**, Procurement & Strategic Sourcing. Email: **Ac9934@wayne.edu**, and copy **Valerie Kreher, Senior Buyer**, at **Rfpteam2@wayne.edu**.

Bids are due **by electronic submission on** no later than 2:00 p.m., **September 9, 2019**. The link for bid submission will be posted with the bid details at **<http://go.wayne.edu/bids>** beginning **August 15, 2019**.

Thank you,

**Kimberly Tomaszewski,**  
**Senior Buyer**