


.\\wsu_primary_stacked_color.jpg


SHIFFMAN LIBRARY FLOORING

2	Addendum	2/10/2023
1	FOR BIDDING	2/3/2023
NO.	REVISION/ISSUE	DATE


WAYNE STATE UNIVERSITY
FACILITIES PLANNING AND MANAGEMENT
DESIGN & CONSTRUCTION SERVICES
5454 CASS AVENUE
DETROIT, MI 48202


SHIFFMAN LIBRARY FLOORING
135, PHYSICS BUILDING,
666 W HANCOCK ST,
DETROIT, MI 48201


 Remove and replace with Carpet #1
Patcraft color Filter 10471 Uplight-00550 (9"x36")

 Remove and replace with Carpet #2
Patcraft color Linear Tension 10541 Moss-00350 (24"x24")

Wall Base- Roppe 4" 100 Black cove base



 Remove and replace with Carpet #1
Patcraft color Filter 10471 Uplight-00550 (9"x36")

 Remove and replace with Carpet #2
Patcraft color Linear Tension 10541 Moss-00350 (24"x24")

Wall Base- Roppe 4" 100 Black cove base

1. ALL DIMENSIONS SHOWN ARE FOR REFERENCE ONLY. CONTRACTOR IS RESPONSIBLE TO VERIFY ALL MEASUREMENTS IN FIELD.
2. WORK WILL BE CONDUCTED IN AN OCCUPIED BUILDING/REGULAR HOURS. NOISY WORK TO BE PLANNED FOR MINIMAL IMPACT. CONTACT WITH THE OCCUPANTS SHOULD BE MINIMAL.
3. WSU DOES NOT PROVIDE PARKING. COST OF PARKING IS CONTRACTORS RESPONSIBILITY.
4. ANY ADDITIONAL WORK REQUESTED. MUST BE APPROVED BY WSU PROJECT MANAGER IN WRITING.
5. CONTRACTOR IS RESPONSIBLE FOR CLEANUP.
6. INSTALL TRANSITION STRIP BETWEEN NEWLY INSTALLED FLOORING AND ADJOINING FLOORING.
7. FINAL FINISH FLOORING HEIGHT TO MATCH ADJOINING FLOORING.
8. PRE DEMO WALK THROUGH IS REQUIRED.
9. BUILDING IS OCCUPIED DURING CONSTRUCTION, WORK TO BE SCHEDULED AROUND CLASSES.
10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR BARRICADES/ENCLOSURES AS REQUIRED TO ASSURE PUBLIC, CONTRACTOR, EMPLOYEE, AND WORKER PROTECTION AT AREAS OF CONSTRUCTION.
11. ANY ADDITIONAL WORK REQUESTED. MUST BE APPROVED BY WSU PROJECT MANAGER IN WRITING.
12. CONTRACTOR IS RESPONSIBLE FOR CLEANUP. WORK AREA MUST BE LEFT IN CLEAN CONDITION AS IT WAS PRIOR TO START OF WORK.