



WAYNE STATE
UNIVERSITY

WAYNE STATE UNIVERSITY

MATTHAEI CENTER - ADDITION OF AIR
CONDITIONING

5101 JOHN C. LODGE FWY DETROIT , MI 48202

ISSUED FOR: **CONSTRUCTION**

10/24/2022

DRAWING INDEX

GENERAL

G-001 TITLE SHEET

STRUCTURAL

S-000 ABBREVIATIONS & SYMBOLS
S-001 GENERAL NOTES
S-101 LOW ROOF FRAMING PLANS
S-102 INTERMEDIATE ROOF FRAMING PLAN
S-102.1 ENLARGED INTERMEDIATE ROOF
FRAMING PLANS
S-103 HIGH ROOF FRAMING PLAN
S-501 STRUCTURAL DETAILS

MECHANICAL

M-001 HVAC NOTES & LEGEND
MD-102 HVAC ROOF DEMO PLAN
MD-103 HVAC ENLARGED DEMOLITION FLOOR
PLAN
M-101 HVAC MAIN LEVEL FLOOR PLAN
M-102 HVAC ROOF PLAN
M-301 HVAC MECHANICAL ROOM NORTH PLAN
M-302 HVAC MECHANICAL SOUTH ROOM PLAN
M-303 HVAC ENLARGED NORTH WEST FLOOR
PLAN
M-304 HVAC ENLARGED NORTH EAST FLOOR
PLAN
M-305 HVAC ENLARGED SOUTH WEST FLOOR
PLAN
M-306 HVAC ENLARGED SOUTH EAST FLOOR
PLAN
M-501 HVAC DETAILS
M-601 CONTROL DIAGRAMS
M-701 HVAC SCHEDULES

ELECTRICAL

E-001 ELECTRICAL SYMBOLS, LEGENDS &
NOTES
E-100 ELECTRICAL BASEMENT FLOOR PLAN
E-101 ELECTRICAL FIRST FLOOR PLAN
E-102 ELECTRICAL SECOND FLOOR PLAN
E-103 ELECTRICAL ROOF PLAN
E-401 ELECTRICAL ENLARGED FLOOR PLAN
E-501 ELECTRICAL DETAILS
E-601 ELECTRICAL ONE LINE DIAGRAM
E-701 ELECTRICAL SCHEDULES

PROJECT SUMMARY

VICINITY MAP



Unless otherwise stated in Contract,
The Osborn Engineering Company
retains copyright ownership.
Instruments of Service may only be
used for the purpose described in the
Contract. The Osborn Engineering
Company may grant specific usage
rights under license, and / or may
transfer copyright ownership /
assignment in writing. Reproduction,
reuse or re-distribution of Instruments
of Service is prohibited.

DRAWN BY DWN
CHECKED BY CHK
CLIENT PROJ NO.
OSBORN PROJ NO. J20220270.000

HVAC MAIN LEVEL
FLOOR PLAN

DRAWING NO.

G-001

MATTHAEI
CENTER
ADDITION OF AIR
CONDITIONING
WAYNE STATE
UNIVERSITY

DETROIT, MI 48208











TAG	ISSUED	DATE
TAG1	FOR BIDDING	08/08/22
TAG2	FOR RE-BIDDING	10/24/22
TAG3		
TAG4		
TAG5		
TAG6		
TAG7		
TAG8		
TAG9		
AG10		
AG11		
AG12		
AG13		
AG14		
AG15		
AG16		
AG17		
AG18		
AG19		
AG20		

ABBREVIATIONS












SYMBOLS			P	PRECAST CONCRETE
				PAF
&	AND		PCF	POUNDS PER CUBIC FOOT
@	AT		PCI	PRESTRESSED CONCRETE INSTITUTE
±	PLUS OR MINUS		PDF	POWER DRIVEN FASTENER
∅	DIAMETER		PERP	PERPENDICULAR
¢	PENNY WEIGHT		PJP	PARTIAL JOINT PENETRATION
c	CONCRETE COMPRESSIVE STRENGTH		PL	PLATE
fm'	MASONRY COMPRESSIVE STRENGTH		PLF	POUNDS PER LINEAR FOOT
A	ANCHOR ROD		PLMB	PLUMBING
AR	AMERICAN CONCRETE INSTITUTE		PNT	POINT
AE	ARCHITECT ENGINEER		PREFAB	PREFABRICATED
ADD	ADDENDUM		PROJ	PROJECTION
ADDL	ADDITIONAL		PSF	POUNDS PER SQUARE FOOT
ADJ	ADJACENT		PSI	POUNDS PER SQUARE INCH
AESS	ARCHITECTURALLY EXPOSED STRUCTURAL STEEL		PSL	PARALLEL STRAND LUMBER
AFF	ABOVE FINISH FLOOR		PST	POST TENSIONED
ASNC	AMERICAN INSTITUTE OF STEEL CONSTRUCTION		PT	PRESSURE TREATED LUMBER
ALU	ALUMINUM		PUR	PURLIN
ALT	ALTERNATE		PVC	POLYVINYL CHLORIDE
AOR	ARCHITECT OF RECORD		Q	QUANTITY
APPROX	APPROXIMATE		QTY	QUANTITY
ARCH	ARCHITECT			
ASCE	AMERICAN SOCIETY OF CIVIL ENGINEERS			
ASD	ALLOWABLE STRENGTH DESIGN			
ASTM	AMERICAN SOCIETY OF TESTING MATERIALS			
AVERAGE	AVERAGE			
AWG	AMERICAN WELDING SOCIETY			
B	BOTTOM OF			
B'	BALANCE		R	RADIUS
BB	BOXED BEAM		RC	REINFORCED CONCRETE
BLDG	BUILDING		RD	ROOF DRAIN
BLK	BLOCK		REF	REFERENCE
BLKG	BLOCKING		REINF	REINFORCING (REINFORCEMENT)
BM	BEAM		REQD	REQUIRED
BN	BOUNDARY NAIL		REV	REVISION
BOT	BOTTOM		R	ROOF
BRD	BRIDGING		RFI	REQUEST FOR INFORMATION
BRG	BEARING		RM	ROOM
BSMT	BASEMENT		RO	ROUGH OPENING
BTW	BETWEEN			
BULL	BULLETIN			
C	CHANNEL			
CA	CAISSON		SBC	SOIL BEARING CAPACITY
C/C	CENTER TO CENTER		SC	SLIP CRITICAL (BOLTS)
CALCS	CALCULATIONS		SCHED	SCHEDULE
CANT	CANTILEVER		SDI	STEEL DECK INSTITUTE
CDF	CONCRETE DENSITY FLIT		SECT	SECTION
CFMF	COLD FORM METAL FRAMING		SEOR	STRUCTURAL ENGINEER OF RECORD
CL	CENTERLINE		SF	SQUARE FEET
CLG	CEILING		SHT	SHEET
CF	CUBIC FEET, CUBIC FOOT		SHTG	SHEATHING
CIP	CAST IN PLACE		SM	SIMILAR
CJP	CONTROL JOINT		SJI	STEEL JOIST INSTITUTE
CJP	COMPLETE JOINT PENETRATION		SL	SNOW LOAD
CLR	CLEAR		SLBB	SHORT LEGS BACK TO BACK
CM	CENTIMETER		SOB	SLAB ON GRADE
CMU	CONCRETE MASONRY UNIT		S	SPACE (S) / SPACING
COL	COLUMN		SPECS	SPECIFICATIONS
COMP	COMPOSITE		SPP	SPRUCE PINE FIR
CONC	CONCRETE		SQ	SQUARE
CONN	CONNECTION		SQ FT	SQUARE FEET
CONST	CONSTRUCTION		SQ IN	SQUARE INCH
CONT	CONTINUOUS		SS	STAINLESS STEEL
COORD	COORDINATE		STD	STANDARD
CTR	CENTER		STIFF	STIFFENER
CY	CUBIC YARD		STL	STEEL
			STFR	STOREFRONT
			STR	STRUCTURAL
			SUP	SUPPORT
			SV	SQUARE YARD
			SYM	SYMMETRICAL
			SWP	SOUTHERN YELLOW PINE
			T	THICKNESS
			T&B	TOP AND BOTTOM
			TOP OF	TOP OF
			T&B	TOP OF BEAM
			TOP OF	TOP OF
			T&SLAB	TOP OF SLAB
			T/STL	TOP OF STEEL
			THRU	THROUGH
			TJ	TIE JOIST
			TYP	TYPICAL
			U	UNLESS NOTED OTHERWISE
			V	VERTICAL EACH FACE
			VERT	VERTICAL
			VIF	VERIFY IN FIELD
			VOL	VOLUME
			W	WIDE FLANGE
			W/	WITH
			W/O	WITHOUT
			WD	WOOD
			WL	WIND LOAD
			WP	WORK POINT
			WT	WEIGHT
			WWF	WELDED WIRE FABRIC
			X	CROSS BRACING
			Y	YARD
			YD	YARD



















SEE STRUCTURAL SYMBOLS, LEGENDS, AND SCHEDULES FOR ADDITIONAL ABBREVIATIONS. ALL ABBREVIATIONS, SYMBOLS, AND LEGENDS SHOWN ARE NOT NECESSARILY USED.



MATERIAL INDICATIONS	
	EXISTING
	EARTH
	AGGREGATE BASE COURSE
	CONCRETE
	CONCRETE MASONRY UNIT
	CONCRETE MASONRY UNIT GROUTED SOLID
	VENEER
	PRECAST CONCRETE
	WOOD FRAMING

GENERAL REFERENCE SYMBOLS	
DETAIL VIEW 	REVISION NUMBER AND EXTENT 
SECTION 	MATCH LINE REFERENCES 
FRAMING ELEVATION 	DRAWING TITLE SYMBOLS 
FRAMING ELEVATION 	LAYOUT GRID LINES 
LEVEL LINE 	NORTH ARROW 

STRUCTURAL FOUNDATION PLAN SYMBOLS

 <p>SPREAD FOOTING MARK</p> <p>PW (9'-5")</p> <p>TOP OF FOOTING ELEVATION</p> <p>CONCRETE PIER MARK</p>	 <p>STRIP FOOTING MARK</p> <p>FOOTING STEP</p> <p>TWB (9'-4")</p> <p>TOP OF FOOTING ELEVATION</p>
 <p>DRILLED PIER MARK</p> <p>DPI (9'-5")</p> <p>TOP OF DRILLED PIER ELEVATION</p> <p>PILE CAP MARK</p>	 <p>RETAINING WALL MARK</p> <p>RWB (9'-4")</p> <p>TOP OF FOOTING ELEVATION</p>
 <p>PILE CAP MARK</p> <p>PCD (9'-5")</p> <p>TOP OF PILE CAP ELEVATION</p>	 <p>CHANGE IN SLAB ELEVATION (± FROM ESTABLISHED ELEVATION)</p>
	 <p>MASONRY NON-BEARING WALL ON THICKENED SLAB</p>
	 <p>CONTROL JOINTS</p>
	 <p>COLUMN ISOLATION JOINT</p>
 <p>TOP OF GRADE BEAM ELEVATION</p> <p>GRADE BEAM MARK</p> <p>GBB (9'-4")</p> <p>CAISSON MARK</p> <p>CBW (9'-5")</p> <p>TOP OF CAISSON ELEVATION</p>	 <p>UNDERGROUND UTILITY LINE (STORMSEWER)</p>

<h2>STRUCTURAL COLUMN PLAN SYMBOLS</h2>	
 W16x40  HSS60x6x1/4  6x6	WIDE FLANGE COLUMN DESIGNATION HSS COLUMN DESIGNATION WOOD POST DESIGNATION
<h2>TRUSS AND SWAY FRAME NOMENCLATURE</h2>	
 BH  J#  SP#  T#	BEAM MARK JOIST MARK SPECIAL JOIST MARK TRUSS MARK
   	HORIZONTAL BRIDGING DIAGONAL BRIDGING KICKER BRACING SPLICE CONNECTION
<h2>JOIST GIRDER DESIGNATION</h2>	
 48G14N10K  362S162-54	JOIST GIRDER DEPTH IN INCHES NUMBER OF JOIST SPACES UNFACTORED POINT LOAD IN KIPS STUD DEPTH IN MILS S=STUD, T=TRACK, U=CHANNEL FLANGE WIDTH IN MILS THICKNESS GAUGE IN MILS
<h2>COLD-FORM MEMBER DESIGNATION</h2>	
 85S52	NOMINAL WALL THICKNESS IN INCHES S=STD LADDER JT REIN, H=HEAVY JT REIN REBAR LAST TWO DIGITS INDICATE REBAR SPACING IN INCHES
<h2>MASONRY WALL REINFORCING DESIGNATION</h2>	
 BF#  MF#	VERTICAL BRACING MARK INDICATES BOT FLANGE BRACE MOMENT FRAME MARK
	
<h2>DIAGONAL BRACING BELOW BEAM</h2>	
	
<h2>INDICATE LRFD OR ASD</h2>	
<h2>AXIAL LOAD IN BRACE</h2>	
<h2>BEARING WALL ABOVE BEAM</h2>	
<h2>CONCRETE / WOOD / CFMF BEARING WALL</h2>	
<h2>MASONRY BEARING WALL</h2>	
<h2>EXISTING BEARING WALL</h2>	
<h2>NON-BEARING WALL</h2>	
<h2>CONCRETE SHEAR WALL MARK</h2>	
<h2>DESIGNATES END REBAR, SEE SCHEDULE</h2>	
<h2>MASONRY SHEAR WALL MARK</h2>	
<h2>DESIGNATES HOLD-DOWN, SEE SCHEDULE</h2>	
<h2>WOOD SHEAR WALL MARK</h2>	

		
 OSBORN ENGINEERING <small>20201 Telegraph Road Brighton, MI 48025 (313) 915-4014 www.osborn-eng.com</small>		
MATTHAEI HVAC STUDY & SCHEMATIC		
WAYNE STATE UNIVERSITY		
DETROIT MI 48208		
TAG	ISSUED	DATE
1	FOR BIDDING	08/09/22
2	FOR RE-BIDDING	10/24/22
<small>Unless otherwise stated in Contract, The Osborn Engineering Company retains copyright ownership. Instruments of Service may only be used for the purpose described in the Contract. The Osborn Engineering Company may grant specific usage rights under license, and/or may transfer copyright ownership/ assignment in writing. Reproduction, re-use or re-distribution of Instruments of Service is prohibited.</small>		
<small>DRAWN BY CHECKED BY CLIENT PROJ NO OSBORN PROJ NO</small>		<small>KC JL J202202270.000</small>
ABBREVIATIONS & SYMBOLS		
<small>DRAWING NO.</small> S-000		

F

E

D

C

B

A

BUILDING DESIGN CRITERIA

GOVERNING CODE: 2015 MICHIGAN BUILDING CODE IN CONJUNCTION WITH ASCE 7-10

RISK CATEGORY: III

ROOF LIVE LOAD 20 PSF

SNOW LOAD:

GROUND SNOW LOAD, Pg: 20 PSF
FLAT ROOF SNOW LOAD, Pf: 20 PSF
SNOW EXPOSURE FACTOR, Ce: 1.0
SNOW IMPORTANCE FACTOR: 1.0
THERMAL FACTOR, Ct: 1.0
SNOW DRIFT: PER ASCE-7

WIND LOAD:

ULTIMATE DESIGN WIND SPEED (Vult): 115 MPH
NOMINAL DESIGN WIND SPEED (Vnom): 90 MPH
WIND EXPOSURE: C
INTERNAL PRESSURE COEFFICIENT: ±0.18

SEISMIC LOAD:

SEISMIC IMPORTANCE FACTOR 1.0
SITE SPECTRAL RESPONSE ACCELERATION (Ss): 0.096
SITE SPECTRAL RESPONSE ACCELERATION (S1): 0.047
SEISMIC SITE CLASS: D (ASSUMED)
DESIGN SPECTRAL RESPONSE ACCELERATION (Sds): 0.077
DESIGN SPECTRAL RESPONSE ACCELERATION (Sd1): 0.053
SEISMIC DESIGN CATEGORY: B

STRUCTURAL MODIFICATION DO NOT ALTER THE EXISTING LATERAL SYSTEMS AND ANY NEW LATERAL LOADS DO NOT EXCEED CODE ALLOWABLE 10% INCREASE

GENERAL CONDITIONS:

- SEE SPECIFICATIONS FOR QUALITY OF CONSTRUCTION REQUIRED, QUALITY OF WORK, MANUFACTURING AND INDUSTRY STANDARDS, PHYSICAL PROPERTIES OF MATERIALS, CONFORMANCE TO CODES AND REGULATIONS GUARANTEE AND WARRANTY REQUIREMENTS.
- SEE ARCHITECTURAL, HVAC, PLUMBING, ELEVATOR, FIRE PROTECTION & ELECTRICAL DRAWINGS FOR OTHER PERTINENT INFORMATION RELATED TO STRUCTURAL WORK AND COORDINATE AS REQUIRED. CONTRACTOR SHALL COORDINATE STRUCTURAL DRAWINGS WITH ALL OTHER DRAWINGS WITHIN THE CONTRACT DOCUMENTS.
- THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS, ELEVATIONS AND CONDITIONS RELATED TO EXISTING CONSTRUCTION, EXISTING SERVICES, AND THE SITE BEFORE BEGINNING WORK.
- CONSTRUCTION LOADS SHALL NOT EXCEED DESIGN LIVE LOADS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DESIGN REQUIRED TO SUPPORT CONSTRUCTION EQUIPMENT USED IN CONSTRUCTING THIS PROJECT. ALL EQUIPMENT SUPPORT DESIGN SHALL BE PERFORMED BY AN ENGINEER LICENSED IN THE STATE OF THE PROJECT. SHORING AND RESHORING IS THE RESPONSIBILITY OF THE CONTRACTOR.
- IF MATERIALS, QUANTITIES, STRENGTHS OR SIZES INDICATED BY THE DRAWINGS OR SPECIFICATIONS ARE NOT IN AGREEMENT WITH THESE NOTES, THE BETTER QUALITY AND/OR QUANTITY, STRENGTH OR SIZE INDICATED, SPECIFIED OR NOTED SHALL BE PROVIDED.
- THE CONTRACTOR IS SOLELY RESPONSIBLE FOR THE FOLLOWING ITEMS THAT WILL NOT BE REVIEWED BY THE OWNER, ARCHITECT OR ENGINEER.
 - DEVIATIONS FROM CONTRACT DOCUMENTS.
 - DIMENSIONS, ELEVATIONS AND CONDITIONS TO BE CONFIRMED AND CORRELATED AT THE SITE.
 - FABRICATION PROCESS INFORMATION.
 - MEANS, METHODS, TECHNIQUES, PROCEDURES OF CONSTRUCTION AND CONSTRUCTION SAFETY.
 - COORDINATION OF THE WORK OF ALL TRADES.
- THE EXISTING CONDITIONS INDICATED ON THE DRAWINGS ARE BASED ON EXISTING DRAWINGS BY ALDEN B DOW ASSOC. INC., HYDE & BOBBIO, AND ROBT J DAVIS, DATED FEBRUARY 19, 1966. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR FIELD VERIFYING ALL EXISTING CONDITIONS AND DIMENSIONS. CONTRACTOR IS TO REPORT ANY DISCREPANCIES TO THE A/E PRIOR TO PROCEEDING.
- THE INFORMATION SHOWN ON THE ARCHITECTURAL AND STRUCTURAL CONSTRUCTION DOCUMENTS IS BASED ON ASSUMPTIONS OF THE EXISTING BUILDING CONSTRUCTION. ORIGINAL CONSTRUCTION DOCUMENTS WERE NOT AVAILABLE FOR THE PREPARATION OF THESE DOCUMENTS. THE CONTRACTOR IS TO NOTIFY THE A/E IF CONDITIONS DIFFERING FROM THOSE STATED ARE UNCOVERED IN THE DEMOLITION PROCESS.
- ANY CHANGES TO THE STRUCTURAL SYSTEMS SHALL BE REDESIGNED BY A PROFESSIONAL ENGINEER AT NO COST TO THE OWNER OR THE A/E AND SUBMITTED TO THE A/E FOR REVIEW. SUBMITTAL SHALL BE ACKNOWLEDGED IN WRITING BEFORE BEGINNING CONSTRUCTION. IF CHANGES ARE MADE WITHOUT WRITTEN APPROVAL SUCH CHANGES SHALL BE THE LEGAL AND FINANCIAL RESPONSIBILITY OF THE PARTY MAKING THE CHANGE TO REPLACE OR REPAIR THE CONDITION AS DIRECTED BY THE A/E.
- CONTRACTOR IS RESPONSIBLE TO UNCOVER AND VISUALLY FIELD VERIFY THE EXISTING CONSTRUCTION PRIOR TO THE START OF ANY WORK AFFECTING THE EXISTING STRUCTURE. CONTRACTOR IS TO REPORT ANY CHANGES OR DISCREPANCIES FROM THOSE SHOWN TO THE A/E.

DEMOLITION:

- IT IS SOLELY THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE DEMOLITION PROCEDURE AND SEQUENCE TO ENSURE THE SAFETY OF THE EXISTING BUILDING AND ITS COMPONENT PARTS DURING DEMOLITION AND FUTURE ERECTION. THIS INCLUDES, BUT IS NOT LIMITED TO, THE ADDITION OF ANY OR ALL TEMPORARY BRACING, GUYS OR TIE-DOWNS WHICH MAY BE NECESSARY. SUCH MATERIAL SHALL BE REMOVED AND SHALL REMAIN THE PROPERTY OF THE CONTRACTOR AFTER COMPLETION OF THE PROJECT.
- THE CONTRACTOR SHALL SUPPORT, BRACE AND SECURE EXISTING STRUCTURE AS REQUIRED. CONTRACTOR IS SOLELY RESPONSIBLE FOR THE SAFETY OF THE EXISTING BUILDING DURING DEMOLITION AND CONSTRUCTION. FIELD VERIFY ALL EXISTING DIMENSIONS, ELEVATIONS AND CONDITIONS WHICH AFFECT THE DEMOLITION AND NEW CONSTRUCTION.
- THE EXTENT OF THE WORK SHOWN SHALL INCLUDE REMOVAL AND DISPOSAL, OFF SITE, OF THE ELEMENTS INDICATED WITHIN THESE DEMOLITION DRAWINGS UNO
- THE EXISTING STRUCTURE SHALL BE DISASSEMBLED IN A MANNER WHICH DOES NOT DAMAGE OR DEFORM ANY EXISTING STRUCTURE TO REMAIN. EXISTING SLABS SHALL BE SAWCUT IN A MANNER WHICH DOES NOT CAUSE THE SLAB SUPPORTING MEMBER TO BE CUT OR DAMAGED.
- CONFORM TO ALL APPLICABLE CODES FOR DEMOLITION OF STRUCTURES, SAFETY OF EXISTING AND ADJACENT STRUCTURES, DUST CONTROL, AND DISPOSAL.
- USE OF EXPLOSIVES SHALL NOT BE PERMITTED.
- EXISTING SLABS SHALL BE CORE DRILLED AT RE-ENTRANT CORNERS OF NEW FLOOR OPENINGS TO PREVENT OVER CUTTING.
- THE DEMOLISHED STRUCTURE SHALL BE REDUCED TO A WEIGHT AND TRANSPORTED ACROSS THE EXISTING STRUCTURE IN A MANNER WHICH DOES NOT OVERSTRESS THE EXISTING BUILDING STRUCTURE.
- FRAMING SHALL BE REMOVED ONLY AFTER THE LOAD SUPPORTED BY THAT FRAMING IS REMOVED. THE FRAMING REMOVAL PROCESS SHALL NOT DEFORM OR INDUCE STRESS TO EXISTING FRAMING TO REMAIN.

STRUCTURAL STEEL:

- DETAIL, FABRICATE AND ERECT STRUCTURAL STEEL IN ACCORDANCE WITH THE LATEST AISC AND OTHER RELATED CODES, STANDARDS AND SPECIFICATIONS LISTED IN THE PROJECT SPECIFICATIONS, EXCEPT AS MODIFIED THEREIN OR ON THE DRAWINGS.
- THE CONTRACTOR IS RESPONSIBLE FOR ALL MISCELLANEOUS/ORNAMENTAL STEEL NOT SHOWN ON THE STRUCTURAL DRAWINGS.
- STRUCTURAL STEEL:
 - ASTM A992 Fy = 50 KSI FOR ROLLED STEEL WIDE FLANGE SHAPES
 - ASTM A36 Fy = 36 KSI FOR CHANNELS, ANGLES, PLATES, BARS, RODS, UNO
 - ASTM A53 TYPE E OR S, GRADE B FOR STEEL PIPE Fy = 35 KSI
 - ASTM A550 GRADE C FOR HSS TUBING Fy = 50 KSI FOR RECTANGULAR AND Fy = 46 KSI FOR ROUND
- HIGH STRENGTH BOLTS: ASTM A325 OR A490, 3/4" DIAMETER MINIMUM UNO
- WORK STRUCTURAL DRAWINGS WITH ARCHITECTURAL, HVAC, PLUMBING, FIRE PROTECTION & ELECTRICAL DRAWINGS FOR CLEARANCES, ATTACHMENTS, ETC.
- ALL FABRICATION AND ERECTION WORK SHALL BE PERFORMED BY AISC CERTIFIED FABRICATORS AND ERECTORS.
- WELDED CONNECTIONS SHALL CONFORM TO THE LATEST REVISED CODE OF THE AMERICAN WELDING SOCIETY, AWS D1.1 AND SHALL BE PERFORMED BY CERTIFIED WELDERS IN ACCORDANCE WITH THE AMERICAN WELDING SOCIETY STANDARDS. PROVIDE MINIMUM 1/4" FILLET WELD UNO.
- CONTRACTOR SHALL ASSUME THAT ANY MODIFICATIONS TO EXISTING STEEL FRAMING SHALL REQUIRE AN ABATEMENT OF EXISTING LEAD PAINT IN CONFORMANCE WITH LOCAL CODES.
- PROVIDE ANGLE WALL ANCHORS, PER PART 4. AISC MANUAL OF STEEL CONSTRUCTION, FOR BEAMS BEARING ON MASONRY WALLS. ANGLE ANCHORS SHALL BE WELDED TO BEAMS.

STRUCTURAL STEEL (CONT):

- CONNECTIONS: WELD OR BOLT CONNECTIONS, AS INDICATED:
 - CONNECTIONS NOT DETAILED ON THE DRAWINGS SHALL CONFORM TO THE REQUIREMENTS OF THE CITED AISC SPECIFICATION
 - WHERE THE REACTION VALUES OF BEAMS ARE NOT SHOWN ON THE DRAWINGS, EACH END CONNECTION SHALL BE DESIGNED TO SUPPORT 55% OF THE TOTAL UNIFORM LOAD CAPACITY DERIVED FROM THE ASD VALUE OF THE TABLES AND FORMULA OF THE MAXIMUM TOTAL UNIFORM LOAD IN PART 3, FOURTEENTH EDITION, OF THE AISC MANUAL OF STEEL CONSTRUCTION FOR THE GIVEN MEMBER SIZE, SPAN, AND YIELD STRENGTH. COMPOSITE BEAM CONNECTIONS MUST DEVELOP 75% OF THE TOTAL BEAM ALLOWABLE UNIFORM LOAD CAPACITY, AS GIVEN IN THE AISC TABLES BASED ON SIZE, SPAN, & YIELD STRENGTH
 - THE MINIMUM LENGTH OF CONNECTION ANGLES SHALL BE EQUAL TO ONE HALF THE DEPTH OF THE MEMBER TO BE SUPPORTED.
 - ONE SIDED CONNECTIONS WILL NOT BE PERMITTED UNLESS SPECIFICALLY DETAILED ON THE DRAWINGS OR SEALED DESIGN CALCULATIONS ARE SUBMITTED WITH THE SHOP DRAWINGS.
 - THE MINIMUM NUMBER OF BOLTS IN BOLTED CONNECTIONS SHALL BE TWO (2) BOLTS
 - MINIMUM 1/4" FILLET WELD SHALL APPLY UNLESS NOTED OTHERWISE.
- TRUSS AND BRACING MEMBER CONNECTIONS SHALL BE DESIGNED FOR THE FORCES INDICATED ON THE DRAWINGS
- TYPICAL CONNECTION DETAILS INDICATED ON THE STRUCTURAL DESIGN DRAWINGS SHALL DICTATE THE FORM AND GEOMETRY OF THE CONNECTIONS. THE FABRICATOR SHALL DETERMINE OR VERIFY TYPE, SIZE AND NUMBER OF BOLTS, PLATE THICKNESS AND SIZES, WELD SIZES AND LENGTHS, AND ALL REQUIRED INFORMATION NOT SPECIFIED ON THE TYPICAL CONNECTION DETAILS.
- THE DESIGN OF ALL STEEL CONNECTIONS (EXCEPT PREDESIGNED CONNECTIONS THAT HAVE BEEN ENGINEERED ON THESE DRAWINGS) SHALL BE PERFORMED UNDER THE DIRECT SUPERVISION OF A PROFESSIONAL ENGINEER REGISTERED IN THE STATE OF THE PROJECT, EMPLOYED BY THE FABRICATOR. THE FABRICATOR'S REGISTERED PROFESSIONAL ENGINEER SHALL SUBMIT COMPLETE DESIGN CALCULATIONS FOR EACH CONNECTION. SUCH CALCULATIONS SHALL SHOW DETAILS OF THE ASSEMBLED JOINT WITH ALL BOLTS AND WELDS REQUIRED.
- ALL DESIGN CALCULATIONS SHALL BE SEALED BY THE FABRICATOR'S PROFESSIONAL ENGINEER REGISTERED IN THE STATE OF [OHIO]. SHOP DRAWINGS SUBMITTED WITHOUT COMPLETE DESIGN CALCULATIONS WILL NOT BE REVIEWED.
- WELDING ELECTRODES SHALL BE E 70XX OR BETTER, FOR WELDING SYMBOLS WITH NO LENGTH DIMENSION GIVEN, THE WELDING SHALL BE CONTINUOUS BETWEEN ABRUPT CHANGES IN DIRECTION.
- UTILIZE SLIP CRITICAL BOLTS AT ALL MOMENT CONNECTIONS, HANGING CONNECTIONS, BRACING CONNECTIONS, AND COLUMN SPLICES.
- ALL STRUCTURAL STEEL MEMBERS EXPOSED TO THE EXTERIOR SHALL BE GALVANIZED UNLESS NOTED OTHERWISE. THIS INCLUDES BUT IS NOT LIMITED TO MASONRY LINTELS AND SHELF ANGLES, INCLUDING BEARING PLATES AND ANCHOR BOLTS, AND ANY OTHER ITEM LISTED ON THE ARCHITECTURAL OR STRUCTURAL DRAWINGS.
- THE FRAMING SHALL BE ERECTED TRUE AND PLUMB. TEMPORARY BRACING SHALL BE PROVIDED AND SHALL REMAIN IN PLACE UNTIL THE LATERAL BRACING SYSTEM IS IN PLACE AND CONNECTIONS OF ALL MEMBERS ARE FINAL AND ALL DECK IS COMPLETELY ERECTED, WELDED AND SCREWED IN PLACE.
- NON-METALLIC, NON-SHRINK, NON-STAINING GROUT UNDER ALL COLUMN BASE PLATES AND BEAM BEARING PLATES SHALL CONSIST OF A PREMIXED PRODUCT COMPLYING WITH ALL REQUIREMENTS OF CRD-0621, ASTM C827, AND C109.
- STUD TYPE EXPANSION ANCHORS SHALL BE CARBON STEEL (UNLESS NOTED OTHERWISE ON DRAWINGS) CONFORMING TO THE REQUIREMENTS OF THE MANUFACTURER'S RECOMMENDATIONS. SEE DRAWINGS FOR LOCATIONS AND TYPE.
- ALL STRUCTURAL STEEL MEMBERS (BEAMS AND COLUMNS) ADJACENT TO OR BUILT INTO MASONRY CONSTRUCTION SHALL BE PROVIDED WITH 12 GAUGE GALVANIZED WELD-ON CHANNEL SLOTS AND 3/16" x 1 1/4" HOOKED GALVANIZED ANCHORS, SPACED 16" ON CENTER VERTICALLY AND 24" ON CENTER HORIZONTALLY, MAXIMUM.
- ALL DISSIMILAR METALS TO BE SEPARATED BY ELECTROLYTIC SEPARATORS
- DO NOT PAINT:
 - SURFACES OF CONNECTIONS INDICATED AS SLIP CRITICAL.
 - SURFACES OF CONNECTIONS TO BE FIELD WELDED.
 - SURFACES TO RECEIVE HEADED SHEAR CONNECTIONS.
 - MEMBERS TO BE EMBEDDED IN CONCRETE OR MASONRY.
 - SURFACES TO RECEIVE SPRAYED ON INSULATION.
 - MEMBERS TO BE GALVANIZED.

STEEL DECK:

- DETAIL, FABRICATE AND ERECT STEEL DECK IN ACCORDANCE WITH THE LATEST STEEL DECK INSTITUTE SPECIFICATIONS, AWS AND CONTRACT DOCUMENTS. DECK SHALL CONFORM TO "BASIC DESIGN SPECIFICATIONS" AS ADOPTED BY THE STEEL DECK INSTITUTE.
- ROOF DECK PROFILE SHALL CONFORM TO FACTORY MUTUAL REQUIREMENTS.
- ROOF DECK SHALL BE MANUFACTURED FROM STEEL CONFORMING TO ASTM A511 GRADE C, D OR E, GR 33 OR HIGHER.
- COMPOSITE FLOOR DECK SHALL BE MANUFACTURED FROM STEEL CONFORMING TO ASTM A553-94, GR 33 OR HIGHER.
- COMPOSITE FLOOR DECK SHALL GALVANIZED & CONFORM TO ASTM A924-94, CLASS G-90.
- ROOF DECK SHALL BE [GALVANIZED AND SHOP PRIMED][GALVANIZED] [PRIMED].
- ROOF DECK SHALL BE CONNECTED TO SUPPORTING STRUCTURAL STEEL MEMBERS WITH A [5/16"] PATTERN WITH [5/16"] X [5/16"] X [5/16"] POWDER ACTUATED FASTENERS) WITH THE FIRST AND LAST RIBS OF EACH SHEET ATTACHED TO THE SUPPORTS. SIDELAPS SHALL BE SCREWED WITH (3) #10 SELF TAPPING SCREWS.
- DECK SHALL INCLUDE ANY MISCELLANEOUS CLOSURE PIECES, POUR STOPS, DRAIN SUMP PANS, REINFORCING AROUND OPENINGS, ETC. REQUIRED TO MAKE A COMPLETE JOB. MISCELLANEOUS ITEMS SHALL BE GALVANIZED G90.
- NO LOADS SHALL BE HUNG FROM THE ROOF DECK.
- ALL DECK LIGHTER THAN 22 GA SHALL USE WELDING WASHERS FOR CONNECTION OF DECK TO STEEL SUPPORT.
- PLACE DECK UNITS ON SUPPORTING STEEL FRAMEWORK IN LENGTHS TO SPAN 4 OR MORE SUPPORTS (3 SPANS). LAP ENDS OF DECK NOT LESS THAN 2". SIDE LAP INTERLOCKS SHALL NOT BE STRETCHED OR CONTRACTED. DECK SHALL BEAR A MINIMUM OF 3" ON SUPPORTS.
- MAXIMUM SIZE OF OPENINGS IN DECK WITHOUT STRUCTURAL FRAMING SUPPORT SHALL NOT EXCEED 10". OPENINGS GREATER THAN 10" MUST HAVE STRUCTURAL SUPPORT ON ALL SIDES OF THE OPENING.
- FOR SLOPING DECK PROVIDE CONTINUOUS SHIMS, AS REQUIRED TO ACHIEVE FULL DECK BEARING ON SUPPORTING MEMBERS.

DEFERRED STRUCTURAL SUBMITTALS:

- SOME STRUCTURAL SYSTEMS ARE DEFINED AS VENDOR-DESIGNED COMPONENTS PER THE STRUCTURAL DOCUMENTS. THESE ELEMENTS OF THE DESIGN ARE DEFERRED SUBMITTAL COMPONENTS AND HAVE NOT BEEN PERMITTED UNDER THE BASIC BUILDING APPLICATION.
- DOCUMENTS FOR DEFERRED SUBMITTAL ITEMS SHALL BE SUBMITTED TO THE ARCHITECT, WHO SHALL REVIEW THEM FOR GENERAL CONFORMANCE TO THE DESIGN OF THE BUILDING. THE CONTRACTOR SHALL SUBMIT THESE REVIEWED DEFERRED SUBMITTAL DOCUMENTS TO THE BUILDING OFFICIAL. THE DEFERRED SUBMITTAL ITEMS SHALL NOT BE INSTALLED UNTIL THE DESIGN AND SUBMITTAL DOCUMENTS HAVE BEEN APPROVED BY THE BUILDING OFFICIAL. DOCUMENTS FOR DEFERRED SUBMITTAL ITEMS SHALL BE SIGNED AND SEALED BY A REGISTERED PROFESSIONAL ENGINEER.
 - EXTERIOR CLADDING
 - METAL STAIRS
- THE FOLLOWING LIST INCLUDES THE ITEMS THAT DEFINED AS DEFERRED STRUCTURAL SUBMITTAL COMPONENTS. REFER TO THE ARCHITECTURAL, MECHANICAL, ELECTRICAL AND CIVIL DRAWINGS FOR ADDITIONAL SUBMITTAL COMPONENTS.

SPECIAL INSPECTIONS:

- THE FOLLOWING ITEMS REQUIRE SPECIAL INSPECTION AND TESTING PER IBC SECTION 1704.
- THIS WORK SHALL BE PERFORMED BY A SPECIAL INSPECTOR CERTIFIED BY THE GOVERNING MUNICIPALITY WHERE THE PROJECT IS LOCATED TO PERFORM THE TYPES OF INSPECTIONS AND TESTS SPECIFIED.
- THE FREQUENCY OF INSPECTIONS AND TESTING SHALL BE AS OUTLINED IN THE IBC TABLE ITEMS LISTED BELOW.
 - DEFICIENCIES SHALL BE REPORTED DAILY TO THE CONTRACTOR.
 - SUMMARY REPORTS SHALL BE DISTRIBUTED WEEKLY TO THE OWNER, ARCHITECT, CONTRACTOR, BUILDING OFFICIAL AND STRUCTURAL ENGINEER.
- SEE THE SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS FOR SPECIAL INSPECTION AND TESTING.

STRUCTURAL TESTS AND SPECIAL INSPECTIONS		
(PER IBC CHAPTER 17)		
CONSTRUCTION MATERIAL	APPLICABLE OBC SECTION /TABLE	ITEMS REQUIRING VERIFICATION AND INSPECTION
STRUCTURAL STEEL	SECTION 1705 2.1	PER ASCI 360 - CHAPTER N



MATTHAEI
HVAC STUDY &
SCHEMATIC

WAYNE STATE
UNIVERSITY

DETROIT MI 48208

TAG	ISSUED	DATE
1	FOR BIDDING	08/08/22
2	FOR RE-BIDDING	10/24/22



Unless otherwise stated in Contract, The Osborn Engineering Company retains copyright ownership. Instruments of Service may only be used for the purpose described in the Contract. The Osborn Engineering Company may grant specific usage rights under license, and/or may transfer copyright ownership/ assignment in writing. Reproduction, re-use or re-distribution of Instruments of Service is prohibited.

DRAWN BY: KC
CHECKED BY: JL
CLIENT PROJ NO:
OSBORN PROJ NO: J20220270.000

GENERAL
NOTES


DRAWING NO.
S-001

F
E
D
C
B
A



2 LOW ROOF ENLARGED FRAMING PLAN: RTU-103
SCALE: 1/4" = 1'-0"

3 LOW ROOF ENLARGED FRAMING PLAN: STAIR
SCALE: 1/4" = 1'-0"



1 LOW ROOF OVERALL FRAMING PLAN
SCALE: 1/16" = 1'-0"

ROOF FRAMING NOTES

1. REFERENCE: GENERAL NOTES - S-001
2. VERIFY ALL ELEVATIONS AND DIMENSIONS SHOWN WITH ARCHITECTURAL DRAWINGS AND EQUIPMENT SUPPLIERS SHOP DRAWINGS PRIOR TO FABRICATION AND INSTALLATION OF STRUCTURAL STEEL
3. TOP OF STEEL ELEVATION = 112' - 9 1/2"
4. ROOF CONSTRUCTION:
A. 1 1/2"x20GA GALVANIZED WIDE RIB METAL ROOF DECK
5. GENERAL CONTRACTOR SHALL COORDINATE ROOF TOP UNIT DIMENSIONS WITH APPROVED RTU MANUFACTURER DRAWINGS.
6. SUPPORT FRAMING SHOWN IS FOR THE RTU'S SPECIFIED ON MECHANICAL DRAWING. IF A DIFFERENT UNIT IS TO BE USED, CONTACT STRUCTURAL ENGINEER BEFORE PROCEEDING.
7. SET UNIT CURB ON EXISTING ROOF FRAMING MEMBERS OR SUPPORT MEMBERS RUNNING BETWEEN THEM. DO NOT PLACE CURB ON UNSUPPORTED ROOF DECK.
8. FIELD VERIFY ALL DIMENSIONS PRIOR TO FINAL DETAILING AND FABRICATION. IF ANY EXISTING CONDITION IS NOT AS SHOWN, CONTACT A/E BEFORE PROCEEDING WITH WORK.
9. COORDINATE LOCATION, SIZE, AND QUANTITY OF ROOF OPENINGS AND PENETRATIONS (HATCHES, EXHAUST FAN, ETC.) WITH ARCHITECTURAL, MECHANICAL, AND ELECTRICAL DRAWINGS.
10. PROVIDE ROOF OPENING FRAMING FOR ALL OPENINGS AND PENETRATIONS THROUGH THE ROOF PER TYPICAL DETAIL.



MATTHAEI
HVAC STUDY &
SCHEMATIC

WAYNE STATE
UNIVERSITY

DETROIT MI 48208

TAG	ISSUED	DATE
1	FOR BIDDING	08/08/22
2	FOR RE-BIDDING	10/24/22


Unless otherwise stated in Contract, The Osborn Engineering Company retains copyright ownership. Instruments of Service may only be used for the purpose described in the Contract. The Osborn Engineering Company may grant specific usage rights under license, and/or may transfer copyright ownership/ assignment in writing. Reproduction, re-use or re-distribution of Instruments of Service is prohibited.

DRAWN BY: KC
CHECKED BY: JL
CLIENT PROJ NO:
OSBORN PROJ NO: J20220270.000

LOW ROOF
FRAMING
PLANS

DRAWING NO.
S-101

F
E
D
C
B
A



ROOF FRAMING NOTES

1. REFERENCE: GENERAL NOTES - S-001
2. VERIFY ALL ELEVATIONS AND DIMENSIONS SHOWN WITH ARCHITECTURAL DRAWINGS AND EQUIPMENT SUPPLIERS SHOP DRAWINGS PRIOR TO FABRICATION AND INSTALLATION OF STRUCTURAL STEEL.
3. TOP OF STEEL ELEVATION = 124' - 10 1/2"
4. ROOF CONSTRUCTION:
A. 1 1/2"x20GA GALVANIZED WIDE RIB METAL ROOF DECK
5. GENERAL CONTRACTOR SHALL COORDINATE ROOF TOP UNIT DIMENSIONS WITH APPROVED RTU MANUFACTURER DRAWINGS.
6. SUPPORT FRAMING SHOWN IS FOR THE RTU'S SPECIFIED ON MECHANICAL DRAWING. IF A DIFFERENT UNIT IS TO BE USED, CONTACT STRUCTURAL ENGINEER BEFORE PROCEEDING.
7. SET UNIT CURB ON EXISTING ROOF FRAMING MEMBERS OR SUPPORT MEMBERS RUNNING BETWEEN THEM. DO NOT PLACE CURB ON UNSUPPORTED ROOF DECK.
8. FIELD VERIFY ALL DIMENSIONS PRIOR TO FINAL DETAILING AND FABRICATION. IF ANY EXISTING CONDITION IS NOT AS SHOWN, CONTACT A/E BEFORE PROCEEDING WITH WORK.
9. COORDINATE LOCATION, SIZE, AND QUANTITY OF ROOF OPENINGS AND PENETRATIONS (HATCHES, EXHAUST FAN, ETC.) WITH ARCHITECTURAL, MECHANICAL, AND ELECTRICAL DRAWINGS.
10. PROVIDE ROOF OPENING FRAMING FOR ALL OPENINGS AND PENETRATIONS THROUGH THE ROOF PER TYPICAL DETAIL.



**MATTHAEI
HVAC STUDY &
SCHEMATIC**

**WAYNE STATE
UNIVERSITY**

DETROIT MI 48208

TAG	ISSUED	DATE
1	FOR BIDDING	08/08/22
2	FOR RE-BIDDING	10/24/22

Unless otherwise stated in Contract, The Osborn Engineering Company retains copyright ownership. Instruments of Service may only be used for the purpose described in the Contract. The Osborn Engineering Company may grant specific usage rights under license, and/or may transfer copyright ownership/ assignment in writing. Reproduction, re-use or re-distribution of Instruments of Service is prohibited.

DRAWN BY: KC
CHECKED BY: JL
CLIENT PROJ NO:
OSBORN PROJ NO: J20220270.000


**INTERMEDIATE
ROOF FRAMING
PLAN**

DRAWING NO.

S-102


1 INTERMEDIATE ROOF T/STL

SCALE: 1/16" = 1'-0"




1 INTERMEDIATE ROOF ENLARGED FRAMING PLAN: RTU-101

SCALE: 1/4" = 1'-0"




2 INTERMEDIATE ROOF ENLARGED FRAMING PLAN: RTU-106

SCALE: 1/4" = 1'-0"




2 INTERMEDIATE ROOF ENLARGED FRAMING PLAN: RTU-102 & RTU-104

SCALE: 1/4" = 1'-



4 INTERMEDIATE ROOF ENLARGED FRAMING PLAN: RTU-107

SCALE: 1/4" = 1'-




5 INTERMEDIATE ROOF ENLARGED FRAMING PLAN: STAIR

SCALE: 1/4" = 1'-0"

- ### ROOF FRAMING NOTES

1. REFERENCE: GENERAL NOTES - S-001
2. VERIFY ALL ELEVATIONS AND DIMENSIONS SHOWN WITH ARCHITECTURAL DRAWINGS AND EQUIPMENT SUPPLIERS SHOP DRAWINGS PRIOR TO FABRICATION AND INSTALLATION OF STRUCTURAL STEEL.
3. TOP OF STEEL ELEVATION = 124' - 10 1/2"
4. ROOF CONSTRUCTION:
 - A. 1 1/2"x2GA GALVANIZED W/BE RIB METAL ROOF DECK
5. GENERAL CONTRACTOR SHALL COORDINATE ROOF TOP UP WITH DIMENSIONS WITH APPROVED RTU MANUFACTURER DRAWINGS.
6. SUPPORT FRAMING SHOWN IS FOR THE RTU'S SPECIFIED ON MECHANICAL DRAWING. IF A DIFFERENT UNIT IS TO BE USED, CONTACT STRUCTURAL ENGINEER BEFORE PROCEEDING.
7. SET UP CURB ON EXISTING ROOF FRAMING MEMBERS OR SUPPORT MEMBERS RUNNING BETWEEN THEM. DO NOT PLACE CURB ON UNSUPPORTED ROOF DECK.
8. FIELD VERIFY ALL DIMENSIONS PRIOR TO FINAL DETAILING AND FABRICATION. IF ANY EXISTING CONDITION IS NOT AS SHOWN, CONTACT A/E BEFORE PROCEEDING WITH WORK.
9. COORDINATE LOCATION, SIZE, AND QUANTITY OF ROOF OPENINGS AND PENETRATIONS (HATCHES, EXHAUST FAN ETC.) WITH ARCHITECTURAL, MECHANICAL, AND ELECTRICAL DRAWINGS.
10. PROVIDE ROOF OPENING FRAMING FOR ALL OPENINGS AND PENETRATIONS THROUGH THE ROOF PER TYPICAL DETAIL.



MATTHAEI
IVAC STUDY &
SCHEMATIC

WAYNE STATE
UNIVERSITY

ETROIT MI 48208

[illegible]

Unless otherwise stated in Contract, The Osborn Engineering Company retains copyright ownership. Instruments of Service may only be used for the purpose described in the Contract. The Osborn Engineering Company may grant specific usage rights under license, and/ or may transfer copyright ownership/assignment in writing. Reproduction, use or re-distribution of Instruments of Service is prohibited.

DRAWN BY	KC
CHECKED BY	JL
CLIENT PROJ NO	
OSBORN PROJ NO	J20220270.000



ENLARGED
INTERMEDIATE
ROOF FRAMING
PLANS


DRAWING NO.

6-102.1



1 HIGH ROOF T/STL
SCALE: 1/16" = 1'-0"


- 
- WAYNE STATE**
-
- 
- OSBORN
ENGINEERING**
- 3000 Telegraph Road | Brighton Farms, MI 48009
(313) 955-4014 www.osborn-eng.com



Unless otherwise stated in Contract, The Osborn Engineering Company retains copyright ownership. Instruments of Service may only be used for the purpose described in the Contract. The Osborn Engineering Company may grant specific usage rights under license, and/ or may transfer copyright ownership/ assignment in writing. Reproduction, re-use or re-distribution of Instruments of Service is prohibited.


HIGH ROOF
 FRAMING PLAN
 DRAWING NO.
 S-103

F
E
D
C
B
A




**1 TYPICAL JOIST REINFORCING
DETAIL AT CONCENTRATED LOADS**

SCALE: 1" = 1'-0"




2 TYPICAL ROOFTOP EQUIPMENT SUPPORT DETAIL

SCALE: 1" = 1'-0"




3 TYPICAL METAL DECK SUPPORT AT STEEL JOISTS


SCALE: 3/4" = 1'-0"



A SECTION




B VIEW




4 TYPICAL METAL DECK SUPPORT AT STEEL BEAMS

SCALE: 3/4" = 1'-0"



5 HANDRAIL POST DETAIL

SCALE: 1" = 1'-0"



6 TYPICAL HSS TO HSS CONNECTION DETAIL

SCALE: 3/4" = 1'-0"



**MATTHAEI
HVAC STUDY &
SCHEMATIC**

**WAYNE STATE
UNIVERSITY**

DETROIT MI 48208

TAG	ISSUED	DATE
1	FOR BIDDING	08/08/22
2	FOR RE-BIDDING	10/24/22

Unless otherwise stated in Contract, The Osborn Engineering Company retains copyright ownership. Instruments of Service may only be used for the purpose described in the Contract. The Osborn Engineering Company may grant specific usage rights under license, and/or may transfer copyright ownership/ assignment in writing. Reproduction, re-use or re-distribution of Instruments of Service is prohibited.

DRAWN BY: KC
CHECKED BY: JL
CLIENT PROJ NO:
OSBORN PROJ NO: J20220270.000

**STRUCTURAL
DETAILS**

DRAWING NO.

S-501

F

E

- D

C

- B

ith A



1

4

6


6

7



HVAC NOTES & LEGENDS

M-001




GENERAL DEMOLITION NOTES

- IN EVERY INSTANCE OF DEMOLITION AND/OR REMODELING, THE MECHANICAL CONTRACTOR SHALL FIGURE A COMPLETE JOB AS NON-RECURRING. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ACCESS TO THE DRAWINGS ARE TO BE USED ONLY AS A GUIDELINE FOR DEMOLITION. THE MECHANICAL CONTRACTOR MUST VISIT THE SITE PRIOR TO BIDING TO OBTAIN A COMPLETE UNDERSTANDING OF THE WORK AND THE COST OF SUCH WORK IN THEIR BID.
- THE CONTRACTOR SHALL MAINTAIN EXISTING SERVICES TO REMAIN AND IN THE EXISTING AREA AS REQUIRED.
- IF NECESSARY, THE MECHANICAL CONTRACTOR SHALL PROVIDE THE FOLLOWING SERVICES IN THE EXISTING AREA:
- ALL MECHANICAL EQUIPMENT AND DEVICES SHOWN AS BEING REMOVED SHALL BE REMOVED COMPLETELY INCLUDING SUPPORTING STEEL AND CONCRETE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVED SHALL BE REPLACED WITH STEEL COVER PLATE.
 - ALL EXISTING DEVICES, INCLUDING BUT NOT LIMITED TO THE WORK SHALL BE RETURNED TO FINISHED CONDITIONS TO MATCH EXISTING BY THE MECHANICAL CONTRACTOR AND THEY SHALL DO THEIR OWN CUTTING AND REMOVAL OF EXISTING EQUIPMENT AND MATERIALS.
 - ALL EXISTING EQUIPMENT AND MATERIALS SHALL BE TURNED OVER TO THE UNIVERSITY. IF NOT REQUIRED BY THE UNIVERSITY, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION, STORAGE, MAINTENANCE AND DISPOSAL OF IN A LEGAL MANNER.
- THE CONTRACTOR SHALL COORDINATE WITH CONSTRUCTION MANAGER AND UNIVERSITY TO CONDUCT TESTING AND ABATEMENT OF ANY HAZARDOUS MATERIAL PRIOR TO STARTING ANY DEMOLITION WORK. CONTRACTOR SHALL PROTECT ALL EXISTING EQUIPMENT TO REMAIN DURING CONSTRUCTION.

SHEET KEYNOTES

1. REMOVE FAN COIL UNIT AND ALL ASSOCIATED REFRIGERANT PIPING. CONTRACTOR RESPONSIBLE FOR ALL DEMOLITION OF EXISTING CEILINGS TO REMOVE UNIT.
2. NOT USED
3. SUPPLY BRANCH DUCTS, RUNOUTS TO DIFFUSERS, AND DIFFUSERS TO REMAIN. PREPARE DUCTWORK FOR RECONNECTION UNDER NEW WORK SCOPE.
4. ALL DUCTWORK ASSOCIATED WITH HV-7 TO BE ABANDONED IN PLACE.
5. ALL DUCTWORK AND DIFFUSERS WITH-IN ATHLETIC ADMINISTRATION TO REMAIN.



PLAN
NORTH

1 HVAC ENLARGED DEMOLITION FLOOR PLAN
SCALE: 1/8" = 1'-0" 0' 2' 4' 8' 16'

SCALE: 1/8" = 1'-0"

[illegible]

Unless otherwise stated in Contract, the Osborn Engineering Company retains copyright ownership. Instruments of Service may only be used for the purpose described in the contract. The Osborn Engineering Company may grant specific usage rights under license, and / or may transfer copyright ownership / assignment in writing. Reproduction, use or re-distribution of Instruments of Service is prohibited.

AWN BY	KAJ
ECKED BY	DVL
IENT PROJ NO.	-
BORN PROJ NO.	J20220270.000

VAC ENLARGED ADDITION FLOOR PLAN


DRAWING NO.

MD-103

P:\Wayne State University\2022\20270.000_Matthaei_HVAC_Study\Drawings\Matthaei-M-101 HVAC MAIN LEVEL FLOOR PLAN.DWG
11/2/2022 3:37 PM Johnson, Keith

GENERAL NOTES

- THESE DRAWINGS ARE DIAGRAMMATIC AND INDICATE THE GENERAL EXTENT OF THE WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE COORDINATION AND PROPER INSTALLATION OF ALL MECHANICAL SYSTEMS. THE CONTRACTOR SHALL PROVIDE ALL NECESSARY OFFSETS AND FITTINGS WHICH MAY BE REQUIRED DUE TO SPACE CONSTRAINTS OR OTHER CONDITIONS.
- THE CONTRACTOR SHALL PROVIDE ALL MISCELLANEOUS SUPPORTING STEEL, ETC. FOR THE PROPER INSTALLATION OF ALL MECHANICAL SYSTEMS.
- THE CONTRACTOR SHALL COORDINATE FLOOR, WALL AND ROOF PENETRATIONS, ETC. WITH GENERAL TRADES.
- THE CONTRACTOR SHALL VERIFY ALL CLEARANCES PRIOR TO FABRICATION OF ANY WORK.
- THE CONTRACTOR SHALL COORDINATE THE LOCATION OF CEILING GRILLES, REGISTERS AND DIFFUSERS WITH THE ARCHITECTURAL REFLECTED CEILING PLANS.
- DUCTWORK SHALL NOT BE LOCATED OVER THE TOP OF ANY ELECTRICAL PANELS OR EQUIPMENT.
- THE CONTRACTOR SHALL COORDINATE AND PROVIDE ACCESS DOORS IN HARD CEILINGS FOR ALL EQUIPMENT WHICH REQUIRES ACCESS, SUCH AS FIRE AND SMOKE DAMPERS, SMOKE DETECTORS, BALANCING DAMPERS, VAV BOXES, ETC.
- ALL MECHANICAL EQUIPMENT, PIPING, VALVES, DAMPERS, SMOKE DETECTORS ETC. WHICH REQUIRE ROUTINE MAINTENANCE OR INSPECTION SHALL BE INSTALLED WITHIN 2 FT OF THE FINISHED CEILING HEIGHT.
- CONTRACTOR SHALL ENSURE THAT ALL MATERIALS USED IN RETURN AIR PLENUMS ARE PLENUM-RATED.
- DUCT SIZES ON THE DRAWINGS DESIGNATE THE FREE AREA DIMENSIONS. THE ACTUAL SHEET METAL SIZES SHALL BE INCREASED TO ACCOUNT FOR LINING WHERE REQUIRED. REFER TO DETAILS AND SPECIFICATIONS FOR LINING REQUIREMENTS.




2 SECTION THRU RTU-105

NOT TO SCALE

SHEET KEYNOTES

- DRUM LOUVER TO BE MOUNTED 30° BELOW HORIZONTAL, TYPICAL ALL DRUM LOUVERS.
- RETURN AIR DUCT, FULL SIZE OF UNIT OPENING, 1" INTERNALLY LINED DUCT WITH 90° ELBOW.
- MC TO FIELD VERIFY PENETRATION OF PARTITION TO AVOID STRUCTURAL MEMBERS.
- FABRIC COVERING OF SUPPORT FOR CURTAIN TRACK MC TO VERIFY DUCT OPENING THROUGH FABRIC WILL NOT WITH CABLING. MC TO VERIFY WITH CURTAIN MANUFACTURER ACCEPTABLE MEANS OF PENETRATION.
- 1" CONDENSATE PIPE DOWN TO DRAIN MECHANICAL ROOM 33.1 ON LOWER LEVEL.
- VRF SYSTEM IS TO SUBMITTED AS DEDUCT ALTERNATE 1.



OSBORN
ENGINEERING
6001 Michigan Road | Brighton, MI 48020
313.975.4874 | www.osborn-eng.com

MATTHAEI
CENTER
ADDITION OF AIR
CONDITIONING
WAYNE STATE
UNIVERSITY

DETROIT, MI 48208

TAG	ISSUED	DATE
FOR BIDDING	06/08/22	
FOR RE-BIDDING	10/24/22	

Unless otherwise stated in Contract, The Osborn Engineering Company retains copyright ownership. Instruments of Service may only be used for the purpose described in the Contract. The Osborn Engineering Company may grant specific usage rights under license, and / or may transfer copyright ownership / assignment in writing. Reproduction, reuse or re-distribution of Instruments of Service is prohibited.

DRAWN BY KAJ
CHECKED BY DVL
CLIENT PROJ NO.
OSBORN PROJ NO. J20220270.000

HVAC MAIN LEVEL
FLOOR PLAN

DRAWING NO.

M-101



CSBORN
ENGINEERING
10 Telegraph Road | Bingham Farms, MI 48025
48014 www.csborn-eng.com

MATTHAEI
CENTER
DIVISION OF AIR
CONDITIONING
WAYNE STATE
UNIVERSITY

ROIT, MI 48208

[illegible]

Unless otherwise stated in Contract, the Osborn Engineering Company retains copyright ownership. Instruments of Service may only be used for the purpose described in the contract. The Osborn Engineering Company may grant specific usage rights under license, and / or may transfer copyright ownership / assignment in writing. Reproduction, use or re-distribution of Instruments of Service is prohibited.

AWN BY	KAJ
ECKED BY	DVL
IENT PROJ NO.	-
BORN PROJ NO.	J20220270.000

VAC ROOF
PLAN

DRAWING NO.


1-102

GENERAL NOTES

- | | | | |
|----|--|-----|---|
| 1. | THESE DRAWINGS ARE DIAGRAMMATIC AND INDICATE THE GENERAL EXTENT OF THE WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE COORDINATION AND PROPORTIONING OF ALL MECHANICAL AND ELECTRICAL SYSTEMS. THE CONTRACTOR SHALL PROVIDE TO SPACE CONSTRAINTS AND FITTINGS WHICH MAY BE REQUIRED DUE TO SPACE CONSTRAINTS OR OTHER CONDITIONS. | 6. | DUCTWORK SHALL NOT BE LOCATED OVER THE TOP OF ANY ELECTRICAL PANELS OR EQUIPMENT. |
| 2. | THE CONTRACTOR SHALL PROVIDE ALL MISCELLANEOUS SUPPORTING STEEL, ETC. FOR THE PROPER INSTALLATION OF ALL MECHANICAL SYSTEMS. | 7. | THE CONTRACTOR SHALL COORDINATE AND PROVIDE ACCESS DOORS IN HARD CEILINGS FOR AIR EQUIPMENT WHICH REQUIRES ACCESS, SUCH AS FIRE AND SMOKE DAMPERS, SMOKE DETECTORS, BALANCING DAMPERS, VAV BOXES, ETC. |
| 3. | THE CONTRACTOR SHALL COORDINATE FLOOR, WALL AND ROOF PENETRATIONS, ETC. WITH GENERAL TRADES. | 8. | ALL MECHANICAL EQUIPMENT, PIPING, VALVES, DAMPERS, SMOKE DETECTORS ETC., WHICH REQUIRE ROUTING MAINTENANCE OR INSPECTION SHALL BE INSTALLED WITHIN 2FT OF THE FINISHED CEILING HEIGHT. |
| 4. | THE CONTRACTOR SHALL VERIFY ALL CLEARANCES PRIOR TO FABRICATION OF ANY WORK. | 9. | THE CONTRACTOR SHALL ENSURE THAT ALL MATERIALS USED IN RETURN AIR PLENUMS ARE PLENUM-RATED. |
| 5. | THE CONTRACTOR SHALL COORDINATE THE LOCATION OF CEILING GRILLERS, REGISTERS AND DIFFUSERS WITH THE ARCHITECTURAL REFLECTED CEILING PLANS. | 10. | DUCT SIZES ON THE DRAWINGS DESIGNATE THE FREE AREA DIMENSIONS. THE ACTUAL SHEET METAL SIZES SHALL BE INCREASED TO ACCOUNT FOR LINING WHERE REQUIRED. REFER TO DETAILS AND SPECIFICATIONS FOR LINING REQUIREMENTS. |


SHEET KEYNOTES

- SA & AR DOWN THRU ROOF CONNECTING TO EXISTING DUCTWORK
IN MECHANICAL ROOM. REFER TO ENLARGED PLANS
PROVIDE SAFETY RAIL AS REQUIRED.
SA DOWN THRU ROOF CONNECTING TO EXISTING SUPPLY
DUCTWORK IN MECHANICAL ROOM. REFER TO ENLARGED PLANS
PROVIDE CURB ADAPTER FOR NEW ROOFTOP UNIT.
CONNECT 1" G TO EXISTING 4" NATURAL GAS LINE ON ROOF AND
ROUTE TO RTU-108.
CONNECT 2" G TO EXISTING 4" NATURAL GAS LINE ON ROOF AND
ROUTE TO RTU-103.
VRF SYSTEM IS TO SUBMITTED AS DEDUCT ALTERNATE 1.




P:\Wayne State University\J2022\20270.000_Matthaei_HVAC_Study\Drawings\MechM-102 HVAC ROOF PLAN.dwg
11/2/2022 3:38 PM Johnson Keith


P:\Wayne State University\2022\2020_000_Matthaei_HVAC_Study\Drawings\Mech\N-303 HVAC ENLARGED NORTH WEST FLOOR PLAN.dwg
10/24/2022 6:47 AM Johnson, Keith



1 HVAC ENLARGED NORTH WEST FLOOR PLAN
SCALE: 1/8" = 1'-0"

- GENERAL NOTES**
- THESE DRAWINGS ARE DIAGRAMMATIC AND INDICATE THE GENERAL EXTENT OF THE WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE COORDINATION AND PROPER INSTALLATION OF ALL MECHANICAL SYSTEMS. THE CONTRACTOR SHALL PROVIDE ALL NECESSARY OFFSETS AND FITTINGS WHICH MAY BE REQUIRED DUE TO SPACE CONSTRAINTS OR OTHER CONDITIONS.
 - THE CONTRACTOR SHALL PROVIDE ALL MISCELLANEOUS SUPPORTING STEEL, ETC. FOR THE PROPER INSTALLATION OF ALL MECHANICAL SYSTEMS.
 - THE CONTRACTOR SHALL COORDINATE FLOOR, WALL AND ROOF PENETRATIONS, ETC. WITH GENERAL TRADES.
 - THE CONTRACTOR SHALL VERIFY ALL CLEARANCES PRIOR TO FABRICATION OF ANY WORK.
 - THE CONTRACTOR SHALL COORDINATE THE LOCATION OF CEILING GRILLES, REGISTERS AND DIFFUSERS WITH THE ARCHITECTURAL REFLECTED CEILING PLANS.
 - DUCTWORK SHALL NOT BE LOCATED OVER THE TOP OF ANY ELECTRICAL PANELS OR EQUIPMENT.
 - THE CONTRACTOR SHALL COORDINATE AND PROVIDE ACCESS DOORS IN HARD CEILINGS FOR ALL EQUIPMENT WHICH REQUIRES ACCESS, SUCH AS FIRE AND SMOKE DAMPERS, SMOKE DETECTORS, BALANCING DAMPERS, VAV BOXES, ETC.
 - ALL MECHANICAL EQUIPMENT, PIPING, VALVES, DAMPERS, SMOKE DETECTORS ETC. WHICH REQUIRE ROUTINE MAINTENANCE OR INSPECTION SHALL BE INSTALLED WITHIN 2FT OF THE FINISHED CEILING HEIGHT.
 - CONTRACTOR SHALL ENSURE THAT ALL MATERIALS USED IN RETURN AIR PLENUMS ARE PLENUM-RATED.
 - DUCT SIZES ON THE DRAWINGS DESIGNATE THE FREE AREA DIMENSIONS. THE ACTUAL SHEET METAL SIZES SHALL BE INCREASED TO ACCOUNT FOR LINING WHERE REQUIRED. REFER TO DETAILS AND SPECIFICATIONS FOR LINING REQUIREMENTS.
- SHEET KEYNOTES**
- EXISTING SUPPLY AIR DUCTWORK UP TO HV-1 AND RTU-101.
 - ALL AIR DISTRIBUTION IN ATHLETIC ADMINISTRATION SUITE TO REMAIN. ROOF TOP UNIT RTU-108 TO REPLACE EXISTING UNIT. EXISTING THERMOSTAT TO REMAIN.
 - EXISTING RETURN AIR DUCTWORK UP TO HV-1 AND RTU-101.
 - CONNECT TO EXISTING DUCT MAIN. EXISTING BRANCH DUCTS AND DIFFUSERS TO REMAIN.
 - PROVIDE OPENING IN BLOCK WALL WITH FIRE DAMPER FOR TRANSFER AIR 68"x18" MINIMUM OPENING.
 - PROVIDE OPENING IN BLOCK WALL WITH FIRE DAMPER FOR TRANSFER AIR 28"x14" MINIMUM OPENING.
 - RTU-103 ON ROOF. SUPPLY AIR DOWN THRU ROOF, RETURN AIR DOWN THRU ROOF DUCT LINED FULL SIZE OF OPENING WITH 90° ELBOW.
 - ALL EXISTING DIFFUSERS TO BE BALANCED DOWNSTREAM OF NEW VAV BOX.
 - CONTRACTOR TO PROVIDE OPENINGS AS REQUIRED IN BLOCK WALL. REFER TO STRUCTURAL DRAWINGS FOR LINTEL SCHEDULE.
 - CONTRACTOR RESPONSIBLE FOR REMOVAL OF EXISTING CEILING TO PERFORM WORK. REPLACE ALL DEVICES TO AS-IS CONDITION AT THE END OF THE INSTALLATION.





WAYNE STATE UNIVERSITY



OSBORN ENGINEERING
6001 Michigan Road | Brighton, MI 48021
313.975.4874 | www.osborn-eng.com

**MATTHAEI CENTER
ADDITION OF AIR
CONDITIONING
WAYNE STATE
UNIVERSITY**

DETROIT, MI 48208

TAG	ISSUED	DATE
TAG1	FOR BIDDING	08/08/22
TAG2	FOR RE-BIDDING	10/24/22
TAG3		
TAG4		
TAG5		
TAG6		
TAG7		
TAG8		
TAG9		
AG10		
AG11		
AG12		
AG13		
AG14		
AG15		
AG16		
AG17		
AG18		
AG19		
AG20		


Unless otherwise stated in Contract, The Osborn Engineering Company retains copyright ownership. Instruments of Service may only be used for the purpose described in the Contract. The Osborn Engineering Company may grant specific usage rights under license, and / or may transfer copyright ownership / assignment in writing. Reproduction, reuse or re-distribution of Instruments of Service is prohibited.

DRAWN BY: KAJ
CHECKED BY: DVL
CLIENT PROJ NO.:
OSBORN PROJ NO.: 20220270.000


**HVAC ENLARGED
NORTH WEST
FLOOR PLAN**

DRAWING NO.
M-303

P:\Wayne State University\2022\2020_000_Matthaei_HVAC_Study\Drawings\Mech\M-304 HVAC ENLARGED NORTH EAST FLOOR PLAN.dwg
10/24/2022 8:19 AM Johnson, Keith



1 HVAC ENLARGED NORTH EAST FLOOR PLAN
SCALE: 1/8" = 1'-0"



- GENERAL NOTES**
- THESE DRAWINGS ARE DIAGRAMMATIC AND INDICATE THE GENERAL EXTENT OF THE WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE COORDINATION AND PROPER INSTALLATION OF ALL MECHANICAL SYSTEMS. THE CONTRACTOR SHALL PROVIDE ALL NECESSARY OFFSETS AND FITTINGS WHICH MAY BE REQUIRED DUE TO SPACE CONSTRAINTS OR OTHER CONDITIONS.
 - THE CONTRACTOR SHALL PROVIDE ALL MISCELLANEOUS SUPPORTING STEEL, ETC. FOR THE PROPER INSTALLATION OF ALL MECHANICAL SYSTEMS.
 - THE CONTRACTOR SHALL COORDINATE FLOOR, WALL AND ROOF PENETRATIONS, ETC. WITH GENERAL TRADES.
 - THE CONTRACTOR SHALL VERIFY ALL CLEARANCES PRIOR TO FABRICATION OF ANY WORK.
 - THE CONTRACTOR SHALL COORDINATE THE LOCATION OF CEILING GRILLES, REGISTERS AND DIFFUSERS WITH THE ARCHITECTURAL REFLECTED CEILING PLANS.
 - DUCTWORK SHALL NOT BE LOCATED OVER THE TOP OF ANY ELECTRICAL PANELS OR EQUIPMENT.
 - THE CONTRACTOR SHALL COORDINATE AND PROVIDE ACCESS DOORS IN HARD CEILINGS FOR ALL EQUIPMENT WHICH REQUIRES ACCESS, SUCH AS FIRE AND SMOKE DAMPERS, SMOKE DETECTORS, BALANCING DAMPERS, VAV BOXES, ETC.
 - ALL MECHANICAL EQUIPMENT, PIPING, VALVES, DAMPERS, SMOKE DETECTORS ETC. WHICH REQUIRE ROUTINE MAINTENANCE OR INSPECTION SHALL BE INSTALLED WITHIN 2FT OF THE FINISHED CEILING HEIGHT.
 - CONTRACTOR SHALL ENSURE THAT ALL MATERIALS USED IN RETURN AIR PLENUMS ARE PLENUM-RATED.
 - DUCT SIZES ON THE DRAWINGS DESIGNATE THE FREE AREA DIMENSIONS. THE ACTUAL SHEET METAL SIZES SHALL BE INCREASED TO ACCOUNT FOR LINING WHERE REQUIRED. REFER TO DETAILS AND SPECIFICATIONS FOR LINING REQUIREMENTS.

- SHEET KEYNOTES**
- ALL EXISTING SUPPLY AND EXHAUST DUCT FROM HV-11 TO REMAIN.
 - EXISTING SUPPLY AIR DUCT UP TO HV-11 AND RTU-16.



MATTHAEI
CENTER
ADDITION OF AIR
CONDITIONING
WAYNE STATE
UNIVERSITY

DETROIT, MI 48208

TAG	ISSUED	DATE
TAG1	FOR BIDDING	08/08/22
TAG2	FOR RE-BIDDING	10/24/22
TAG3		
TAG4		
TAG5		
TAG6		
TAG7		
TAG8		
TAG9		
AG10		
AG11		
AG12		
AG13		
AG14		
AG15		
AG16		
AG17		
AG18		
AG19		
AG20		

Unless otherwise stated in Contract, The Osborn Engineering Company retains copyright ownership. Instruments of Service may only be used for the purpose described in the Contract. The Osborn Engineering Company may grant specific usage rights under license, and / or may transfer copyright ownership / assignment in writing. Reproduction, reuse or re-distribution of Instruments of Service is prohibited.


DRAWN BY KAJ
CHECKED BY DVL
CLIENT PROJ NO.
OSBORN PROJ NO. J20220270.000

HVAC ENLARGED
NORTH EAST
FLOOR PLAN

DRAWING NO.

M-304

KEY PLAN



DETROIT, MI 48208

AG	ISSUED	DATE
	FOR BIDDING	08/08/22
	FOR RE-BIDDING	10/24/22

Unless otherwise stated in Contract, The Osborn Engineering Company retains copyright ownership. Instruments of Service may only be used for the purpose described in the Contract. The Osborn Engineering Company may grant specific usage rights under license, and / or may transfer copyright ownership / assignment in writing. Reproduction, use or re-distribution of Instruments of Service is prohibited.

RAWN BY	KAJ
CHECKED BY	DVL
CLIENT PROJ NO.	-
SBORN PROJ NO.	J20220270.000

DRAWING NO.


1-306

GENERAL NOTES


1. THESE DRAWINGS ARE DIAGRAMMATIC AND INDICATE THE GENERAL EXTENT OF THE WORK. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER LOCATION AND SPACING OF THE INSTALLATION OF ALL MECHANICAL SYSTEMS. THE CONTRACTOR SHALL PROVIDE ALL NECESSARY OFFSETS AND FITTINGS WHICH MAY BE REQUIRED DUE TO SPACE CONSTRAINTS OR OTHER CONDITIONS.
2. THE CONTRACTOR SHALL PROVIDE ALL MISCELLANEOUS SUPPORTING STEEL, ETC., FOR THE PROPER INSTALLATION OF ALL MECHANICAL SYSTEMS.
3. THE CONTRACTOR SHALL COORDINATE FLOOR, WALL AND ROOF PENETRATIONS, ETC., WITH ALL GENERAL TRADES.
4. THE CONTRACTOR SHALL VERIFY ALL CLEARANCES PRIOR TO FABRICATION OF ANY WORK.
5. THE CONTRACTOR SHALL COORDINATE THE LOCATION OF CEILING GRILLES, REGISTERS AND DIFFUSERS WITH THE ARCHITECTURAL REFLECTED CEILING PLANS.
6. DUCTWORK SHALL NOT BE LOCATED OVER THE TOP OF ANY ELEVATOR PANELS OR STAIRWAYS.
7. THE CONTRACTOR SHALL COORDINATE AND PROVIDE ACCESS DOORS IN HARD CEILINGS FOR ALL EQUIPMENT WHICH REQUIRES ACCESS, SUCH AS FIRE AND SMOKE DAMPERS, SMOKE DETECTORS, BIRD AND INSECT SCREENS, ETC., ALL MECHANICAL EQUIPMENT, PIPING, VALVES, DAMPERS, SMOKE DETECTORS ETC. WHICH REQUIRE ROUTING.
8. ALL DUCTWORK OR EQUIPMENT SHALL BE INSTALLED WITHIN 2FT OF THE FINISHED CEILING HEIGHT.
9. CONTRACTOR SHALL ENSURE THAT ALL MATERIALS USED IN THE RETURN AIR SYSTEM ARE OF THE SPECIFIED DUCT SIZES ON THE DRAWINGS DESIGNATE THE FREE AREA DIMENSIONS. THE ACTUAL SHEET METAL SIZES SHALL BE INCREASED TO ACCOMMODATE THE LOSS OF FREE AREA. REFER TO DETAILS AND SPECIFICATIONS FOR LINING REQUIREMENTS.


SHEET KEYNOTES

1. ALL EXISTING SUPPLY AND EXHAUST DUCT FROM HV-12 TO REMAIN.
2. EXISTING SUPPLY AIR DUCT UP TO HV-12 AND RTU-107.
3. LOCATION OF NEW TEMPERATURE AND HUMIDITY SENSOR FOR DEDICATED OUTSIDE AIR UNIT.




1 HVAC ENLARGED SOUTH EAST FLOOR PLAN
SCALE: 1/8" = 1'-0"






ROOFTOP UNIT INSTALLATION DETAIL




1. ACCESS DOORS TO 16"x16" WHERE DUCT SIZE AND SPACES ALLOWS
2. FOUR CAM LATCHES ARE REQUIRED
3. DOORS TO BE INSTALLED ON SIDE OR BOTTOM OF DUCT WITH REST ACCESS

DUCT ACCESS DOOR AND SCHEDULE

NOT TO SCALE



TERMINAL BOX INSTALLATION AND CLEARANCE



MITERED ELBOW VANE



GAS EQUIPMENT CONNECTION



BRANCH CONNECTIONS

Unless otherwise stated in Contract, The Osborn Engineering Company retains copyright ownership. Instruments of Service may only be used for the purpose described in the Contract. The Osborn Engineering Company may grant specific usage rights under license, and / or may transfer copyright ownership / assignment in writing. Reproduction, e-use or re-distribution of Instruments of Service is prohibited.

GENERAL					SUPPLY FAN DATA							COOLING DATA										HEATING DATA							UNIT ELECTRICAL DATA			OPER WEIGHT (LBS)	MANUFACTURER / MODEL	NOTES
MARK	NOMINAL TONS	SERVES	EER	OA CFM	UNIT TYPE	QTY	TOTAL CFM	ESP. IN. W.G.	MOTOR HP	DISCHARGE POSITION	REFRIGERANT TYPE	OA DBWB °F	EAT DBWB °F	LAT DBWB °F	SENSIBLE MBH	TOTAL MBH	COMPRESSOR QTY	NO. OF STAGES	CONDENSER QTY OF FANS	BURNER TYPE	OAT °F DBWB	GAS			TEMP RISE °F	NO. OF STAGES	VOLT/PH	MCA	MCCP					
																						INPUT MBH	OUTPUT MBH	PRESSURE IN. W.C.										
RTU-101	10	HV-1	12.4	1,000	CONSTANT	1	3,750	1.5	8	DOWN	R410A	95 / 75	80 / 67	57.5 / 57.1	98.31	125.17	2	MODULATING	2	-	-	-	-	-	-	-	-	460 / 3	23.5	30	2171	DAIKIN DPS010A	1-10	
RTU-102	10	HV-2	12.4	1,000	CONSTANT	1	3,750	1.5	8	DOWN	R410A	95 / 75	80 / 67	57.5 / 57.1	98.31	125.17	2	MODULATING	2	-	-	-	-	-	-	-	-	460 / 3	23.5	30	2171	DAIKIN DPS010A	1-10	
RTU-103	15	AC-0802.3	11.1	1,500	VAV	1	6,000	2.00	8	DOWN	R410A	95/23.5	80/67	57.5 / 57.5	147.48	181.93	2	MODULATING	2	MODULATING	0	400	320	7-11	-	MODULATING	460 / 3	33.0	45	2334	DAIKIN DPS015A	1-10		
RTU-104	15	HV-9	11.1	1,500	CONSTANT	1	6,000	1.5	8	DOWN	R410A	95 / 75	80 / 67	57.5 / 57.5	147.48	181.93	2	MODULATING	2	-	-	-	-	-	-	-	-	460 / 3	33.0	45	2334	DAIKIN DPS015A	1-10	
RTU-105	50	HV-3.4.5.6	10.3	5,500	CONSTANT	1	20,000	1.0	15	DOWN	R410A	95 / 75	80 / 67	55.4 / 55.0	482.01	571.72	4	MODULATING	4	-	-	-	-	-	-	-	-	460 / 3	110.8	125	5800	DAIKIN MP5050F	1-10	
RTU-106	25	HV-11	11.3	5,500	DOAS	1	5,500	1.5	5	DOWN	R410A	95 / 75	95 / 75	56.956 / 5	219.3	318.2	2	MODULATING	2	-	=	-	-	-	-	-	-	460 / 3	58.3	80	4000	DAIKIN DPS025A	1-10,11	
RTU-107	25	HV-12	11.3	5,500	DOAS	1	5,500	1.5	5	DOWN	R410A	95 / 75	95 / 75	56.956 / 5	219.3	318.2	2	MODULATING	4	-	-	-	-	-	-	-	-	460 / 3	58.3	80	4000	DAIKIN DPS025A	1-10,11	
RTU-108	7.5	AC-8001	12.2	3000	CONSTANT	1	500	1.0	2	DOWN	R410A	95 / 75	80 / 67	59.8 / 57.6	66.9	90.0	2	2	2	MODULATING	0	200	160	7-11	MODULATING	460 / 3	20.8	25	1500	DAIKEN DRG09A	1-10			

1. PROVIDE UNIT WITH 100% COMPARATIVE DRYBULB ECONOMIZER, MAXIMUM TEMPERATURE OF 65 DEGREES F.
2. PROVIDE UNIT HAIL GUARD
3. PROVIDE ROOF CURB WITH 16" HEIGHT ABOVE ROOF.
4. FACTORY NON-FUSED DISCONNECT.
5. 2" MERV 8 PREFILTER.
6. CLOGGED FILTER SWITCH.
7. 115V GFI OUTLET.
8. DOUBLE WALL CONSTRUCTION.
9. BACNET CARD
10. PHASE FAILURE AND GROUND FAULT.
11. PROVIDE UNIT WITH HOT GAS REHEAT COIL.
12. PROVIDE FACTORY INSTALLED VFD

[illegible]

- | | |
|----------|---|
| REMARKS: | |
| 1. | BACNET DEVICE DCM601A71 |
| 2. | DCM601A71 INTELLIGENT TOUCH MANAGER, OR APPROVED EQUAL, COORDINATE LOCATION WITH OWNER. |
| 3. | MANUFACTURER MUST BE CERTIFIED, LISTED, AND LABELED PER AHRI 1230. |
| 4. | CONDENSING UNITS MUST HAVE FULLY MODULATING COMPRESSORS. |
| 5. | CONDENSING UNITS MUST HAVE AUTO CHANGEOVER FUNCTIONS. |
| 6. | EEV ACTUATORS MUST BE REMOVABLE FROM VALVE BODY WITHOUT DISTURBING THE REFRIGERANT SYSTEM. |
| 7. | MANUFACTURERS SUBMITTAL MUST INCLUDE REFRIGERANT PIPING DIAGRAM WITH PIPE DIAMETERS, LENGTHS, AND REFRIGERANT VOLUME. |
| 8. | REFNET BRANCH PIPING KIT. |
| 9. | VRF SYSTEM IS TO SUBMITTED AS DEDUCT ALTERNATE 1. |

MARK	GENERAL				COOLING DATA		HEATING DATA			ELECTRICAL DATA		OPER. WEIGHT (LB)	MANUFACTURER	MODEL	REMARKS	
	ASSOCIATED OUTDOOR UNIT	TYPE	FAN DATA		TOTAL CAPACITY (MBH)	SENSIBLE CAPACITY (MBH)	CAPACITY (MBH)	AUX. HEAT		V / PH / HZ	MCA (AMPS)					MOCP (AMPS)
			FLOW (CFM)	MAX ESP (”wg)				KW	MODEL							
AC-1	CU-101	WALL MOUNT	180	-	12.0	8.9	13.5	-	-	208 / 1 / 60	0.4	15	26	DAIKIN	FXAQ12PVJU	1, 2, 3.
AC-2	CU-101	WALL MOUNT	180	-	12.0	8.9	13.5	-	-	208 / 1 / 60	0.4	16	26	DAIKIN	FXAQ12PVJU	1, 2, 3, 4
AC-3	CU-101	WALL MOUNT	180	-	12.0	8.9	13.5	-	-	208 / 1 / 60	0.4	17	26	DAIKIN	FXAQ12PVJU	1, 2, 3, 4
AC-4	CU-101	WALL MOUNT	180	-	12.0	8.9	13.5	-	-	208 / 1 / 60	0.4	18	26	DAIKIN	FXAQ13PVJU	1, 2, 3, 4
AC-5	CU-101	WALL MOUNT	180	-	12.0	8.9	13.5	-	-	208 / 1 / 60	0.4	19	26	DAIKIN	FXAQ13PVJU	1, 2, 3, 4
AC-6	CU-101	WALL MOUNT	180	-	12.0	8.9	13.5	-	-	208 / 1 / 60	0.4	20	26	DAIKIN	FXAQ12PVJU	1, 2, 3, 4
AC-7	CU-101	WALL MOUNT	180	-	12.0	8.9	13.5	-	-	208 / 1 / 60	0.4	21	26	DAIKIN	FXAQ12PVJU	1, 2, 3, 4
AC-8	CU-101	WALL MOUNT	180	-	12.0	8.9	13.5	-	-	208 / 1 / 60	0.4	22	26	DAIKIN	FXAQ12PVJU	1, 2, 3, 4
AC-9	CU-101	WALL MOUNT	180	-	12.0	8.9	13.5	-	-	208 / 1 / 60	0.4	23	26	DAIKIN	FXAQ12PVJU	1, 2, 3, 4
AC-10	CU-101	WALL MOUNT	180	-	12.0	8.9	13.5	-	-	208 / 1 / 60	0.4	24	26	DAIKIN	FXAQ12PVJU	1, 2, 3, 4
AC-11	CU-101	WALL MOUNT	180	-	12.0	8.9	13.5	-	-	208 / 1 / 60	0.4	25	26	DAIKIN	FXAQ12PVJU	1, 2, 3, 4
AC-12	CU-101	WALL MOUNT	180	-	12.0	8.9	13.5	-	-	208 / 1 / 60	0.4	26	26	DAIKIN	FXAQ12PVJU	1, 2, 3, 4
AC-13	CU-101	WALL MOUNT	180	-	12.0	8.9	13.5	-	-	208 / 1 / 60	0.4	27	26	DAIKIN	FXAQ12PVJU	1, 2, 3, 4
AC-14	CU-101	WALL MOUNT	180	-	12.0	8.9	13.5	-	-	208 / 1 / 60	0.4	28	26	DAIKIN	FXAQ12PVJU	1, 2, 3, 4

- REMARKS:
1. UNITS REQUIRE SEPARATE POWER SUPPLY. THEY ARE NOT POWERED BY CU.
 2. DISCONNECT BY EC. PROVIDE WITH LONG LIFE FILTER AND BRC1E73 NAVIGATOR REMOTE CONTROL
 3. PROVIDE CONDENSATE PUMP EQUAL TO LITTLE GIAN VCMA-20U.S. 115 VOLT/60HZ, 1.5 AMPS, 20" SHUT-OFF HEAD, OVERFLOW DETECTION SWITCH
 4. MC TO PROVIDE 3/4" I.D. VINYL DISCHARGE TUBING ROUTED TO CONDENSATE DRAIN LINE-SEE PLAN.
 5. VRF SYSTEM IS TO SUBMITTED AS DEDUCT ALTERNATE 1.

MARK	SERVE	MAXIMUM COOLING CFM	HEATING CFM	MINIMUM CFM	INLET SIZE	ELECTRIC REHEAT COIL						UNIT SELECTION BASED ON:	NOTES:
						KW	EAT °F	LAT °F	V/PH/Hz	MCA	MOP		
VAV-1	OFFICE	1375	450	325	12	2	55	69.0	208/1/60	12.0	15	TITUS DESV	1, 2, 3, 4, 5
VAV-2	OFFICE	1025	300	230	10	2	55	71.0	208/3/60	5.2	15	TITUS DESV	1, 2, 3, 4, 5
VAV-3	FITNESS	3600	1400	1400	24X16	6	55	71.0	208/3/60	20.8	25	TITUS DESV	1, 2, 3, 4, 5
NOTES:													
1.	BOX SHALL BE SINGLE-DUCT AND PRESSURE-INDEPENDENT, WITH ELECTRIC REHEAT COIL. PROVIDE ROOM THERMOSTAT AND CONTROLS NECESSARY FOR COMMUNICATION WITH, AND CONTROL BY, NEW VERSAYS BUILDING AUTOMATION SYSTEM.												
2.	SELECTIONS BASED ON 1.00 IN. W.G. PRIMARY INLET STATIC PRESSURE, 0.25 IN. W.G. DOWNSTREAM STATIC PRESSURE.												
3.	COORDINATE LR HAND ORIENTATION WITH FINAL INSTALLATION CONDITIONS.												
4.	PROVIDE SCR CONTROL ON HEATING COIL. PROVIDE 24 V TRANSFORMER FOR CONTROLS.												
5.	PROVIDE DOOR INTERLOCK DISCONNECT SWITCH AND FUSE BLOCK. COORDINATE FUSING WITH ELECTRICAL CONTRACTOR.												

MARK	TYPE	FRAME TYPE	DAMPER TYPE	NOMINAL SIZE IN.	UNIT SELECTION BASED ON:	NOTES
CD-1	SUPPLY DIFFUSER	LAY-IN	NONE	24x24	PRICE SPD	1, 2, 3
DL-1	DRUM	SURFACE-MOUNT	NONE	SEE PLANS	PRICE HCD	5
RG-1	RETURN GRILLE	SURFACE-MOUNT	NONE	SEE PLANS	PRICE G30	3, 4
RG-2	RETURN GRILLE	SURFACE-MOUNT	NONE	SEE PLANS	PRICE G30	3, 4
NOTES:						
1.	DIFFUSERS SHALL BE WHITE WITH STEEL CONSTRUCTION. FACE SIZE IS 24x24, UNLESS OTHERWISE NOTED. SEE PLANS FOR NECK SIZE. BRANCH RUNOUT TO SAME SIZE AS DIFFUSER CONNECTOR, UNLESS OTHERWISE NOTED.					
2.	GRILLES TO BE WHITE WITH STEEL BORDER AND CORE. SEE PLANS FOR DUCT CONNECTION AND DUCT BRANCH SIZE.					
3.	FRAME TYPE TO BE COMPATIBLE WITH CEILING TYPE, WHERE APPLICABLE.					
4.	GRILLES TO BE WHITE WITH ALUMINUM BORDER AND CORE. SEE PLANS FOR DUCT CONNECTION AND DUCT BRANCH SIZE.					
5.	PROVIDE WITH SPIRAL DUCT FRAME, STANDARD WHITE FINISH.					

MARK	REFERENCE DRAWING	SERVICE	TYPE	CFM	ESP. IN W.G.	MOTOR DATA			UNIT SELECTION BASED ON:	NOTES
						DRIVE	MIN. MOTOR HP	VOLTAGE/PH		
RF-10	M-1.1	HV-10	MIXED FLOW	9400	1.8	BELT	5	480-3	GREENHECK-QEI-24	1
NOTES:										
1. PROVIDE DISCONNECT										


C

CHECKED FOR EXISTING EMBEDDED CONDUITS AND WIRE. IF ANY EXISTING CONDUITS OR WIRING ARE DAMAGED BY THIS CONTRACTOR IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAKE ALL REPAIRS TO CONDUITS, WIRE, FLOORS AND BUILDING FINISHES IN KIND AT NO COST TO OWNER.

27. PROVIDE UL LISTED FIRE STOP ASSEMBLY AT ALL NEW AND EXISTING PENETRATIONS IN FIRE RATED STRUCTURES.

28. ALL 120 VOLT, SINGLE PHASE 15 AND 20 AMPERE RECEPTACLE OUTLETS USED BY THE WORKMEN SHALL BE PROTECTED BY A "GROUND FAULT INTERRUPTER".

Unless otherwise stated in Contract, The Osborn Engineering Company retains copyright ownership. Instruments of Service may only be used for the purpose described in the Contract. The Osborn Engineering Company may grant specific usage rights under license, and / or may transfer copyright ownership / assignment in writing. Reproduction, re-use or re-distribution of Instruments of Service is prohibited.



MATTHAEI
CENTER
ADDITION OF AIR
CONDITIONING
WAYNE STATE
UNIVERSITY

DETROIT, MI 48208

TAG	ISSUED	DATE
FOR BIDDING		08/08/22
FOR RE-BIDDING		10/24/22


Unless otherwise stated in Contract, The Osborn Engineering Company retains copyright ownership. Instruments of Service may only be used for the purpose described in the Contract. The Osborn Engineering Company may grant specific usage rights under license, and / or may transfer copyright ownership / assignment in writing. Reproduction, reuse or re-distribution of Instruments of Service is prohibited.

DRAWN BY BTf
CHECKED BY JRB
CLIENT PROJ NO.
OSBORN PROJ NO. J20220270.000

ELECTRICAL
FIRST FLOOR
PLAN

DRAWING NO.

E-101



KEY NOTES


- REFER TO EQUIPMENT ELECTRICAL CONNECTION SCHEDULE ON SHEET E-701 FOR ADDITIONAL INFORMATION.
- VRF SYSTEM IS TO BE SUBMITTED AS DEDUCT ALTERNATE 1.

POWER SHEET GENERAL NOTES

- EXACT LOCATION OF MECHANICAL, PLUMBING, KITCHEN, FURNITURE SYSTEMS, OWNER FURNISHED EQUIPMENT, ETC. THAT REQUIRE ELECTRICAL CONNECTIONS ARE SHOWN ON THEIR RESPECTIVE DISCIPLINE DRAWINGS. COORDINATE EXACT LOCATIONS WITH RESPECTIVE CONTRACTORS AND/OR VENDORS PRIOR TO ANY ROUGH-INS.
- REVIEW AND COORDINATE WITH ALL TRADES' CONTRACT DOCUMENTS AND CONTRACTORS TO DETERMINE SPECIFIC MOUNTING LOCATIONS FOR EQUIPMENT WITH ELECTRICAL CONNECTIONS. COORDINATE EXACT MOUNTING LOCATIONS WITH THE SPECIFIC TRADE.
- MINIMUM CONDUCTOR SIZE FOR 277 VOLT BRANCH CIRCUITING SHALL BE #12AWG. FOR 277 VOLT BRANCH CIRCUITS WITH HOMERUNS OVER 125 LINEAR FEET A MINIMUM CONDUCTOR SIZE OF #10AWG SHALL BE PROVIDED FROM FIRST JUNCTION BOX TO BRANCH CIRCUIT PANELBOARD. ASSOCIATED EQUIPMENT GROUNDING CONDUCTOR SHALL ALSO BE INCREASED PER N.E.C. ARTICLE 250.122(B) REQUIREMENTS.
- MINIMUM CONDUCTOR SIZE FOR 120 VOLT BRANCH CIRCUITS SHALL BE #12AWG. FOR 120 VOLT BRANCH CIRCUITS WITH HOMERUNS OVER 75 LINEAR FEET, A MINIMUM WIRE SIZE OF #10AWG SHALL BE PROVIDED FROM FIRST JUNCTION BOX TO BRANCH CIRCUIT PANELBOARD. FOR 120 VOLT BRANCH CIRCUITS WITH HOMERUN OVER 150 LINEAR FEET, A MINIMUM WIRE SIZE OF #8AWG SHALL BE PROVIDED FROM FIRST JUNCTION BOX TO BRANCH CIRCUIT PANELBOARD. ASSOCIATED EQUIPMENT GROUNDING CONDUCTOR SHALL ALSO BE INCREASED PER N.E.C. ARTICLE 250.122(B) REQUIREMENTS.
- AT A MINIMUM ALL BRANCH CIRCUITS SHALL CONTAIN (2)#12AWG. (1)#12 EG. IN 3/4" CONDUIT UNLESS OTHERWISE INDICATED.
- ALL BRANCH CIRCUITS SHALL BE RUN WITH AN INDIVIDUAL NEUTRAL WIRE. BRANCH CIRCUITS SHALL NOT SHARE NEUTRAL WIRES.
- RECEPTACLE BRANCH CIRCUITS MAY SHARE EQUIPMENT GROUND CONDUCTORS.
- ALL CONDUCTORS SHALL BE IDENTIFIED BY PANELBOARD AND CIRCUIT NUMBERS IN ALL CABINETS, JUNCTION BOXES, WIRING TROUGHS, ENCLOSURES, SPLICE OR TERMINATION POINTS, ETC.
- A NEW TYPED PANELBOARD DIRECTORY CARD SHALL BE PROVIDED FOR ALL PANELS INSTALLED OR MODIFIED UNDER THIS CONTRACT. NEW DIRECTORY CARDS SHALL BE LOCATED ON THE INSIDE DOOR OF ASSOCIATED PANELS.



TROY, MI 48068



A horizontal scale bar with markings at 0, 4, 8, 16, and 32 feet. The segments between 0 and 4, 4 and 8, and 8 and 16 are white, while the segments between 16 and 32 and the final segment to 32 are black.

9. A NEW TYPED PANELBOARD DIRECTORY CARD SHALL BE PROVIDED FOR ALL PANELS INSTALLED OR MODIFIED UNDER THIS CONTRACT. NEW DIRECTORY CARDS SHALL BE LOCATED ON THE INSIDE DOOR OF ASSOCIATED PANELS.

Unless otherwise stated in Contract, The Osborn Engineering Company retains copyright ownership. Instruments of Service may only be used for the purpose described in the Contract. The Osborn Engineering Company may grant specific usage rights under license, and / or may transfer copyright ownership / assignment in writing. Reproduction, use or re-distribution of Instruments of Service is prohibited.

RAWN BY	BTF
CHECKED BY	JRB
CLIENT PROJ NO.	-
SBORN PROJ NO.	J20220270.000

DRAWING NO.

E-102



MATTHAEI
CENTER
ADDITION OF AIR
CONDITIONING
WAYNE STATE
UNIVERSITY

DETROIT, MI 48208

TAG	ISSUED	DATE
FOR BIDDING	08/08/22	
FOR RE-BIDDING	10/24/22	

Unless otherwise stated in Contract, The Osborn Engineering Company retains copyright ownership. Instruments of Service may only be used for the purpose described in the Contract. The Osborn Engineering Company may grant specific usage rights under license, and / or may transfer copyright ownership / assignment in writing. Reproduction, reuse or re-distribution of Instruments of Service is prohibited.


DRAWN BY BTJ
CHECKED BY JR8
CLIENT PROJ NO. 1
OSBORN PROJ NO. J20220270.000

ELECTRICAL
ROOF PLAN

DRAWING NO.

E-103

1 ELECTRICAL ROOF PLAN
SCALE: 1/16" = 1'-0"



KEY NOTES

1. REFER TO EQUIPMENT ELECTRICAL CONNECTION SCHEDULE ON SHEET E-701 FOR ADDITIONAL INFORMATION.
2. DISCONNECT CONDUIT AND WIRE TO EXISTING RTU AND RECONNECT TO NEW RTU. COORDINATE WITH MECHANICAL TRADES.
3. DISCONNECT AND REMOVE EXISTING AC UNIT AND FAN COIL UNIT BELOW AND ALL ASSOCIATED CONDUIT AND WIRING BACK TO SOURCE.
4. DISCONNECT AND REMOVE EXISTING RTU AND ALL ASSOCIATED CONDUIT AND WIRING BACK TO SOURCE.


POWER SHEET GENERAL NOTES

1. EXACT LOCATION OF MECHANICAL, PLUMBING, KITCHEN, FURNITURE SYSTEMS, OWNER FURNISHED EQUIPMENT, ETC. THAT REQUIRE ELECTRICAL CONNECTIONS ARE SHOWN ON THEIR RESPECTIVE DISCIPLINE DRAWINGS. COORDINATE EXACT LOCATIONS WITH RESPECTIVE CONTRACTORS AND/OR VENDORS PRIOR TO ANY ROUGH-INS.
2. REVIEW AND COORDINATE WITH ALL TRADES' CONTRACT DOCUMENTS AND CONTRACTORS TO DETERMINE SPECIFIC MOUNTING LOCATIONS FOR EQUIPMENT WITH ELECTRICAL CONNECTIONS. COORDINATE EXACT MOUNTING LOCATIONS WITH THE SPECIFIC TRADE.
3. MINIMUM CONDUCTOR SIZE FOR 277 VOLT BRANCH CIRCUITING SHALL BE #12AWG. FOR 277 VOLT BRANCH CIRCUITS WITH HOMERUNS OVER 125 LINEAR FEET A MINIMUM CONDUCTOR SIZE OF #10AWG SHALL BE PROVIDED FROM FIRST JUNCTION BOX TO BRANCH CIRCUIT PANELBOARD. ASSOCIATED EQUIPMENT GROUNDING CONDUCTOR SHALL ALSO BE INCREASED PER N.E.C. ARTICLE 250.122(B) REQUIREMENTS.
4. MINIMUM CONDUCTOR SIZE FOR 120 VOLT BRANCH CIRCUITS SHALL BE #12AWG. FOR 120 VOLT BRANCH CIRCUITS WITH HOMERUNS OVER 75 LINEAR FEET, A MINIMUM WIRE SIZE OF #10AWG SHALL BE PROVIDED FROM FIRST JUNCTION BOX TO BRANCH CIRCUIT PANELBOARD. FOR 120 VOLT BRANCH CIRCUITS WITH HOMERUN OVER 150 LINEAR FEET, A MINIMUM WIRE SIZE OF #8AWG SHALL BE PROVIDED FROM FIRST JUNCTION BOX TO BRANCH CIRCUIT PANELBOARD. ASSOCIATED EQUIPMENT GROUNDING CONDUCTOR SHALL ALSO BE INCREASED PER N.E.C. ARTICLE 250.122(B) REQUIREMENTS.
5. AT A MINIMUM ALL BRANCH CIRCUITS SHALL CONTAIN (2)#12AWG, (1)#12 EG, IN 3/4" CONDUIT UNLESS OTHERWISE INDICATED.
6. ALL BRANCH CIRCUITS SHALL BE RUN WITH AN INDIVIDUAL NEUTRAL WIRE. BRANCH CIRCUITS SHALL NOT SHARE NEUTRAL WIRES.
7. RECEPTACLE BRANCH CIRCUITS MAY SHARE EQUIPMENT GROUND CONDUCTORS.
8. ALL CONDUCTORS SHALL BE IDENTIFIED BY PANELBOARD AND CIRCUIT NUMBER(S) IN ALL CABINETS, JUNCTION BOXES, WIRING TROUGHS, ENCLOSURES, SPLICE OR TERMINATION POINTS, ETC.
9. A NEW TYPED PANELBOARD DIRECTORY CARD SHALL BE PROVIDED FOR ALL PANELS INSTALLED OR MODIFIED UNDER THIS CONTRACT. NEW DIRECTORY CARDS SHALL BE LOCATED ON THE INSIDE DOOR OF ASSOCIATED PANELS.



ETROIT, MI 48208

SCALE: 1/4" = 1'-0"



1. DISCONNECT AND REMOVE ALL EXISTING ELECTRICAL DEVICES IN THIS ROOM. MEDIUM VOLTAGE TRANSFORMER, BUS DUCT, PLD LOOP, INCLUDING ALL ASSOCIATED SUPPORTS AND WIRING.
2. DISCONNECT AND REMOVE ALL LIGHTING IN THIS ROOM INCLUDING ASSOCIATED SWITCHES. EXISTING CIRCUIT TO REMAIN.
3. NEW 1x4 VAPOR TIGHT FROSTED POLYCARBONATE LENS SUSPENDED MOUNTED LED STRIP LIGHT, LITHONIA CATALOG NUMBER CVST 14 5000LM MVOLT 40K 80CRI. CONNECT TO EXISTING LIGHTING CIRCUIT.
4. PROVIDE 4" CONCRETE PAD.

1. EXACT LOCATION OF MECHANICAL, PLUMBING, KITCHEN, FURNITURE SYSTEMS, OWNER FURNISHED EQUIPMENT, ETC. THAT REQUIRE ELECTRICAL CONNECTIONS ARE SHOWN ON THEIR RESPECTIVE DISCREET DRAWINGS. COORDINATE ELECTRICAL LOCATIONS WITH RESPECTIVE CONTRACTORS AND VENDORS PRIOR TO ANY ROUGH-INS.
2. REVIEW AND COORDINATE WITH ALL TRADES' CONTRACT DOCUMENTS AND CONTRACTORS TO DETERMINE SPECIFIC MOUNTING LOCATIONS FOR EQUIPMENT WITH ELECTRICAL CONNECTIONS. COORDINATE ELECTRICAL MOUNTING LOCATIONS WITH THE SPECIFIC TRADE.
3. MINIMUM CONDUCTOR SIZE FOR 277 VOLT BRANCH CIRCUITS SHALL BE #12AWG. FOR 277 VOLT BRANCH CIRCUITS WITH HOMERUNS OVER 125 LINEAR FEET A MINIMUM CONDUCTOR SIZE OF #10AWG SHALL BE PROVIDED FROM FIRST JUNCTION BOX TO BRANCH CIRCUIT PANELBOARD. ASSOCIATED EQUIPMENT GROUNDING CONDUCTOR SHALL BE AS TO BE INCREASED PER N.E.C. ARTICLE 250.122(B) REQUIREMENTS.
4. MINIMUM CONDUCTOR SIZE FOR 120 VOLT BRANCH CIRCUITS SHALL BE #12AWG. FOR 120 VOLT BRANCH CIRCUITS WITH HOMERUNS OVER 75 LINEAR FEET, A MINIMUM WIRE SIZE OF #10AWG SHALL BE PROVIDED FROM FIRST JUNCTION BOX TO BRANCH CIRCUIT PANELBOARD. ASSOCIATED EQUIPMENT GROUNDING CONDUCTOR SHALL BE AS TO BE INCREASED PER N.E.C. ARTICLE 250.122(B) REQUIREMENTS.
5. AT A MINIMUM ALL BRANCH CIRCUITS SHALL CONTAIN 2#12AWG, (1912 EGT, IN 3/4" CONDUIT UNLESS OTHERWISE INDICATED.
6. ALL BRANCH CIRCUITS SHALL BE RUN WITH AN INDIVIDUAL NEUTRAL WIRE. BRANCH CIRCUITS SHALL NOT SHARE NEUTRAL WIRES.
7. RECEPTACLE BRANCH CIRCUITS MAY SHARE EQUIPMENT GROUND CONDUCTORS.
8. ALL CONDUCTORS SHALL BE IDENTIFIED BY PANELBOARD AND CIRCUIT NUMBER(S) IN ALL CABINETS, JUNCTION BOXES, WIRING TRAYS, ENCLOSURES, SPLICE OR TERMINATION POINTS, ETC.
9. A NEW TYPED PANELBOARD DIRECTORY CARD SHALL BE PROVIDED FOR ALL PANELS INSTALLED OR MODIFIED UNDER THIS CONTRACT. THE DIRECTORY CARD SHALL BE LOCATED ON THE INSIDE DOOR OF ASSOCIATED PANELS.

[illegible]

Unless otherwise stated in Contract, The Osborn Engineering Company retains copyright ownership. Instruments of Service may only be used for the purpose described in the Contract. The Osborn Engineering Company may grant specific usage rights under license, and / or may transfer copyright ownership / assignment in writing. Reproduction, use or re-distribution of Instruments of Service is prohibited.

DRAWN BY	BTF
CHECKED BY	JRB
CLIENT PROJ NO.	-
OSBORN PROJ NO.	J20220270.000

ELECTRICAL
ENLARGED
FLOOR PLAN

DRAWING NO.

E-401

MFR		SQUARE D		PANEL ID:		LP-ACN		LOCATION		MECH RM NORTH			
TYPE								MOUNTING		SURFACE			
BUS		COPPER		SERVICE:		L-L 208		L-N 120		DWG. NO.			
NOTES	CIRCUIT DESCRIPTION	LOAD AMPS	BREAKER POLE TRIP	A	B	C	KILOVOLT-AMPS A	B	C	BREAKER POLE TRIP	LOAD AMPS	DESCRIPTION	NOTES
	AC-1,2,3,4	1.6	2 20	0.17	1	2	0.12	3	4	0.12	2 20	1.2	AC-9,10,11
		1.6	-	-	0.17	3	4	0.12	-	-	-	1.2	-
	AC-1,2,3,4 PUMPS	6.0	1 20		0.72	5	6		0.72	1 20	6.0	AC-9,10,11 PUMPS	
	RTU RECEPITS	6.0	1 20	0.72	7	8	0.14			0.72	1 20	0.2	BS-1
	BAS PANELS	3.0	1 20		0.36	9	10	0.50		3 20	4.2	VAV-102	
	VAV-101	9.6	2 20		1.00	11	12		0.50	-	-	4.2	-
		9.6	-	1.00	13	14	0.50		-	-	-	4.2	-
	SPARE	0.0	1 20	0.00	15	16		2.00		2 20	16.7	VAV-103	
	SPARE	0.0	1 20	0.00	17	18		2.00		2.00	-	16.7	-
	SPARE	0.0	1 20	0.00	19	20		2.00		-	-	16.7	-
	SPARE	0.0	1 20		0.00	21	22	0.00		1 20	0.0	SPARE	
	SPARE	0.0	1 20		0.00	23	24		0.00	1 20	0.0	SPARE	
	SPARE	0.0	1 20	0.00	25	26	0.00		0.00	1 20	0.0	SPARE	
	SPARE	0.0	1 20		0.00	27	28	0.00		1 20	0.0	SPARE	
	SPARE	0.0	1 20		0.00	29	30		0.00	1 20	0.0	SPARE	
	SPACE	0.0	1 20	0.00	31	32	0.00		0.00	1 20	0.0	SPACE	
	SPACE	0.0	1 20		0.00	33	34		0.00	1 20	0.0	SPACE	
	SPACE	0.0	1 20		0.00	35	36		0.00	1 20	0.0	SPACE	
	SPACE	0.0	1 20	0.00	37	38	0.00		0.00	1 20	0.0	SPACE	
	SPACE	0.0	1 20		0.00	39	40		0.00	1 20	0.0	SPACE	
	SPACE	0.0	1 20		0.00	41	42		0.00	1 20	0.0	SPACE	
TOTAL:		AMPS	KVA	MAIN BREAKER				100A		BUS RATING		100A	
BUS A		38.8	4.650	CONDUIT SIZE				1 1/4"		A.I.C. SYM.		10,000	
BUS B		26.3	3.150	FEEDER SIZE				1		Total Connected Load		35.4 A 12.740 KVA	
BUS C		41.2	4.940	SOURCE				PP-CAN		Estimated Demand Load		35.4 A 12.740 KVA	
NOTES:							ADDITIONAL REQUIREMENTS:						

MFR		SQUARE D		PANEL ID:		LP-ACS		LOCATION		MECH RM SOUTH			
TYPE				SERVICE:		L-L 208		MOUNTING		SURFACE			
BUS		COPPER				L-N 120		DWG. NO.					
NOTES	CIRCUIT DESCRIPTION	LOAD AMPS	BREAKER POLE TRIP	A	B	C	KILOVOLT-AMPS A	B	C	BREAKER POLE TRIP	LOAD AMPS	DESCRIPTION	NOTES
	AC-5,6,7,8	1.6	2	20	0.17		1	2	0.12	2	20	1.2	AC-12,13,14
		1.6	-	-	0.17		3	4	0.12	-	-	1.2	-
	AC-5,6,7,8 PUMPS	6.0	1	20			5	6		0.72	1	20	6.0
	RTU RECEPITS	4.5	1	20	0.54		7	8	0.00		1	20	0.0
	BAS PANELS	3.0	1	20		0.36	9	10	0.00		1	20	0.0
	SPARE	0.0	1	20		0.00	11	12		0.00	1	20	0.0
	SPARE	0.0	1	20	0.00		13	14	0.00		1	20	0.0
	SPARE	0.0	1	20		0.00	15	16		0.00	1	20	0.0
	SPARE	0.0	1	20		0.00	17	18		0.00	1	20	0.0
	SPARE	0.0	1	20	0.00		19	20	0.00		1	20	0.0
	SPARE	0.0	1	20		0.00	21	22	0.00		1	20	0.0
	SPARE	0.0	1	20			23	24		0.00	1	20	0.0
	SPARE	0.0	1	20	0.00		25	26	0.00		1	20	0.0
	SPARE	0.0	1	20		0.00	27	28		0.00	1	20	0.0
	SPARE	0.0	1	20		0.00	29	30		0.00	1	20	0.0
	SPACE	0.0	1	20	0.00		31	32	0.00		1	20	0.0
	SPACE	0.0	1	20		0.00	33	34		0.00	1	20	0.0
	SPACE	0.0	1	20		0.00	35	36		0.00	1	20	0.0
	SPACE	0.0	1	20	0.00		37	38	0.00		1	20	0.0
	SPACE	0.0	1	20		0.00	39	40		0.00	1	20	0.0
	SPACE	0.0	1	20		0.00	41	42		0.00	1	20	0.0
TOTAL:		AMPS					MAIN BREAKER		100A		BUS RATING		100A
BUS A		6.9					CONDUIT SIZE		1 1/4"		A.I.C. SYM.		10,000
BUS B		5.4					FEEDER SIZE		1		Total Connected Load		8.1 A 2.920 KVA
BUS C		12.0					SOURCE		PP-ACS		Estimated Demand Load		8.1 A 2.920 KVA
NOTES:							ADDITIONAL REQUIREMENTS:						

EQUIPMENT ELECTRICAL CONNECTION SCHEDULE									
EQUIPMENT DESIGNATION	EQUIPMENT DESCRIPTION	MOTOR / EQUIPMENT				BRANCH CIRCUIT			REMARKS
		HP	KVA	VOLTAGE	PHASE	LOCATION	OCPD SIZE	CONDUCTORS / CONDUIT	
RTU-101	ROOF TOP UNIT	-	19.5 KVA	480V	3Ø	ROOF	30A	3Ø10, 1#10 EG - 3/4"C.	FACTORY NON-FUSED DISCONNECT, 115V GFI OUTLET
RTU-102	ROOF TOP UNIT	-	19.5 KVA	480V	3Ø	ROOF	30A	3Ø10, 1#10 EG - 3/4"C.	FACTORY NON-FUSED DISCONNECT, 115V GFI OUTLET
RTU-103	ROOF TOP UNIT	-	27.4 KVA	480V	3Ø	ROOF	45A	3Ø8, 1#10 EG - 3/4"C.	FACTORY NON-FUSED DISCONNECT, 115V GFI OUTLET
RTU-104	ROOF TOP UNIT	-	27.4 KVA	480V	3Ø	ROOF	45A	3Ø8, 1#10 EG - 3/4"C.	FACTORY NON-FUSED DISCONNECT, 115V GFI OUTLET
RTU-105	ROOF TOP UNIT	-	92 KVA	480V	3Ø	ROOF	150A	3Ø1, 1#6 EG - 1 1/2"C.	FACTORY NON-FUSED DISCONNECT, 115V GFI OUTLET
RTU-106	ROOF TOP UNIT	-	48.4 KVA	480V	3Ø	ROOF	100A	3Ø6, 1#10 EG - 3/4"C.	FACTORY NON-FUSED DISCONNECT, 115V GFI OUTLET
RTU-107	ROOF TOP UNIT	-	48.4 KVA	480V	3Ø	ROOF	80A	3Ø6, 1#10 EG - 3/4"C.	FACTORY NON-FUSED DISCONNECT, 115V GFI OUTLET
RTU-108	ROOF TOP UNIT	-	17.3kVA	480V	3Ø	ROOF	-	-	CONNECT NEW RTU TO EXISTING CIRCUIT.
CU-101	VRF OUTDOOR UNIT	-	30 KVA	480V	3Ø	ROOF	60A	3Ø8, 1#10 EG - 3/4"C.	DISCONNECT BY EC
AC-1	VRF INDOOR UNIT	-	0.144 KVA	208V	1Ø	FIRST FLOOR NORTH	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-2	VRF INDOOR UNIT	-	0.144 KVA	208V	1Ø	FIRST FLOOR NORTH	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-3	VRF INDOOR UNIT	-	0.144 KVA	208V	1Ø	FIRST FLOOR NORTH	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-4	VRF INDOOR UNIT	-	0.144 KVA	208V	1Ø	FIRST FLOOR NORTH	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-5	VRF INDOOR UNIT	-	0.144 KVA	208V	1Ø	FIRST FLOOR SOUTH	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-6	VRF INDOOR UNIT	-	0.144 KVA	208V	1Ø	FIRST FLOOR SOUTH	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-7	VRF INDOOR UNIT	-	0.144 KVA	208V	1Ø	FIRST FLOOR SOUTH	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-8	VRF INDOOR UNIT	-	0.144 KVA	208V	1Ø	FIRST FLOOR SOUTH	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-9	VRF INDOOR UNIT	-	0.144 KVA	208V	1Ø	FIRST FLOOR WEST	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-10	VRF INDOOR UNIT	-	0.144 KVA	208V	1Ø	FIRST FLOOR WEST	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-11	VRF INDOOR UNIT	-	0.144 KVA	208V	1Ø	FIRST FLOOR WEST	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-12	VRF INDOOR UNIT	-	0.144 KVA	208V	1Ø	FIRST FLOOR EAST	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-13	VRF INDOOR UNIT	-	0.144 KVA	208V	1Ø	FIRST FLOOR EAST	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-14	VRF INDOOR UNIT	-	0.144 KVA	208V	1Ø	FIRST FLOOR EAST	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-1 PUMP	VRF INDOOR UNIT PUMP	-	0.18 KVA	115V	1Ø	FIRST FLOOR NORTH	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-2 PUMP	VRF INDOOR UNIT PUMP	-	0.18 KVA	115V	1Ø	FIRST FLOOR NORTH	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-3 PUMP	VRF INDOOR UNIT PUMP	-	0.18 KVA	115V	1Ø	FIRST FLOOR NORTH	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-4 PUMP	VRF INDOOR UNIT PUMP	-	0.18 KVA	115V	1Ø	FIRST FLOOR NORTH	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-5 PUMP	VRF INDOOR UNIT PUMP	-	0.18 KVA	115V	1Ø	FIRST FLOOR SOUTH	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-6 PUMP	VRF INDOOR UNIT PUMP	-	0.18 KVA	115V	1Ø	FIRST FLOOR SOUTH	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-7 PUMP	VRF INDOOR UNIT PUMP	-	0.18 KVA	115V	1Ø	FIRST FLOOR SOUTH	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-8 PUMP	VRF INDOOR UNIT PUMP	-	0.18 KVA	115V	1Ø	FIRST FLOOR SOUTH	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-9 PUMP	VRF INDOOR UNIT PUMP	-	0.18 KVA	115V	1Ø	FIRST FLOOR WEST	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-10 PUMP	VRF INDOOR UNIT PUMP	-	0.18 KVA	115V	1Ø	FIRST FLOOR WEST	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-11 PUMP	VRF INDOOR UNIT PUMP	-	0.18 KVA	115V	1Ø	FIRST FLOOR WEST	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-12 PUMP	VRF INDOOR UNIT PUMP	-	0.18 KVA	115V	1Ø	FIRST FLOOR EAST	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-13 PUMP	VRF INDOOR UNIT PUMP	-	0.18 KVA	115V	1Ø	FIRST FLOOR EAST	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
AC-14 PUMP	VRF INDOOR UNIT PUMP	-	0.18 KVA	115V	1Ø	FIRST FLOOR EAST	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
BS-1	BRANCH SELECTOR BOX	-	0.14 KVA	208V	1Ø	FIRST FLOOR EAST	15A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY EC
VAV-101	SINGLE DUCT TERMINAL UNIT	-	2KW	208V	1Ø	FIRST FLOOR WEST	20A	2#12, 1#12 EG - 3/4"C.	DISCONNECT BY MFG
VAV-102	SINGLE DUCT TERMINAL UNIT	-	1.5KW	208V	3Ø	FIRST FLOOR WEST	20A	3#12, 1#10 EG - 3/4"C.	DISCONNECT BY MFG
VAV-103	SINGLE DUCT TERMINAL UNIT	-	6KW	208V	3Ø	FIRST FLOOR WEST	25A	3#10, 1#10 EG - 3/4"C.	DISCONNECT BY MFG



MATTHAEI
CENTER
ADDITION OF AIR
CONDITIONING
WAYNE STATE
UNIVERSITY

DETROIT, MI 48208

TAG	ISSUED	DATE
	FOR BIDDING	08/08/22
	FOR RE-BIDDING	10/24/22

Unless otherwise stated in Contract, The Osborn Engineering Company retains copyright ownership. Instruments of Service may only be used for the purpose described in the Contract. The Osborn Engineering Company may grant specific usage rights under license, and / or may transfer copyright ownership / assignment in writing. Reproduction, reuse or re-distribution of Instruments of Service is prohibited.

DRAWN BY BTB
CHECKED BY JRB
CLIENT PROJ NO.
OSBORN PROJ NO. J20220270.000

ELECTRICAL
SCHEDULES

DRAWING NO.
E-701